

# Autoconf, Automake, Libtool

---

Edition 1.4.3-unofficial, 2 February 2005  
\$Id: autobook.m4,v 1.2 2005/01/26 14:01:43 joostvb Exp \$

**Gary V. Vaughan**

**Ben Elliston**

[bje@redhat.com](mailto:bje@redhat.com)

**Tom Tromey**

[tromey@redhat.com](mailto:tromey@redhat.com)

**Ian Lance Taylor**

[ian@zembu.com](mailto:ian@zembu.com)

---

Copyright © 1999, 2000 Gary V. Vaughan, Ben Elliston, Tom Tromey, Ian Lance Taylor

Permission is granted to make and distribute verbatim copies of this manual provided the copyright notice and this permission notice are preserved on all copies.

Permission is granted to copy and distribute modified versions of this manual under the conditions for verbatim copying, provided that the entire resulting derived work is distributed under the terms of a permission notice identical to this one.

Permission is granted to copy and distribute translations of this manual into another language, under the above conditions for modified versions, except that this permission notice may be stated in a translation approved by the Authors.

# Foreword

## Preamble

This book is published on paper by New Riders (ISBN 1-57870-190-2), their webpage on the book is at <http://www.newriders.com/autoconf/>. Technical reviewers of the paper book were Akim Demaille, Phil Edwards, Bruce Korb, Alexandre Oliva, Didier Verna, Benjamin Koznik and Jason Molenda. The paper book includes Acknowledgements to: Richard Stallman and the FSF, Gord Matzigkeit, David Mackenzie, Akim Demaille, Phil Edwards, Bruce Korb, Alexandre Oliva, Didier Verna, Benjamin Koznik, Jason Molenda, the Gnits group, and the New Riders staff.

From the paper book, quoted from "About the Authors":

"Gary V. Vaughan spent three years as a Computer Systems Engineering undergraduate at the University of Warwick and then two years at Coventry University studying Computer Science. He has been employed as a professional C programmer in several industry sectors for the past seven years, but most recently as a scientist for the Defence Evaluation and Research Agency. Over the past 10 years or so, Gary has contributed to several free software projects, including AutoGen, Cygwin, Enlightenment, and GNU M4. He currently helps maintain GNU Libtool for the Free Software Foundation.

Ben Elliston works at Red Hat Inc., telecommuting from his home in Canberra, Australia. He develops instruction set simulators and adapts the GNU development tools to new microprocessors. He has worked with GNU tools for many years and is a past maintainer of GNU Autoconf. He has a bachelor's degree in Computer Engineering from the University of Canberra.

Tom Tromey works at Red Hat Inc., where he works on GCJ, the Java front end to the GNU Compiler Collection. Patches of his appear in GCC, emacs, Gnome, Autoconf, GDB, and probably other packages he has forgotten about. He is the primary author of GNU Automake.

Ian Lance Taylor is co-founder and CTO of Zembu Labs. Previously, he worked at Cygnus Solutions, where he designed and wrote features and ports for many free software programs, including the GNU Compiler Collection and the GNU binutils. He was the maintainer of the GNU binutils for several years. He is the author of GNU/Taylor UUCP. He was one of the first contributors to Autoconf, and has also made significant contributions to Automake and Libtool."

Until 2001-09-05, this package was maintained by Gary V. Vaughan, Tom Tromey, Ian Lance Taylor and Ben Elliston. It was (and is) available via anonymous CVS:

```
cvs -d :pserver:anoncvs@sources.redhat.com:/cvs/autobook login
Password is anoncvs
cvs -d :pserver:anoncvs@sources.redhat.com:/cvs/autobook co autobook
```

The sources there would build autobook-0.5a.tar.gz .

Furthermore, <http://sources.redhat.com/autobook/autobook-1.4.tar.gz>, a tarball containing html pages, is linked to from <http://sources.redhat.com/autobook/>.

I've made some changes to the sources I've found in the redhat.com CVS (see ChangeLog), and maintain the sources via CVS on topaz.conuropsis.org. I maintain a

webpage on <http://mdcc.cx/autobook/>, the package can be downloaded from there. It also has instructions on how to get informed about changes to the autobook package.

This package is not blessed by the maintainers of the official autobook-1.4.tar.gz. Therefore, I take responsibility for all errors you might find in this package. Of course, all credit should go to Vaughan, Tromey, Taylor and Elliston for their excellent work.

Beware! The Autobook is getting somewhat obsolete, I'm afraid: the text has not been updated (apart from minor corrections) since 2001-09. Autobook talks likely about autoconf version 2.13, automake version 1.4 and libtool version 1.3.5 (see Appendix A.2: Downloading GNU Autotools). As of January 2005, released are autoconf 2.59a, automake 1.9.4 and libtool 1.5.6. Therefore, regard the texinfo documentation shipped with these tools as the authoritative source of information.

See the unofficial Autobook webpage at <http://mdcc.cx/autobook/> for pointers to other sources of information on the GNU Autotools.

*Joost van Baal*  
*January 2005*

## Magic Happens Here

Do you remember the 1980s? Veteran users of free software on Unix could testify that though there were a lot of programs distributed as source code back then (over USENET), there was not a lot of consistency in how to compile and install it. The more complicated a package was, the more likely it was to have its own unique build procedure that had to be learned first. And there were no widely used approaches to portability problems. Each software author handled them in a different way, if they did at all.

Fast forward to the present. A de facto standard is in widespread use for solving those problems, and it's not just free software packages that are using it; some proprietary programs from the largest computer companies are built using this software. It even does Windows.

As it evolved in the 1990s it demonstrated the power of some good ideas: sharing expertise, automating repetitive work, and having consistency where it is helpful without sacrificing flexibility where it is helpful.

What is "it"? The GNU Autotools, a group of utilities developed in the 1990s for the GNU Project. The authors of this book and I were some of its principal developers, but it turned out to help solve many other peoples' problems as well, and many other people contributed to it. It is one of the many projects that developed by cooperation while making what is now often called GNU/Linux. The community made the GNU Autotools widespread, as people adopted it for their own programs and extended it where they found that was needed. The creation of Libtool is that type of contribution.

Autoconf, Automake, and Libtool were developed separately, to make tackling the problem of software configuration more manageable by partitioning it. But they were designed to be used as a system, and they make more sense when you have documentation for the whole system. This book stands a level above the software packages, giving the expertise

of its authors in using this whole system to its fullest. It was written by people who have lived closest to the problems and their solutions in software.

Magic happens under the hood, where experts have tinkered until the GNU Autotools engine can run on everything from jet fuel to whale oil. But there is a different kind of magic, in the cooperation and sharing that built a widely used system over the Internet, for anyone to use and improve. Now, as the authors share their knowledge and experience, you are part of the community, too. Perhaps its spirit will inspire you to make your own contributions.

*David MacKenzie*  
*Germantown, Maryland*  
*June 2000*



## Part I





# 1 Introduction

Autoconf, Automake and Libtool are packages for making your software more portable and to simplify building it—usually on someone else’s system. Software portability and effective build systems are crucial aspects of modern software engineering practice. It is unlikely that a software project would be started today with the expectation that the software would run on only one platform. Hardware constraints may change the choice of platform, new customers with different kinds of systems may emerge or your vendor might introduce incompatible changes in newer versions of their operating system. In addition, tools that make building software easier and less error prone are valuable.

Autoconf is a tool that makes your packages more portable by performing tests to discover system characteristics before the package is compiled. Your source code can then adapt to these differences.

Automake is a tool for generating ‘Makefile’s—descriptions of what to build—that conform to a number of standards. Automake substantially simplifies the process of describing the organization of a package and performs additional functions such as dependency tracking between source files.

Libtool is a command line interface to the compiler and linker that makes it easy to portably generate static and shared libraries, regardless of the platform it is running on.

## 1.1 What this book is

This book is a tutorial for Autoconf, Automake and Libtool, hereafter referred to as the GNU Autotools. The GNU manuals that accompany each tools adequately document each tool in isolation. Until now, there has not been a guide that has described how these tools work *together*.

As these tools have evolved over the years, design decisions have been made by contributors who clearly understand the associated problems, but little documentation exists that captures why things are the way they are. By way of example, one might wonder why some Autoconf macros use shell constructs like:

```
if test "x$var" = xbar; then
  echo yes 1>&5
fi
```

instead of the simpler:

```
if [ $var = bar ]; then
  echo yes 1>&5
fi
```

Much of this reasoning is recorded in this book.

## 1.2 What the book is not

This book is not a definitive reference to Autoconf, Automake or Libtool. Attempting to do so would fill this book with information that is doomed to obsolescence. For instance, you will not find a description of every predefined macro provided by Autoconf. Instead, the book will attempt to help you understand any macro you encounter and, instead, influence

how you approach software portability and package building. The GNU manual for each tool should be consulted as a reference.

This book briefly introduces pertinent concepts, but does not attempt to teach them comprehensively. You will find an introduction to writing ‘`Makefile`’s and Bourne shell scripts, but you should consult other references to become familiar with these broader topics.

### 1.3 Who should read this book

Revealing the mystery around the GNU Autotools is likely to raise the interest of a wide audience of software developers, system administrators and technical managers.

Software developers, especially those involved with free software projects, will find it valuable to understand how to use these tools. The GNU Autotools are enjoying growing popularity in the free software community. Developers of in-house projects can reap the same benefits by using these tools.

System administrators can benefit from a working knowledge of these tools – a common task for system administrators is to compile and install packages which commonly use the GNU Autotools framework. Occasionally, a feature test may produce a false result, leading to a compilation error or a misbehaving program. Some hacking is usually sufficient to get the package to compile, but knowing the correct way to fix the problem can assist the package maintainer.

Finally, technical managers may find the discussion to be an insight into the complex nature of software portability and the process of building a large project.

### 1.4 How this book is organized

Like any good tutorial, this book starts with an explanation of simple concepts and builds on these fundamentals to progress to advanced topics.

Part I of the book provides a history of the development of these tools and why they exist.

Part II contains most of the book’s content, starting with an introduction to concepts such as ‘`Makefile`’s and configuration triplets. Later chapters introduce each tool and how to manage projects of varying sizes using the tools in concert. Programs written in C and C++ can be non-portable if written carelessly. Chapters 14 and 15 offer guidelines for writing portable programs in C and C++, respectively.

Part III provides information that you are unlikely to find in any other documentation, that is based on extensive experience with the tools. It embodies chapters that treat some advanced, yet essential, concepts such as the `m4` macro processor and how to write portable Bourne shell scripts. Chapter 23 outlines how to migrate an existing package to the GNU Autotools framework and will be of interest to many developers. One of the most mystifying aspects of using the GNU Autotools for building packages in a cross-compilation environment. This is de-mystified in Chapter 25.

## 2 History

In this chapter we provide a brief history of the tools described in this book. You don't need to know this history in order to use the tools. However, the history of how the tools developed over time helps explain why the tools act the way that they do today. Also, in a book like this, it's only fair for us to credit the original authors and sources of inspiration, and to explain what they did.

### 2.1 The Diversity of Unix Systems

Of the programs discussed in this book, the first to be developed was Autoconf. Its development was determined by the history of the Unix operating system.

The first version of Unix was written by Dennis Ritchie and Ken Thompson at Bell Labs in 1969. During the 1970s, Bell Labs was not permitted to sell Unix commercially, but did distribute Unix to universities at relatively low cost. The University of California at Berkeley added their own improvements to the Unix sources; the result was known as the BSD version of Unix.

In the early 1980s, AT&T signed an agreement permitting them to sell Unix commercially. The first AT&T version of Unix was known as System III.

As the popularity of Unix increased during the 1980s, several other companies modified the Unix sources to create their own variants. Examples include SunOS from Sun Microsystems, Ultrix from Digital Equipment Corporation, and HP-UX from Hewlett Packard.

Although all of the Unix variants were fundamentally similar, there were various differences between them. They had slightly different sets of header files and slightly different lists of functions in the system libraries, as well as more significant differences in areas such as terminal handling and job control.

The emerging POSIX standards helped to eliminate some of these differences. However, in some areas POSIX introduced new features, leading to more variants. Also, different systems adopted the POSIX standard at different times, leading to further disparities.

All of these variations caused problems for programs distributed as source code. Even a function as straightforward as `memcpy` was not available everywhere; the BSD system library provided the similar function `bcopy` instead, but the order of arguments was reversed.

Program authors who wanted their programs to run on a wide variety of Unix variants had to be familiar with the detailed differences between the variants. They also had to worry about the ways in which the variants changed from one version to another, as variants on the one hand converged on the POSIX standard and on the other continued to introduce new and different features.

While it was generally possible to use `#ifdef` to identify particular systems and versions, it became increasingly difficult to know which versions had which features. It became clear that some more organized approach was needed to handle the differences between Unix variants.

## 2.2 The First Configure Programs

By 1992, four different systems had been developed to help with source code portability:

- The Metaconfig program, by Larry Wall, Harlan Stenn, and Raphael Manfredi.
- The Cygnus ‘**configure**’ script, by K. Richard Pixley, and the original GCC ‘**configure**’ script, by Richard Stallman. These are quite similar, and the developers communicated regularly. GCC is the GNU Compiler Collection, formerly the GNU C compiler.
- The GNU Autoconf package, by David MacKenzie.
- Imake, part of the X Window system.

These systems all split building a program into two steps: a configuration step, and a build step. For all the systems, the build step used the standard Unix **make** program. The **make** program reads a set of rules in a ‘**Makefile**’, and uses them to build a program. The configuration step would generate ‘**Makefile**’s, and perhaps other files, which would then be used during the build step.

Metaconfig and Autoconf both use feature tests to determine the capabilities of the system. They use Bourne shell scripts (all variants of Unix support the Bourne shell in one form or another) to run various tests to see what the system can support.

The Cygnus ‘**configure**’ script and the original GCC ‘**configure**’ script are also Bourne shell scripts. They rely on little configuration files for each system variant, both header files and ‘**Makefile**’ fragments. In early versions, the user compiling the program had to tell the script which type of system the program should be built for; they were later enhanced with a shell script written by Per Bothner which determines the system type based on the standard Unix **uname** program and other information.

Imake is a portable C program. Imake can be customized for a particular system, and run as part of building a package. However, it is more normally distributed with a package, including all the configuration information needed for supported systems.

Metaconfig and Autoconf are programs used by program authors. They produce a shell script which is distributed with the program’s source code. A user who wants to build the program runs the shell script in order to configure the source code for the particular system on which it is to be built.

The Cygnus and GCC ‘**configure**’ scripts, and **imake**, do not have this clear distinction between use by the developer and use by the user.

The Cygnus and GCC ‘**configure**’ scripts included features to support cross development, both to support building a cross-compiler which compiles code to be run on another system, and to support building a program using a cross-compiler.

Autoconf, Metaconfig and Imake did not have these features (they were later added to Autoconf); they only worked for building a program on the system on which it was to run.

The scripts generated by Metaconfig are interactive by default: they ask questions of the user as they go along. This permits them to determine certain characteristics of the system which it is difficult or impossible to test, such as the behavior of **setuid** programs.

The Cygnus and GCC ‘**configure**’ scripts, and the scripts generated by **autoconf**, and the **imake** program, are not interactive: they determine everything themselves. When using Autoconf, the package developer normally writes the script to accept command line options for features which can not be tested for, or sometimes requires the user to edit a header file after the ‘**configure**’ script has run.

## 2.3 Configure Development

The Cygnus `'configure'` script and the original GCC `'configure'` script both had to be updated for each new Unix variant they supported. This meant that packages which used them were continually out of date as new Unix variants appeared. It was not hard for the developer to add support for a new system variant; however, it was not something which package users could easily do themselves.

The same was true of Imake as it was commonly used. While it was possible for a user to build and configure Imake for a particular system, it was not commonly done. In practice, packages such as the X window system which use Imake are shipped with configuration information detailed for specific Unix variants.

Because Metaconfig and Autoconf used feature tests, the scripts they generated were often able to work correctly on new Unix variants without modification. This made them more flexible and easier to work with over time, and led to the wide adoption of Autoconf.

In 1994, David MacKenzie extended Autoconf to incorporate the features of the Cygnus `'configure'` script and the original GCC `'configure'` script. This included support for using system specified header file and makefile fragments, and support for cross-compilation.

GCC has since been converted to use Autoconf, eliminating the GCC `'configure'` script. Most programs which use the Cygnus `'configure'` script have also been converted, and no new programs are being written to use the Cygnus `'configure'` script.

The `metaconfig` program is still used today to configure Perl and a few other programs. `imake` is still used to configure the X window system. However, these tools are not generally used for new packages.

## 2.4 Automake Development

By 1994, Autoconf was a solid framework for handling the differences between Unix variants. However, program developers still had to write large `'Makefile.in'` files in order to use it. The `'configure'` script generated by `autoconf` would transform the `'Makefile.in'` file into a `'Makefile'` used by the `make` program.

A `'Makefile.in'` file has to describe how to build the program. In the Imake equivalent of a `'Makefile.in'`, known as an `'Imakefile'`, it is only necessary to describe which source files are used to build the program. When Imake generates a `'Makefile'`, it adds the rules for how to build the program itself. Later versions of the BSD `make` program also include rules for building a program.

Since most programs are built in much the same way, there was a great deal of duplication in `'Makefile.in'` files. Also, the GNU project developed a reasonably complex set of standards for `'Makefile's'`, and it was easy to get some of the details wrong.

These factors led to the development of Automake. `automake`, like `autoconf`, is a program run by a developer. The developer writes files named `'Makefile.am'`; these use a simpler syntax than ordinary `'Makefile's'`. `automake` reads the `'Makefile.am'` files and produces `'Makefile.in'` files. The idea is that a script generated by `autoconf` converts these `'Makefile.in'` files into `'Makefile's'`.

As with Imake and BSD `make`, the `'Makefile.am'` file need only describe the files used to build a program. `automake` automatically adds the necessary rules when it generates the `'Makefile.in'` file. `automake` also adds any rules required by the GNU `'Makefile'` standards.

The first version of Automake was written by David MacKenzie in 1994. It was completely rewritten in 1995 by Tom Tromey.

## 2.5 Libtool Development

Over time, Unix systems added support for shared libraries.

Conventional libraries, or static libraries, are linked into a program image. This means that each program which uses a static library includes some or all of the library in the program binary on disk.

Shared libraries, on the other hand, are a separate file. A program which uses a shared library does not include a copy of the library; it only includes the name of the library. Many programs can use a single shared library.

Using a shared library reduces disk space requirements. Since the system can generally share a single executable instance of the shared library among many programs, it also reduces swap space requirements at run time. Another advantage is that it is possible to fix a bug by updating the single shared library file on disk, without requiring all the programs which use the library to be rebuilt.

The first Unix shared library implementation was in System V release 3 from AT&T. The idea was rapidly adopted by other Unix vendors, appearing in SunOS, HP-UX, AIX, and Digital Unix among others. Unfortunately, each implementation differed in the creation and use of shared libraries and in the specific features which were supported.

Naturally, packages distributed as source code which included libraries wanted to be able to build their own shared libraries. Several different implementations were written in the Autoconf/Automake framework.

In 1996, Gordon Matzigkeit began work on a package known as Libtool. Libtool is a collection of shell scripts which handle the differences between shared library generation and use on different systems. It is closely tied to Automake, although it is possible to use it independently.

Over time, Libtool has been enhanced to support more Unix variants and to provide an interface for standardizing shared library features.

## 2.6 Microsoft Windows

In 1995, Microsoft released Windows 95, which soon became the most widely-used operating system in the world. Autoconf and Libtool were written to support portability across Unix variants, but they provided a framework to support portability to Windows as well. This made it possible for a program to support both Unix and Windows from a single source code base.

The key requirement of both Autoconf and Libtool was the Unix shell. The GNU bash shell was ported to Windows as part of the Cygwin project, which was originally written by Steve Chamberlain. The Cygwin project implements the basic Unix API in Windows, making it possible to port Unix programs directly.

Once the shell and the Unix `make` program (also provided by Cygwin) were available, it was possible to make Autoconf and Libtool support Windows directly, using either the Cygwin interface or the Visual C++ tools from Microsoft. This involved handling details

like the different file extensions used by the different systems, as well as yet another set of shared library features. This first version of this work was by Ian Lance Taylor in 1998. Automake has also been ported to Windows. It requires Perl to be installed (see [Section A.1 \[Prerequisite tools\]](#), page 303).





## Part II



## 3 How to run configure and make

A package constructed using Autoconf will come with a ‘`configure`’ script. A user who wants to build and install the package must run this script in order to prepare their source tree in order to build it on their particular system. The actual build process is performed using the `make` program.

The ‘`configure`’ script tests system features. For example, it might test whether the C library defines the `time_t` data type for use by the `time()` C library function. The ‘`configure`’ script then makes the results of those tests available to the program while it is being built.

This chapter explains how to invoke a ‘`configure`’ script from the perspective of a user—someone who just wants to take your package and compile it on their system with a minimum of fuss. It is because Autoconf works as well as it does that it is usually possible to build a package on any kind of machine with a simple `configure; make` command line. The topics covered in this chapter include how to invoke `configure`, the files that `configure` generates and the most useful ‘`Makefile`’ targets—actions that you want `make` to perform—that will be available when compiling the package (see [Chapter 4 \[Introducing Makefiles\]](#), [page 25](#)).

### 3.1 Configuring

A ‘`configure`’ script takes a large number of command line options. The set of options can vary from one package to the next, although a number of basic options are always present. The available options can be discovered by running ‘`configure`’ with the ‘`--help`’ option. Although many of these options are esoteric, it’s worthwhile knowing of their existence when configuring packages with special installation requirements. Each option will be briefly described below:

‘`--cache-file=file`’

‘`configure`’ runs tests on your system to determine the availability of features (or bugs!). The results of these tests can be stored in a *cache file* to speed up subsequent invocations of `configure`. The presence of a well primed cache file makes a big improvement when configuring a complex tree which has ‘`configure`’ scripts in each subtree.

‘`--help`’ Outputs a help message. Even experienced users of ‘`configure`’ need to use ‘`--help`’ occasionally, as complex projects will include additional options for per-project configuration. For example, ‘`configure`’ in the GCC package allows you to control whether the GNU assembler will be built and used by GCC in preference to a vendor’s assembler.

‘`--no-create`’

One of the primary functions of ‘`configure`’ is to generate output files. This option prevents ‘`configure`’ from generating such output files. You can think of this as a kind of *dry run*, although the cache will still be modified.

`--quiet`  
`--silent`

As `configure` runs its tests, it outputs brief messages telling the user what the script is doing. This was done because `configure` can be slow. If there was no such output, the user would be left wondering what is happening. By using this option, you too can be left wondering!

`--version`

Prints the version of Autoconf that was used to generate the `configure` script.

`--prefix=prefix`

The `--prefix` option is one of the most frequently used. If generated `Makefile`'s choose to observe the argument you pass with this option, it is possible to entirely relocate the architecture-independent portion of a package when it is installed. For example, when installing a package like Emacs, the following command line will cause the Emacs Lisp files to be installed in `/opt/gnu/share`:

```
$ ./configure --prefix=/opt/gnu
```

It is important to stress that this behavior is dependent on the generated files making use of this information. For developers writing these files, Automake simplifies this process a great deal. Automake is introduced in [Chapter 7 \[Introducing GNU Automake\]](#), page 41.

`--exec-prefix=eprefix`

Similar to `--prefix`, except that it sets the location of installed files which are architecture-dependent. The compiled `emacs` binary is such a file. If this option is not given, the default `exec-prefix` value inserted into generated files is set to the same values at the `prefix`.

`--bindir=dir`

Specifies the location of installed binary files. While there may be other generated files which are binary in nature, binary files here are defined to be programs that are run directly by users.

`--sbindir=dir`

Specifies the location of installed superuser binary files. These are programs which are usually only run by the superuser.

`--libexecdir=dir`

Specifies the location of installed executable support files. Contrasted with 'binary files', these files are never run directly by users, but may be executed by the binary files mentioned above.

`--datadir=dir`

Specifies the location of generic data files.

`--sysconfdir=dir`

Specifies the location of read-only data used on a single machine.

`--sharedstatedir=dir`

Specifies the location of data which may be modified, and which may be shared across several machines.

- `--localstatedir=dir`  
 Specifies the location of data which may be modified, but which is specific to a single machine.
- `--libdir=dir`  
 Specifies where object code library should be installed.
- `--includedir=dir`  
 Specifies where C header files should be installed. Header files for other languages such as C++ may be installed here also.
- `--oldincludedir=dir`  
 Specifies where C header files should be installed for compilers other than GCC.
- `--infodir=dir`  
 Specifies where Info format documentation files should be installed. Info is the documentation format used by the GNU project.
- `--mandir=dir`  
 Specifies where manual pages should be installed.
- `--srcdir=dir`  
 This option does not affect installation. Instead, it tells `'configure'` where the source files may be found. It is normally not necessary to specify this, since the configure script is normally in the same directory as the source files.
- `--program-prefix=prefix`  
 Specifies a prefix which should be added to the name of a program when installing it. For example, using `'--program-prefix=g'` when configuring a program normally named `'tar'` will cause the installed program to be named `'gtar'` instead. As with the other installation options, this `'configure'` option only works if it is utilized by the `'Makefile.in'` file.
- `--program-suffix=suffix`  
 Specifies a suffix which should be appended to the name of a program when installing it.
- `--program-transform-name=program`  
 Here, *program* is a `sed` script. When a program is installed, its name will be run through `'sed -e script'` to produce the installed name.
- `--build=build`  
 Specifies the type of system on which the package will be built. If not specified, the default will be the same configuration name as the host.
- `--host=host`  
 Specifies the type of system on which the package will run—or *be hosted*. If not specified, the host triplet is determined by executing `'config.guess'`.
- `--target=target`  
 Specifies the type of system which the package is to be targeted to. This makes the most sense in the context of programming language tools like compilers and assemblers. If not specified, the default will be the same configuration name as the host.

**'--disable-feature'**

Some packages may choose to provide compile-time configurability for large-scale options such as using the Kerberos authentication system or an experimental compiler optimization pass. If the default is to provide such features, they may be disabled with **'--disable-feature'**, where *feature* is the feature's designated name. For example:

```
$ ./configure --disable-gui
```

**'--enable-feature[=arg]'**

Conversely, some packages may provide features which are disabled by default. To enable them, use **'--enable-feature'**, where *feature* is the feature's designated name. A feature may accept an optional argument. For example:

```
$ ./configure --enable-buffers=128
```

Using **'--enable-feature=no'** is synonymous with **'--disable-feature'**, described above.

**'--with-package[=arg]'**

In the free software community, there is a healthy tendency to reuse existing packages and libraries where possible. At the time when a source tree is configured by **'configure'**, it is possible to provide hints about other installed packages. For example, the BLT widget toolkit relies on Tcl and Tk. To configure BLT, it may be necessary to give **'configure'** some hints about where you have installed Tcl and Tk:

```
$ ./configure --with-tcl=/usr/local --with-tk=/usr/local
```

Using **'--with-package=no'** is synonymous with **'--without-package'** which is described below.

**'--without-package'**

Sometimes you may not want your package to inter-operate with some pre-existing package installed on your system. For example, you might not want your new compiler to use GNU ld. You can prevent this by using an option such as:

```
$ ./configure --without-gnu-ld
```

**'--x-includes=dir'**

This option is really a specific instance of a **'--with-package'** option. At the time when Autoconf was initially being developed, it was common to use **'configure'** to build programs to run on the X Window System as an alternative to Imake. The **'--x-includes'** option provides a way to guide the configure script to the directory containing the X11 header files.

**'--x-libraries=dir'**

Similarly, the **--x-libraries** option provides a way to guide **'configure'** to the directory containing the X11 libraries.

It is unnecessary, and often undesirable, to run **'configure'** from within the source tree. Instead, a well-written **'Makefile'** generated by **'configure'** will be able to build packages whose source files reside in another tree. The advantages of building derived files in a separate tree to the source code are fairly obvious: the derived files, such as object files,

would clutter the source tree. This would also make it impossible to build those same object files on a different system or with a different configuration. Instead, it is recommended to use three trees: a source tree, a build tree and an *install tree*. Here is a closing example of how to build the GNU malloc package in this way:

```
$ gtar zxf mmalloc-1.0.tar.gz
$ mkdir build && cd build
$ ../mmalloc-1.0/configure
creating cache ./config.cache
checking for gcc... gcc
checking whether the C compiler (gcc ) works... yes
checking whether the C compiler (gcc ) is a cross-compiler... no
checking whether we are using GNU C... yes
checking whether gcc accepts -g... yes
checking for a BSD compatible install... /usr/bin/install -c
checking host system type... i586-pc-linux-gnu
checking build system type... i586-pc-linux-gnu
checking for ar... ar
checking for ranlib... ranlib
checking how to run the C preprocessor... gcc -E
checking for unistd.h... yes
checking for getpagesize... yes
checking for working mmap... yes
checking for limits.h... yes
checking for stddef.h... yes
updating cache ../config.cache
creating ./config.status
```

Now that this build tree is configured, it is possible to go on and build the package and install it into the default location of `/usr/local`:

```
$ make all && make install
```

## 3.2 Files generated by configure

After you have invoked `configure`, you will discover a number of generated files in your build tree. The build directory structure created by `configure` and the number of files will vary from package to package. Each of the generated files are described below and their relationships are shown in [Appendix C \[Generated File Dependencies\]](#), page 313:

### `config.cache`

`configure` can cache the results of system tests that have been performed to speed up subsequent tests. This file contains the cache data and is a plain text file that can be hand-modified or removed if desired.

### `config.log`

As `configure` runs, it outputs a message describing each test it performs and the result of each test. There is substantially more output produced by the shell and utilities that `configure` invokes, but it is hidden from the user to keep the output understandable. The output is instead redirected to `config.log`. This file is the first place to look when `configure` goes hay-wire or a test produces

a nonsense result. A common scenario is that `'configure'`, when run on a Solaris system, will tell you that it was unable to find a working C compiler. An examination of `'config.log'` will show that Solaris' default `'/usr/ucb/cc'` is a program that informs the user that the optional C compiler is not installed.

#### `'config.status'`

`'configure'` generates a shell script called `'config.status'` that may be used to recreate the current configuration. That is, all generated files will be regenerated. This script can also be used to re-run `'configure'` if the `'--recheck'` option is given.

#### `'config.h'`

Many packages that use `'configure'` are written in C or C++. Some of the tests that `'configure'` runs involve examining variability in the C and C++ programming languages and implementations thereof. So that source code can programmatically deal with these differences, `#define` preprocessor directives can be optionally placed in a *config header*, usually called `'config.h'`, as `'configure'` runs. Source files may then include the `'config.h'` file and act accordingly:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif /* HAVE_CONFIG_H */

#if HAVE_UNISTD_H
# include <unistd.h>
#endif /* HAVE_UNISTD_H */
```

We recommend always using a config header.

#### `'Makefile'`

One of the common functions of `'configure'` is to generate `'Makefile's` and other files. As it has been stressed, a `'Makefile'` is just a file often generated by `'configure'` from a corresponding input file (usually called `'Makefile.in'`). The following section will describe how you can use `make` to process this `'Makefile'`. There are other cases where generating files in this way can be helpful. For instance, a Java developer might wish to make use of a `'defs.java'` file generated from `'defs.java.in'`.

### 3.3 The most useful Makefile targets

By now `'configure'` has generated the output files such as a `'Makefile'`. Most projects include a `'Makefile'` with a basic set of well-known *targets* (see [Section 4.1 \[Targets and dependencies\]](#), page 25). A target is a name of a task that you want `make` to perform – usually it is to build all of the programs belonging to your package (commonly known as the *all* target). From your build directory, the following commands are likely to work for a configured package:

`make all` Builds all derived files sufficient to declare the package built.

`make check`

Runs any self-tests that the package may have.



**make install**

Installs the package in a predetermined location.

**make clean**

Removes all derived files.

There are other less commonly used targets which are likely to be recognized, particularly if the package includes a **‘Makefile’** which conforms to the GNU **‘Makefile’** standard or is generated by **automake**. You may wish to inspect the generated **‘Makefile’** to see what other targets have been included.

### 3.4 Configuration Names

The GNU Autotools name all types of computer systems using a *configuration name*. This is a name for the system in a standardized format.

Some example configuration names are **‘sparc-sun-solaris2.7’**, **‘i386-pc-linux-gnu’**, or **‘i386-pc-cygwin’**.

All configuration names used to have three parts, and in some documentation they are still called *configuration triplets*. A three part configuration name is *cpu-manufacturer-operating\_system*. Currently configuration names are permitted to have four parts on systems which distinguish the kernel and the operating system, such as GNU/Linux. In these cases, the configuration name is *cpu-manufacturer-kernel-operating\_system*.

When using a configuration name in an option to a tool such as **configure**, it is normally not necessary to specify an entire name. In particular, the middle field (*manufacturer*, described below) is often omitted, leading to strings such as **‘i386-linux’** or **‘sparc-sunos’**. The shell script **‘config.sub’** is used to translate these shortened strings into the canonical form.

On most Unix variants, the shell script **‘config.guess’** will print the correct configuration name for the system it is run on. It does this by running the standard **‘uname’** program, and by examining other characteristics of the system. On some systems, **‘config.guess’** requires a working C compiler or an assembler.

Because **‘config.guess’** can normally determine the configuration name for a machine, it is only necessary for a user or developer to specify a configuration name in unusual cases, such as when building a cross-compiler.

Here is a description of each field in a configuration name:

*cpu*           The type of processor used on the system. This is typically something like **‘i386’** or **‘sparc’**. More specific variants are used as well, such as **‘mipsel’** to indicate a little endian MIPS processor.

*manufacturer*

A somewhat freeform field which indicates the manufacturer of the system. This is often simply **‘unknown’**. Other common strings are **‘pc’** for an IBM PC compatible system, or the name of a workstation vendor, such as **‘sun’**.

*operating\_system*

The name of the operating system which is run on the system. This will be something like **‘solaris2.5’** or **‘winnt4.0’**. There is no particular restriction on the version number, and strings like **‘aix4.1.4.0’** are seen.

Configuration names may be used to describe all sorts of systems, including embedded systems which do not run any operating system. In this case, the field is normally used to indicate the object file format, such as ‘elf’ or ‘coff’.

*kernel* This is used mainly for GNU/Linux systems. A typical GNU/Linux configuration name is ‘i586-pc-linux-gnulibc1’. In this case the kernel, ‘linux’, is separated from the operating system, ‘gnulibc1’.

‘configure’ allows fine control over the format of binary files. It is not necessary to build a package for a given kind of machine on that machine natively—instead, a cross-compiler can be used. Moreover, if the package you are trying to build is itself capable of operating in a cross configuration, then the build system need not be the same kind of machine used to host the cross-configured package once the package is built! Consider some examples:

Compiling a simple package for a GNU/Linux system.

*host = build = target = ‘i586-pc-linux-gnu’*

Cross-compiling a package on a GNU/Linux system that is intended to

run on an IBM AIX machine: *build = ‘i586-pc-linux-gnu’, host = target = ‘rs6000-ibm-aix3.2’*

Building a Solaris-hosted MIPS-ECOFF cross-compiler on a GNU/Linux

system. *build = ‘i586-pc-linux-gnu’, host = ‘sparc-sun-solaris2.4’, target = ‘mips-idt-ecoff’*

## 4 Introducing ‘Makefile’s

A ‘Makefile’ is a specification of dependencies between files and how to resolve those dependencies such that an overall goal, known as a *target*, can be reached. ‘Makefile’s are processed by the `make` utility. Other references describe the syntax of ‘Makefile’s and the various implementations of `make` in detail. This chapter provides an overview into ‘Makefile’s and gives just enough information to write custom rules in a ‘Makefile.am’ (see [Chapter 7 \[Introducing GNU Automake\], page 41](#)) or ‘Makefile.in’.

### 4.1 Targets and dependencies

The `make` program attempts to bring a target up to date by bring all of the target’s dependencies up to date. These dependencies may have further dependencies. Thus, a potentially complex dependency graph forms when processing a typical ‘Makefile’. From a simple ‘Makefile’ that looks like this:


```
all: foo

foo: foo.o bar.o baz.o

.c.o:
    $(CC) $(CFLAGS) -c $< -o $@

.l.c:
    $(LEX) $< && mv lex.yy.c $@
```

We can draw a dependency graph that looks like this:



Unless the ‘Makefile’ contains a directive to `make`, all targets are assumed to be filename and rules must be written to create these files or somehow bring them up to date.

When leaf nodes are found in the dependency graph, the ‘Makefile’ must include a set of shell commands to bring the dependent up to date with the dependency. Much to the chagrin of many `make` users, *up to date* means the dependent has a more recent timestamp than the target. Moreover, each of these shell commands are run in their own sub-shell and, unless the ‘Makefile’ instructs `make` otherwise, each command must exit with an exit code of 0 to indicate success.

Target rules can be written which are executed unconditionally. This is achieved by specifying that the target has no dependents. A simple rule which should be familiar to most users is:

```
clean:
-rm *.o core
```

## 4.2 Makefile syntax

‘Makefile’s have a rather particular syntax that can trouble new users. There are many implementations of **make**, some of which provide non-portable extensions. An abridged description of the syntax follows which, for portability, may be stricter than you may be used to.

Comments start with a ‘#’ and continue until the end of line. They may appear anywhere except in command sequences—if they do, they will be interpreted by the shell running the command. The following ‘Makefile’ shows three individual targets with dependencies on each:

```
target1:  dep1 dep2 ... depN
<tab>    cmd1
<tab>    cmd2
<tab>    ...
<tab>    cmdN

target2:  dep4 dep5
<tab>    cmd1
<tab>    cmd2

dep4 dep5:
<tab>    cmd1
```

Target rules start at the beginning of a line and are followed by a colon. Following the colon is a whitespace separated list of dependencies. A series of lines follow which contain shell commands to be run by a sub-shell (the default is the Bourne shell). Each of these lines *must* be prefixed by a horizontal tab character. This is the most common mistake made by new **make** users.

These commands may be prefixed by an ‘@’ character to prevent **make** from echoing the command line prior to executing it. They may also optionally be prefixed by a ‘-’ character to allow the rule to continue if the command returns a non-zero exit code. The combination of both characters is permitted.

## 4.3 Macros

A number of useful macros exist which may be used anywhere throughout the ‘Makefile’. Macros start with a dollar sign, like shell variables. Our first ‘Makefile’ used a few:

```
$(CC) $(CFLAGS) -c $< -o $@
```

Here, syntactic forms of ‘\$(...)’ are **make** variable expansions. It is possible to define a **make** variable using a ‘var=value’ syntax:

```
CC = ec++
```

In a ‘Makefile’, `$(CC)` will then be literally replaced by ‘ec++’. **make** has a number of built-in variables and default values. The default value for ‘\$(CC)’ is **cc**.

Other built-in macros exist with fixed semantics. The two most common macros are `$$` and `$(1)`. They represent the names of the target and the first dependency for the rule in which they appear. `$$` is available in any rule, but for some versions of `make` `$(1)` is only available in suffix rules. Here is a simple ‘Makefile’:

```
all:    dummy
@echo "$$ depends on dummy"

dummy:
touch $$
```

This is what `make` outputs when processing this ‘Makefile’:

```
$ make
touch dummy
all depends on dummy
```

The GNU Make manual documents these macros in more detail.

## 4.4 Suffix rules

To simplify a ‘Makefile’, there is a special kind of rule syntax known as a *suffix rule*. This is a wildcard pattern that can match targets. Our first ‘Makefile’ used some. Here is one:

```
.c.o:
$(CC) $(CFLAGS) -c $(1) -o $$
```

Unless a more specific rule matches the target being sought, this rule will match any target that ends in ‘.o’. These files are said to always be dependent on ‘.c’. With some background material now presented, let’s take a look at these tools in use.



## 5 A Minimal GNU Autotools Project

This chapter describes how to manage a minimal project using the GNU Autotools. A minimal project is defined to be the smallest possible project that can still illustrate a sufficient number of principles in using the tools. By studying a smaller project, it becomes easier to understand the more complex interactions between these tools when larger projects require advanced features.

The example project used throughout this chapter is a fictitious command interpreter called `foonly`. `foonly` is written in C, but like many interpreters, uses a lexical analyzer and a parser expressed using the `lex` and `yacc` tools. The package will be developed to adhere to the GNU ‘`Makefile`’ standard, which is the default behavior for Automake.

There are many features of the GNU Autotools that this small project will not utilize. The most noteworthy one is libraries; this package does not produce any libraries of its own, so Libtool will not feature in this chapter. The more complex projects presented in [Chapter 9 \[A Small GNU Autotools Project\]](#), [page 51](#) and [Chapter 12 \[A Large GNU Autotools Project\]](#), [page 123](#) will illustrate how Libtool participates in the build system. The purpose of this chapter will be to provide a high-level overview of the user-written files and how they interact.

### 5.1 User-Provided Input Files

The smallest project requires the user to provide only two files. The remainder of the files needed to build the package are generated by the GNU Autotools (see [Section 5.2 \[Generated Output Files\]](#), [page 30](#)).

- ‘`Makefile.am`’ is an input to `automake`.
- ‘`configure.in`’ is an input to `autoconf`.

I like to think of ‘`Makefile.am`’ as a high-level, bare-bones specification of a project’s build requirements: what needs to be built, and where does it go when it is installed? This is probably Automake’s greatest strength—the description is about as simple as it could possibly be, yet the final product is a ‘`Makefile`’ with an array of convenient `make` targets.

The ‘`configure.in`’ is a template of macro invocations and shell code fragments that are used by `autoconf` to produce a ‘`configure`’ script (see [Appendix C \[Generated File Dependencies\]](#), [page 313](#)). `autoconf` copies the contents of ‘`configure.in`’ to ‘`configure`’, expanding macros as they occur in the input. Other text is copied verbatim.

Let’s take a look at the contents of the user-provided input files that are relevant to this minimal project. Here is the ‘`Makefile.am`’:

```
## Makefile.am -- Process this file with automake to produce Makefile.in
bin_PROGRAMS = foonly
foonly_SOURCES = main.c foo.c foo.h nly.c scanner.l parser.y
foonly_LDADD = @LEXLIB@
```

This ‘`Makefile.am`’ specifies that we want a program called ‘`foonly`’ to be built and installed in the ‘`bin`’ directory when `make install` is run. The source files that are used to build ‘`foonly`’ are the C source files ‘`main.c`’, ‘`foo.c`’, ‘`nly.c`’ and ‘`foo.h`’, the `lex` program in ‘`scanner.l`’ and a `yacc` grammar in ‘`parser.y`’. This points out a particularly

nice aspect about Automake: because `lex` and `yacc` both generate intermediate C programs from their input files, Automake knows how to build such intermediate files and link them into the final executable. Finally, we must remember to link a suitable `lex` library, if ‘`configure`’ concludes that one is needed.

And here is the ‘`configure.in`’:

```
dnl Process this file with autoconf to produce a configure script.
AC_INIT(main.c)
AM_INIT_AUTOMAKE(fonly, 1.0)
AC_PROG_CC
AM_PROG_LEX
AC_PROG_YACC
AC_OUTPUT(Makefile)
```

This ‘`configure.in`’ invokes some mandatory Autoconf and Automake initialization macros, and then calls on some Autoconf macros from the `AC_PROG` family to find suitable C compiler, `lex`, and `yacc` programs. Finally, the `AC_OUTPUT` macro is used to cause the generated ‘`configure`’ script to output a ‘`Makefile`’—but from what? It is processed from ‘`Makefile.in`’, which Automake produces for you based on your ‘`Makefile.am`’ (see [Appendix C \[Generated File Dependencies\]](#), page 313).

## 5.2 Generated Output Files

By studying the diagram in [Appendix C \[Generated File Dependencies\]](#), page 313, it should be possible to see which commands must be run to generate the required output files from the input files shown in the last section.

First, we generate ‘`configure`’:

```
$ aclocal
$ autoconf
```

Because ‘`configure.in`’ contains macro invocations which are not known to `autoconf` itself—`AM_INIT_AUTOMAKE` being a case in point, it is necessary to collect all of the macro definitions for `autoconf` to use when generating ‘`configure`’. This is done using the `aclocal` program, so called because it generates ‘`aclocal.m4`’ (see [Appendix C \[Generated File Dependencies\]](#), page 313). If you were to examine the contents of ‘`aclocal.m4`’, you would find the definition of the `AM_INIT_AUTOMAKE` macro contained within.

After running `autoconf`, you will find a ‘`configure`’ script in the current directory. It is important to run `aclocal` first because `automake` relies on the contents of ‘`configure.in`’ and ‘`aclocal.m4`’. On to `automake`:

```
$ automake --add-missing
automake: configure.in: installing ./install-sh
automake: configure.in: installing ./mkinstalldirs
automake: configure.in: installing ./missing
automake: Makefile.am: installing ./INSTALL
automake: Makefile.am: required file ./NEWS not found
automake: Makefile.am: required file ./README not found
automake: Makefile.am: installing ./COPYING
automake: Makefile.am: required file ./AUTHORS not found
automake: Makefile.am: required file ./ChangeLog not found
```



The ‘`--add-missing`’ option copies some boilerplate files from your Automake installation into the current directory. Files such as ‘`COPYING`’, which contain the GNU General Public License change infrequently, and so can be generated without user intervention. A number of utility scripts are also installed—these are used by the generated ‘`Makefile`’s, particularly by the `install` target. Notice that some required files are still missing. These are:

- ‘`NEWS`’      A record of user-visible changes to a package. The format is not strict, but the changes to the most recent version should appear at the top of the file.
- ‘`README`’    The first place a user will look to get an overview for the purpose of a package, and perhaps special installation instructions.
- ‘`AUTHORS`’   Lists the names, and usually mail addresses, of individuals who worked on the package.
- ‘`ChangeLog`’   The `ChangeLog` is an important file—it records the changes that are made to a package. The format of this file is quite strict (see [Section 5.5 \[Documentation and ChangeLogs\]](#), page 33).

For now, we’ll do enough to placate Automake:

```
$ touch NEWS README AUTHORS ChangeLog
$ automake --add-missing
```

Automake has now produced a ‘`Makefile.in`’. At this point, you may wish to take a snapshot of this directory before we really let loose with automatically generated files.

By now, the contents of the directory will be looking fairly complete and reminiscent of the top-level directory of a GNU package you may have installed in the past:

```
AUTHORS      INSTALL      NEWS          install-sh    mkinstalldirs
COPYING      Makefile.am  README        configure     missing
ChangeLog    Makefile.in  aclocal.m4    configure.in
```

It should now be possible to package up your tree in a `tar` file and give it to other users for them to install on their own systems. One of the `make` targets that Automake generates in ‘`Makefile.in`’ makes it easy to generate distributions (see [Chapter 13 \[Rolling Distribution Tarballs\]](#), page 139). A user would merely have to unpack the `tar` file, run `configure` (see [Chapter 3 \[Invoking configure\]](#), page 17) and finally type `make all`:

```

$ ./configure
creating cache ./config.cache
checking for a BSD compatible install... /usr/bin/install -c
checking whether build environment is sane... yes
checking whether make sets ${MAKE}... yes
checking for working aclocal... found
checking for working autoconf... found
checking for working automake... found
checking for working autoheader... found
checking for working makeinfo... found
checking for gcc... gcc
checking whether the C compiler (gcc ) works... yes
checking whether the C compiler (gcc ) is a cross-compiler... no
checking whether we are using GNU C... yes
checking whether gcc accepts -g... yes
checking how to run the C preprocessor... gcc -E
checking for flex... flex
checking for flex... (cached) flex
checking for yywrap in -lfl... yes
checking lex output file root... lex.yy
checking whether yytext is a pointer... yes
checking for bison... bison -y
updating cache ./config.cache
creating ./config.status
creating Makefile

$ make all
gcc -DPACKAGE=\"foonly\" -DVERSION=\"1.0\" -DYYTEXT_POINTER=1 -I. -I. \
-g -O2 -c main.c
gcc -DPACKAGE=\"foonly\" -DVERSION=\"1.0\" -DYYTEXT_POINTER=1 -I. -I. \
-g -O2 -c foo.c
flex scanner.l && mv lex.yy.c scanner.c
gcc -DPACKAGE=\"foonly\" -DVERSION=\"1.0\" -DYYTEXT_POINTER=1 -I. -I. \
-g -O2 -c scanner.c
bison -y parser.y && mv y.tab.c parser.c
if test -f y.tab.h; then \
  if cmp -s y.tab.h parser.h; then rm -f y.tab.h; \
  else mv y.tab.h parser.h; fi; \
else ;; fi
gcc -DPACKAGE=\"foonly\" -DVERSION=\"1.0\" -DYYTEXT_POINTER=1 -I. -I. \
-g -O2 -c parser.c
gcc -g -O2 -o foonly main.o foo.o scanner.o parser.o -lfl

```

### 5.3 Maintaining Input Files

If you edit any of the GNU Autotools input files in your package, it is necessary to regenerate the machine generated files for these changes to take effect. For instance, if you add a new source file to the `foonly_SOURCES` variable in `'Makefile.am'`. It is necessary to re-generate the derived file `'Makefile.in'`. If you are building your package, you need

to re-run `configure` to re-generate the site-specific ‘`Makefile`’, and then re-run `make` to compile the new source file and link it into ‘`foonly`’.

It is possible to regenerate these files by running the required tools, one at a time. However, as we can see above, it can be difficult to compute the dependencies—does a particular change require `aclocal` to be run? Does a particular change require `autoconf` to be run? There are two solutions to this problem.

The first solution is to use the `autoreconf` command. This tool regenerates all derived files by re-running all of the necessary tools in the correct order. It is somewhat of a brute force solution, but it works very well, particularly if you are not trying to accommodate other maintainers, or regular maintenance that would render this command bothersome.

The alternative is Automake’s ‘maintainer mode’. By invoking the `AM_MAINTAINER_MODE` macro from ‘`configure.in`’, automake will activate an ‘`--enable-maintainer-mode`’ option in ‘`configure`’. This is explained at length in [Chapter 8 \[Bootstrapping\]](#), page 49.

## 5.4 Packaging Generated Files

The debate about what to do with generated files is one which is keenly contested on the relevant Internet mailing lists. There are two points of view and I will present both of them to you so that you can try to decide what the best policy is for your project.

One argument is that generated files should not be included with a package, but rather only the ‘preferred form’ of the source code should be included. By this definition, ‘`configure`’ is a derived file, just like an object file, and it should not be included in the package. Thus, the user should use the GNU Autotools to bootstrap themselves prior to building the package. I believe there is some merit to this purist approach, as it discourages the practice of packaging derived files.

The other argument is that the advantages of providing these files can far outweigh the violation of good software engineering practice mentioned above. By including the generated files, users have the convenience of not needing to be concerned with keeping up to date with all of the different versions of the tools in active use. This is especially true for Autoconf, as ‘`configure`’ scripts are often generated by maintainers using locally modified versions of `autoconf` and locally installed macros. If ‘`configure`’ were regenerated by the user, the result could be different to that intended. Of course, this is poor practice, but it happens to reflect reality.

I believe the answer is to include generated files in the package when the package is going to be distributed to a wide user community (ie. the general public). For in-house packages, the former argument might make more sense, since the tools may also be held under version control.

## 5.5 Documentation and ChangeLogs

As with any software project, it is important to maintain documentation as the project evolves—the documentation must reflect the current state of the software, but it must also accurately record the changes that have been made in the past. The GNU coding standard rigorously enforces the maintenance of documentation. Automake, in fact, implements some of the standard by checking for the presence of a ‘`ChangeLog`’ file when `automake` is run!

A number of files exist, with standardized filenames, for storing documentation in GNU packages. The complete GNU coding standard, which offers some useful insights, can be found at <http://www.gnu.org/prep/standards.html>.

Other projects, including in-house projects, can use these same tried-and-true techniques. The purpose of most of the standard documentation files was outlined earlier See [Section 5.2 \[Generated Output Files\]](#), page 30, but the ‘ChangeLog’ deserves additional treatment.

When recording changes in a ‘ChangeLog’, one entry is made per person. Logical changes are grouped together, while logically distinct changes (ie. ‘change sets’) are separated by a single blank line. Here is an example from Automake’s own ‘ChangeLog’:

```
1999-11-21  Tom Tromey  <tromey@cygnus.com>

* automake.in (finish_languages): Only generate suffix rule
when not doing dependency tracking.

* m4/init.m4 (AM_INIT_AUTOMAKE): Use AM_MISSING_INSTALL_SH.
* m4/missing.m4 (AM_MISSING_INSTALL_SH): New macro.

* depend2.am: Use @SOURCE@, @OBJ@, @LTOBJ@, @OBJOBJ@,
and @BASE@. Always use -o.
```

Another important point to make about ‘ChangeLog’ entries is that they should be brief. It is not necessary for an entry to explain in details *why* a change was made, but rather *what* the change was. If a change is not straightforward then the explanation of *why* belongs in the source code itself. The GNU coding standard offers the complete set of guidelines for keeping ‘ChangeLog’s. Although any text editor can be used to create ChangeLog entries, Emacs provides a major mode to help you write them.

## 6 Writing ‘configure.in’

Writing a portable ‘configure.in’ is a tricky business. Since you can put arbitrary shell code into ‘configure.in’, your options seem overwhelming. There are many questions the first-time Autoconf user asks: What constructs are portable and what constructs aren’t portable? How do I decide what to check for? What shouldn’t I check for? How do I best use Autoconf’s features? What shouldn’t I put in ‘configure.in’? In what order should I run my checks? When should I look at the name of the system instead of checking for specific features?

### 6.1 What is Portability?

Before we talk about the mechanics of deciding what to check for and how to check for it, let’s ask ourselves a simple question: what is portability? Portability is a quality of the code that enables it to be built and run on a variety of platforms. In the Autoconf context, portability usually refers to the ability to run on Unix-like systems—sometimes including Windows.

When I first started using Autoconf, I had a hard time deciding what to check for in my ‘configure.in’. At the time, I was maintaining a proprietary program that ran only on SunOS 4. However, I was interested in porting it to Solaris, OSF/1, and possibly Irix.

The approach I took, while workable, was relatively time-consuming and painful: I wrote a minimal ‘configure.in’ and then proceeded to simply try to build my program on Solaris. Each time I encountered a build problem, I updated ‘configure.in’ and my source and started again. Once it built correctly, I started testing to see if there were runtime problems related to portability.

Since I didn’t start with a relatively portable base, and since I was unaware of the tools available to help with adding Autoconf support to a package (see [Chapter 24 \[Migrating Existing Packages\]](#), page 261), it was much more difficult than it had to be. If at all possible, it is better to write portable code to begin with.

There are a large number of Unix-like systems in the world, including many systems which, while still running, can only be considered obsolete. While it is probably possible to port some programs to all such systems, typically it isn’t useful to even try. Porting to everything is a difficult process, especially given that it usually isn’t possible to test on all platforms, and that new operating systems, with their own bugs and idiosyncrasies are released every year.

We advocate a pragmatic approach to portability: we write our programs to target a fairly large, but also fairly modern, cross-section of Unix-like systems. As deficiencies are discovered in our portability framework, we update ‘configure.in’ and our sources, and move on. In practice, this is an effective approach.

### 6.2 Brief introduction to portable sh

If you read a number of ‘configure.in’s, you’ll quickly notice that they tend to be written in an unusual style. For instance, you’ll notice you hardly ever see the ‘[’ program used; instead you’ll see ‘test’ invoked. We won’t go into all the details of writing a portable

shell script here; instead we leave that for [Chapter 22 \[Writing Portable Bourne Shell\]](#), [page 239](#).

Like other aspects of portability, the approach you take to writing shell scripts in ‘`configure.in`’ and ‘`Makefile.am`’ should depend on your goals. Some platforms have notoriously broken `sh` implementations. For instance, Ultrix `sh` doesn’t implement `unset`. Of course, the GNU Autotools are written in the most portable style possible, so as not to limit your possibilities.

Also, it doesn’t really make sense to talk about portable `sh` programming in the abstract. `sh` by itself does very little; most actual work is done by separate programs, each with its own potential portability problems. For instance, some options are not portable between systems, and some seemingly common programs don’t exist on every system – so not only do you have to know which `sh` constructs are not portable, but you also must know which programs you can (and cannot) use, and which options to those programs are portable.

This seems daunting, but in practice it doesn’t seem to be too hard to write portable shell scripts – once you’ve internalized the rules. Unfortunately, this process can take a long time. Meanwhile, a pragmatic ‘try and see’ approach, while noting other portable code you’ve seen elsewhere, works fairly well. Once again, it pays to be aware of which architectures you’ll probably care about – you will make different choices if you are writing an extremely portable program like `emacs` or `gcc` than if you are writing something that will only run on various flavors of Linux. Also, the cost of having unportable code in ‘`configure.in`’ is relatively low – in general it is fairly easy to rewrite pieces on demand as unportable constructs are found.

## 6.3 Ordering Tests

In addition to the problem of writing portable `sh` code, another problem which confronts first-time ‘`configure.in`’ writers is determining the order in which to run the various tests. Autoconf indirectly (via the `autoscan` program, which we cover in [Chapter 24 \[Migrating Existing Packages\]](#), [page 261](#)) suggests a standard ordering, which is what we describe here.

The standard ordering is:

1. Boilerplate. This section should include standard boilerplate code, such as the call to `AC_INIT` (which must be first), `AM_INIT_AUTOMAKE`, `AC_CONFIG_HEADER`, and perhaps `AC_REVISION`.
2. Options. The next section should include macros which add command-line options to `configure`, such as `AC_ARG_ENABLE`. It is typical to put support code for the option in this section as well, if it is short enough, like this example from `libgcj`:

```
AC_ARG_ENABLE(getenv-properties,
[  --disable-getenv-properties
                                don't set system properties from GCJ_PROPERTIES])

dnl Whether GCJ_PROPERTIES is used depends on the target.
if test -n "$enable_getenv_properties"; then
  enable_getenv_properties=${enable_getenv_properties-default-yes}
fi
if test "$enable_getenv_properties" = no; then
  AC_DEFINE(DISABLE_GETENV_PROPERTIES)
```

fi

3. Programs. Next it is traditional to check for programs that are either needed by the configure process, the build process, or by one of the programs being built. This usually involves calls to macros like `AC_CHECK_PROG` and `AC_PATH_TOOL`.
4. Libraries. Checks for libraries come before checks for other objects visible to C (or C++, or anything else). This is necessary because some other checks work by trying to link or run a program; by checking for libraries first you ensure that the resulting programs can be linked.
5. Headers. Next come checks for existence of headers.
6. Typedefs and structures. We do checks for typedefs after checking for headers for the simple reason that typedefs appear in headers, and we need to know which headers we can use before we look inside them.
7. Functions. Finally we check for functions. These come last because functions have dependencies on the preceding items: when searching for functions, libraries are needed in order to correctly link, headers are needed in order to find prototypes (this is especially important for C++, which has stricter prototyping rules than C), and typedefs are needed for those functions which use or return types which are not built in.
8. Output. This is done by invoking `AC_OUTPUT`.

This ordering should be considered a rough guideline, and not a list of hard-and-fast rules. Sometimes it is necessary to interleave tests, either to make ‘configure.in’ easier to maintain, or because the tests themselves do need to be in a different order. For instance, if your project uses both C and C++ you might choose to do all the C++ checks after all the C checks are done, in order to make ‘configure.in’ a bit easier to read.

## 6.4 What to check for

Deciding what to check for is really the central part of writing ‘configure.in’. Once you’ve read the Autoconf reference manual, the “how”s of writing a particular test should be fairly clear. The “when”s might remain a mystery – and it’s just as easy to check for too many things as it is to check for too few.

One notable area of divergence between various Unix-like systems is that the same programs don’t exist on all systems, and, even when they do, they don’t always work in the same way. For these problems we recommend, when possible, following the advice of the GNU Coding Standards: use the most common options from a relatively limited set of programs. Failing that, try to stick to programs and options specified by POSIX, perhaps augmenting this approach by doing checks for known problems on platforms you care about.

Checking for tools and their differences is usually a fairly small part of a ‘configure’ script; more common are checks for functions, libraries, and the like.

Except for a few core libraries like ‘libc’ and, usually, ‘libm’ and libraries like ‘libX11’ which typically aren’t considered system libraries, there isn’t much agreement about library names or contents between Unix systems. Still, libraries are easy to handle, because decisions about libraries almost always only affect the various ‘Makefile’*s*. That means that checking for another library typically doesn’t require major (or even, sometimes, any) changes to the source code. Also, because adding a new library test has a small impact



on the development cycle – effectively just re-running ‘`configure`’ and then a relink – you can effectively adopt a lax approach to libraries. For instance, you can just make things work on the few systems you immediately care about and then handle library changes on an as-needed basis.

Suppose you do end up with a link problem. How do you handle it? The first thing to do is use `nm` to look through the system libraries to see if the missing function exists. If it does, and it is in a library you can use then the solution is easy – just add another `AC_CHECK_LIB`. Note that just finding the function in a library is not enough, because on some systems, some "standard" libraries are undesirable; ‘`libucb`’ is the most common example of a library which you should avoid.

If you can’t find the function in a system library then you have a somewhat more difficult problem: a non-portable function. There are basically three approaches to a missing function. Below we talk about functions, but really these same approaches apply, more or less, to typedefs, structures, and global variables.

The first approach is to write a replacement function and either conditionally compile it, or put it into an appropriately-named file and use `AC_REPLACE_FUNCS`. For instance, Tcl uses `AC_REPLACE_FUNCS(strstr)` to handle systems that have no `strstr` function.

The second approach is used when there is a similar function with a different name. The idea here is to check for all the alternatives and then modify your source to use whichever one might exist. The idiom here is to use `break` in the second argument to `AC_CHECK_FUNCS`; this is used both to skip unnecessary tests and to indicate to the reader that these checks are related. For instance, here is how `libgcj` checks for `inet_aton` or `inet_addr`; it only uses the first one found:

```
AC_CHECK_FUNCS(inet_aton inet_addr, break)
```

Code to use the results of these checks looks something like:

```
#if HAVE_INET_ATON
... use inet_aton here
#else
#if HAVE_INET_ADDR
... use inet_addr here
#else
#error Function missing!
#endif
#endif
```

Note how we’ve made it a compile-time error if the function does not exist. In general it is best to make errors occur as early as possible in the build process.

The third approach to non-portable functions is to write code such that these functions are only optionally used. For instance, if you are writing an editor you might decide to use `mmap` to map a file into the editor’s memory. However, since `mmap` is not portable, you would also write a function to use the more portable `read`.

Handling known non-portable functions is only part of the problem, however. The pragmatic approach works fairly well, but it is somewhat inefficient if you are primarily developing on a more modern system, like GNU/Linux, which has few functions missing. In this case the problem is that you might not notice non-portable constructs in your code until it has largely been finished.



Unfortunately, there’s no high road to solving this problem. In the end, you need to have a working knowledge of the range of existing Unix systems. Knowledge of standards such as POSIX and XPG can be useful here, as a first cut – if it isn’t in POSIX, you should at least consider checking for it. However, standards are not a panacea – not all systems are POSIX compliant, and sometimes there are bugs in systems functions which you must work around.

One final class of problems you might encounter is that it is also easy to check for too much. This is bad because it adds unnecessary maintenance burden to your program. For instance, sometimes you’ll see code that checks for `<sys/types.h>`. However, there’s no point in doing that – using this header is mostly portable. Again, this can only be addressed by having a practical knowledge, which is only really possible by examining your target systems.

## 6.5 Using Configuration Names

While feature tests are definitely the best approach, a ‘configure’ script may occasionally have to make a decision based on a configuration name. This may be necessary if certain code must be compiled differently based on something which can not be tested using a standard Autoconf feature test. For instance, the `expect` package needs to find information about the system’s ‘tty’ implementation; this can’t reliably be done when cross compiling without examining the particular configuration name.

It is normally better to test for particular features, rather than to test for a particular system type. This is because as Unix and other operating systems evolve, different systems copy features from one another.

When there is no alternative to testing the configuration name in a ‘configure’ script, it is best to define a macro which describes the feature, rather than defining a macro which describes the particular system. This permits the same macro to be used on other systems which adopt the same feature (see [Chapter 23 \[Writing New Macros for Autoconf\]](#), [page 253](#)).

Testing for a particular system is normally done using a case statement in the autoconf ‘configure.in’ file. The case statement might look something like the following, assuming that ‘host’ is a shell variable holding a canonical configuration system—which will be the case if ‘configure.in’ uses the ‘AC\_CANONICAL\_HOST’ or ‘AC\_CANONICAL\_SYSTEM’ macros.

```
case "${host}" in
  i[[3456]]86-*-linux-gnu*) do something ;;
  sparc*-sun-solaris2.([[56789]])*) do something ;;
  sparc*-sun-solaris*) do something ;;
  mips*-*-elf*) do something ;;
  esac
```

Note the doubled square brackets in this piece of code. These are used to work around an ugly implementation detail of `autoconf`—it uses M4 under the hood. Without these extra brackets, the square brackets in the case statement would be swallowed by M4, and would not appear in the resulting ‘configure’. This nasty detail is discussed at more length in [Chapter 21 \[M4\]](#), [page 227](#).

It is particularly important to use ‘\*’ after the operating system field, in order to match the version number which will be generated by ‘`config.guess`’. In most cases you must

be careful to match a range of processor types. For most processor families, a trailing `*` suffices, as in `mips*` above. For the i386 family, something along the lines of `i[34567]86` suffices at present. For the m68k family, you will need something like `m68*`. Of course, if you do not need to match on the processor, it is simpler to just replace the entire field by a `*`, as in `*-*-irix*`.

## 7 Introducing GNU Automake

The primary goal of Automake is to generate ‘`Makefile.in`’s compliant with the GNU Makefile Standards. Along the way, it tries to remove boilerplate and drudgery. It also helps the ‘`Makefile`’ writer by implementing features (for instance automatic dependency tracking and parallel `make` support) that most maintainers don’t have the patience to implement by hand. It also implements some best practices as well as workarounds for vendor `make` bugs – both of which require arcane knowledge not generally available.

A secondary goal for Automake is that it works well with other free software, and, specifically, GNU tools. For example, Automake has support for Dejanu-based test suites.

Chances are that you don’t care about the GNU Coding Standards. That’s okay. You’ll still appreciate the convenience that Automake provides, and you’ll find that the GNU standards compliance feature, for the most part, assists rather than impedes.

Automake helps the maintainer with five large tasks, and countless minor ones. The basic functional areas are:

1. Build
2. Check
3. Clean
4. Install and uninstall
5. Distribution

We cover the first three items in this chapter, and the others in later chapters. Before we get into the details, let’s talk a bit about some general principles of Automake.

### 7.1 General Automake principles

Automake at its simplest turns a file called ‘`Makefile.am`’ into a GNU-compliant ‘`Makefile.in`’ for use with ‘`configure`’. Each ‘`Makefile.am`’ is written according to `make` syntax; Automake recognizes special macro and target names and generates code based on these.

There are a few Automake rules which differ slightly from `make` rules:

- Ordinary `make` comments are passed through to the output, but comments beginning with ‘`##`’ are Automake comments and are not passed through.
- Automake supports `include` directives. These directives are not passed through to the ‘`Makefile.in`’, but instead are processed by `automake` – files included this way are treated as if they were textually included in ‘`Makefile.am`’ at that point. This can be used to add boilerplate to each ‘`Makefile.am`’ in a project via a centrally-maintained file. The filename to include can start with ‘`$(top_srcdir)`’ to indicate that it should be found relative to the top-most directory of the project; if it is a relative path or if it starts with ‘`$(srcdir)`’ then it is relative to the current directory. For example, here is how you would reference boilerplate code from the file ‘`config/Make-rules`’ (where ‘`config`’ is a top-level directory in the project):

```
include $(top_srcdir)/config/Make-rules
```

- Automake supports conditionals which are not passed directly through to ‘`Makefile.in`’. This feature is discussed in [Chapter 19 \[Advanced GNU Automake Usage\]](#), page 205.
- Automake supports macro assignment using ‘`+=`’; these assignments are translated by Automake into ordinary ‘`=`’ assignments in ‘`Makefile.in`’.

All macros and targets, including those which Automake does not recognize, are passed through to the generated ‘`Makefile.in`’ – this is a powerful extension mechanism. Sometimes Automake will define macros or targets internally. If these are also defined in ‘`Makefile.am`’ then the definition in ‘`Makefile.am`’ takes precedence. This feature provides an easy way to tailor specific parts of the output in small ways.

Note, however, that it is a mistake to override parts of the generated code that aren’t documented (and thus ‘exported’ by Automake). Overrides like this stand a good chance of not working with future Automake releases.

Automake also scans ‘`configure.in`’. Sometimes it uses the information it discovers to generate extra code, and sometimes to provide extra error checking. Automake also turns every `AC_SUBST` into a ‘`Makefile`’ variable. This is convenient in more ways than one: not only does it mean that you can refer to these macros in ‘`Makefile.am`’ without extra work, but, since Automake scans ‘`configure.in`’ before it reads any ‘`Makefile.am`’, it also means that special variables and overrides Automake recognizes can be defined once in ‘`configure.in`’.

## 7.2 Introduction to Primaries

Each type of object that Automake understands has a special root variable name associated with it. This root is called a *primary*. Many actual variable names put into ‘`Makefile.am`’ are constructed by adding various prefixes to a primary.

For instance, scripts—interpreted executable programs—are associated with the `SCRIPTS` primary. Here is how you would list scripts to be installed in the user’s ‘`bindir`’:

```
bin_SCRIPTS = magic-script
```

(Note that the mysterious ‘`bin_`’ prefix will be discussed later.)

The contents of a primary-derived variable are treated as targets in the resulting ‘`Makefile`’. For instance, in our example above, we could generate ‘`magic-script`’ using `sed` by simply introducing it as a target:

```
bin_SCRIPTS = magic-script

magic-script: magic-script.in
sed -e 's/whatever//' < $(srcdir)/magic-script.in > magic-script
chmod +x magic-script
```

## 7.3 The easy primaries

This section describes the common primaries that are relatively easy to understand; the more complicated ones are discussed in the next section.

DATA	This is the easiest primary to understand. A macro of this type lists a number of files which are installed verbatim. These files can appear either in the source directory or the build directory.
HEADERS	Macros of this type list header files. These are separate from DATA macros because this allows for extra error checking in some cases.
SCRIPTS	This is used for executable scripts (interpreted programs). These are different from DATA because they are installed with different permissions and because they have the program name transform applied to them (e.g., the ‘ <code>--program-transform-name</code> ’ argument to <code>configure</code> ). Scripts are also different from compiled programs because the latter can be stripped while scripts cannot.
MANS	This lists man pages. Installing man pages is more complicated than you might think due to the lack of a single common practice. One developer might name a man page in the source tree ‘ <code>foo.man</code> ’ and then rename to the real name (‘ <code>foo.1</code> ’) at install time. Another developer might instead use numeric suffixes in the source tree and install using the same name. Sometimes an alphabetic code follows the numeric suffix (e.g., ‘ <code>quux.3n</code> ’); this code must be stripped before determining the correct install directory (this file must still be installed in ‘ <code>\$(man3dir)</code> ’). Automake supports all of these modes of operation:

`man_MANS` can be used when numeric suffixes are already in place:

```
man_MANS = foo.1 bar.2 quux.3n
```

`man1_MANS`, `man2_MANS`, etc., can be used to force renaming at install time. This renaming is skipped if the suffix already begins with the correct number. For instance:

```
man1_MANS = foo.man
man3_MANS = quux.3n
```

Here ‘`foo.man`’ will be installed as ‘`foo.1`’ but ‘`quux.3n`’ will keep its name at install time.

TEXINFOS	GNU programs traditionally use the Texinfo documentation format, not man pages. Automake has full support for Texinfo, including some additional features such as versioning and <code>install-info</code> support. We won’t go into that here except to mention that it exists. See the Automake reference manual for more information.
----------	--

Automake supports a variety of lesser-used primaries such as `JAVA` and `LISP` (and, in the next major release, `PYTHON`). See the reference manual for more information on these.

## 7.4 Programs and libraries

The preceding primaries have all been relatively easy to use. Now we’ll discuss a more complicated set, namely those used to build programs and libraries. These primaries are more complex because building a program is more complex than building a script (which often doesn’t even need building at all).

Use the `PROGRAMS` primary for programs, `LIBRARIES` for libraries, and `LTLIBRARIES` for Libtool libraries (see [Chapter 10 \[Introducing GNU Libtool\]](#), page 81). Here is a minimal example:

```
bin_PROGRAMS = doit
```

This creates the program `doit` and arranges to install it in `bindir`. First `make` will compile `doit.c` to produce `doit.o`. Then it will link `doit.o` to create `doit`.

Of course, if you have more than one source file, and most programs do, then you will want to be able to list them somehow. You will do this via the program's `SOURCES` variable. Each program or library has a set of associated variables whose names are constructed by appending suffixes to the 'normalized' name of the program. The *normalized name* is the name of the object with non-alphanumeric characters changed to underscores. For instance, the normalized name of `'quux'` is `'quux'`, but the normalized name of `'install-info'` is `'install_info'`. Normalized names are used because they correspond to `make` syntax, and, like all macros, Automake propagates these definitions into the resulting `'Makefile.in'`.

So if `'doit'` is to be built from files `'main.c'` and `'doit.c'`, we would write:

```
bin_PROGRAMS = doit
doit_SOURCES = doit.c main.c
```

The same holds for libraries. In the `zlib` package we might make a library called `'libzlib.a'`. Then we would write:

```
lib_LIBRARIES = libzlib.a
libzlib_a_SOURCES = Adler32.c compress.c crc32.c deflate.c deflate.h \
gzio.c inffblock.c inffblock.h inffcodes.c inffcodes.h inffast.c inffast.h \
inffixed.h inflate.c inftrees.c inftrees.h infutil.c infutil.h trees.c \
trees.h uncompr.c zconf.h zlib.h zutil.c zutil.h
```

We can also do this with libtool libraries. For instance, suppose we want to build `'libzlib.la'` instead:

```
lib_LTLIBRARIES = libzlib.la
libzlib_la_SOURCES = Adler32.c compress.c crc32.c deflate.c deflate.h \
gzio.c inffblock.c inffblock.h inffcodes.c inffcodes.h inffast.c inffast.h \
inffixed.h inflate.c inftrees.c inftrees.h infutil.c infutil.h trees.c \
trees.h uncompr.c zconf.h zlib.h zutil.c zutil.h
```

As you can see, making shared libraries with Automake and Libtool is just as easy as making static libraries.

In the above example, we listed header files in the `SOURCES` variable. These are ignored (except by `make dist`<sup>1</sup>) but can serve to make your `'Makefile.am'` a bit clearer (and sometimes shorter, if you aren't installing headers).

Note that you can't use `'configure'` substitutions in a `SOURCES` variable. Automake needs to know the *static* list of files which can be compiled into your program. There are still various ways to conditionally compile files, for instance Automake conditionals or the use of the `LDADD` variable.

The static list of files is also used in some versions of Automake's automatic dependency tracking. The general rule is that each source file which might be compiled should be listed in some `SOURCES` variable. If the source is conditionally compiled, it can be listed in an

---

<sup>1</sup> See [Chapter 13 \[Rolling Distribution Tarballs\]](#), page 139

EXTRA variable. For instance, suppose in this example ‘@FOO\_OBJ@’ is conditionally set by ‘configure’ to ‘foo.o’ when ‘foo.c’ should be compiled:

```
bin_PROGRAMS = foo
foo_SOURCES = main.c
foo_LDADD = @FOO_OBJ@
foo_DEPENDENCIES = @FOO_OBJ@
EXTRA_foo_SOURCES = foo.c
```

In this case, ‘EXTRA\_foo\_SOURCES’ is used to list sources which are conditionally compiled; this tells Automake that they exist even though it can’t deduce their existence automatically.

In the above example, note the use of the ‘foo\_LDADD’ macro. This macro is used to list other object files and libraries which should be linked into the foo program. Each program or library has several such associated macros which can be used to customize the link step; here we list the most common ones:

‘\_DEPENDENCIES’

Extra dependencies which are added to the program’s dependency list. If not specified, this is automatically computed based on the value of the program’s ‘\_LDADD’ macro.

‘\_LDADD’    Extra objects which are passed to the linker. This is only used by programs and shared libraries.

‘\_LDFLAGS’

Flags which are passed to the linker. This is separate from ‘\_LDADD’ to allow ‘\_DEPENDENCIES’ to be auto-computed.

‘\_LIBADD’    Like ‘\_LDADD’, but used for static libraries and not programs.

You aren’t required to define any of these macros.

## 7.5 Frequently Asked Questions

Experience has shown that there are several common questions that arise as people begin to use automake for their own projects. It seemed prudent to mention these issues here.

Users often want to make a library (or program, but for some reason it comes up more frequently with libraries) whose sources live in subdirectories:

```
lib_LIBRARIES = libsub.a
libsub_a_SOURCES = subdir1/something.c ...
```

If you try this with Automake 1.4, you’ll get an error:

```
$ automake
automake: Makefile.am: not supported: source file subdir1/something.c is in subdire
```

For libraries, this problem is mostly simply solve by using libtool convenience libraries. For programs, there is no simple solution. Many people elect to restructure their package in this case.

The next major release of Automake addresses this problem.

Another general problem that comes up is that of setting compilation flags. Most rules have flags—for instance, compilation of C code automatically uses ‘CFLAGS’. However, these

variables are considered user variables. Setting them in ‘`Makefile.am`’ is unsafe, because the user will expect to be able to override them at will.

To handle this, for each flag variable, Automake introduce an ‘`AM_`’ version which can be set in ‘`Makefile.am`’. For instance, we could set some flags for C and C++ compilation like so:

```
AM_CFLAGS = -DFOR_C
AM_CXXFLAGS = -DFOR_CXX
```

Finally, people often ask how to compile a single source file in two different ways. For instance, the ‘`etags.c`’ file which comes with Emacs can be compiled with different ‘`-D`’ options to produce the `etags` and `ctags` programs.

With Automake 1.4 this can only be done by writing your own compilation rules, like this:

```
bin_PROGRAMS = etags ctags
etags_SOURCES = etags.c
ctags_SOURCES =
ctags_LDADD = ctags.o

etags.o: etags.c
$(CC) $(CFLAGS) -DETAGS ...

ctags.o: etags.c
$(CC) $(CFLAGS) -DCTAGS ...
```

This is tedious and hard to maintain for larger programs. Automake 1.5 will support a much more natural approach:

```
bin_PROGRAMS = etags ctags
etags_SOURCES = etags.c
etags_CFLAGS = -DETAGS
ctags_SOURCES = etags.c
ctags_CFLAGS = -DCTAGS
```

## 7.6 Multiple directories

So far, we’ve only dealt with single-directory projects. Automake can also handle projects with many directories. The variable ‘`SUBDIRS`’ is used to list the subdirectories which should be built. Here is an example from Automake itself:

```
SUBDIRS = . m4 tests
```

Automake does not need to know the list of subdirectories statically, so there is no ‘`EXTRA_SUBDIRS`’ variable. You might think that Automake would use ‘`SUBDIRS`’ to see which ‘`Makefile.am`’s to scan, but it actually gets this information from ‘`configure.in`’. This means that, if you have a subdirectory which is optionally built, you should still list it unconditionally in your call to `AC_OUTPUT` and then arrange for it to be substituted (or not, as appropriate) at `configure` time.

Subdirectories are always built in the order they appear, but cleaning rules (e.g., `maintainer-clean`) are always run in the reverse order. The reason for this odd reversal is that it is wrong to remove a file before removing all the files which depend on it.



You can put `‘.’` into `‘SUBDIRS’` to control when the objects in the current directory are built, relative to the objects in the subdirectories. In the example above, targets in `‘.’` will be built before subdirectories are built. If `‘.’` does not appear in `‘SUBDIRS’`, it is built following all the subdirectories.

## 7.7 Testing

Automake also includes simple support for testing your program.

The most simple form of this is the `‘TESTS’` variable. This variable holds a list of tests which are run when the user runs `make check`. Each test is built (if necessary) and then executed. For each test, `make` prints a single line indicating whether the test has passed or failed. Failure means exiting with a non-zero status, with the special exception that an exit status of `‘77’`<sup>2</sup> means that the test should be ignored. `make check` also prints a summary showing the number of passes and fails.

Automake also supports the notion of an *xfail*, which is a test which is expected to fail. Sometimes this is useful when you want to track a known failure, but you aren’t prepared to fix it right away. Tests which are expected to fail should be listed in both `‘TESTS’` and `‘XFAIL_TESTS’`.

The special prefix `‘check’` can be used with primaries to indicate that the objects should only be built at `make check` time. For example, here is how you can build a program that will only be used during the testing process:

```
check_PROGRAMS = test-program
test_program_SOURCES = ...
```

Automake also supports the use of DejaGNU, the GNU test framework. DejaGNU support can be enabled using the `‘dejagnu’` option:

```
AUTOMAKE_OPTIONS = dejagnu
```

The resulting `‘Makefile.in’` will include code to invoke the `runtest` program appropriately.

---

<sup>2</sup> A number chosen arbitrarily by the Automake developers.



## 8 Bootstrapping

There are many programs in the GNU Autotools, each of which has a complex set of inputs. When one of these inputs changes, it is important to run the proper programs in the proper order. Unfortunately, it is hard to remember both the dependencies and the ordering.

For instance, whenever you edit ‘`configure.in`’, you must remember to re-run `aclocal` in case you added a reference to a new macro. You must also rebuild ‘`configure`’ by running `autoconf`; ‘`config.h`’ by running `autoheader`, in case you added a new `AC_DEFINE`; and `automake` to propagate any new `AC_SUBST`s to the various ‘`Makefile.in`’s. If you edit a ‘`Makefile.am`’, you must re-run `automake`. In both these cases, you must then remember to re-run `config.status --recheck` if ‘`configure`’ changed, followed by `config.status` to rebuild the ‘`Makefile`’s.

When doing active development on the build system for your project, these dependencies quickly become painful. Of course, Automake knows how to handle this automatically. By default, `automake` generates a ‘`Makefile.in`’ which knows all these dependencies and which automatically re-runs the appropriate tools in the appropriate order. These rules assume that the correct versions of the tools are all in your `PATH`.

It helps to have a script ready to do all of this for you once, before you have generated a ‘`Makefile`’ that will automatically run the tools in the correct order, or when you make a fresh checkout of the code from a CVS repository where the developers don’t keep generated files under source control. There are at least two opposing schools of thought regarding how to go about this – the `autogen.sh` school and the `bootstrap` school:

### `autogen.sh`

From the outset, this is a poor name for a bootstrap script, since there is already a GNU automatic text generation tool called AutoGen. Often packages that follow this convention have the script automatically run the generated `configure` script after the bootstrap process, passing `autogen.sh` arguments through to `configure`. Except you don’t know what options you want yet, since you can’t run ‘`configure --help`’ until `configure` has been generated. I suggest that if you find yourself compiling a project set up in this way that you type:

```
$ /bin/sh ./autogen.sh --help
```

and ignore the spurious warning that tells you `configure` will be executed.

### `bootstrap`

Increasingly, projects are starting to call their bootstrap scripts ‘`bootstrap`’. Such scripts simply run the various commands required to bring the source tree into a state where the end user can simply:

```
$ configure
$ make
$ make install
```

Unfortunately, proponents of this school of thought don’t put the bootstrap script in their distributed tarballs, since the script is unnecessary except when the build environment of a developer’s machine has changed. This means the

proponents of the `autogen.sh` school may never see the advantages of the other method.

Autoconf comes with a program called `autoreconf` which essentially does the work of the `bootstrap` script. `autoreconf` is rarely used because, historically, has not been very well known, and only in Autoconf 2.13 did it acquire the ability to work with Automake. Unfortunately, even the Autoconf 2.13 `autoreconf` does not handle `libtoolize` and some `automake`-related options that are frequently nice to use.

We recommend the `bootstrap` method, until `autoreconf` is fixed. At this point `bootstrap` has not been standardized, so here is a version of the script we used while writing this book<sup>1</sup>:

```
#!/bin/sh

aclocal \
&& automake --gnu --add-missing \
&& autoconf
```

We don't use `autoreconf` here because that script (as of Autoconf 2.13) also does not handle the `--add-missing` option, which we want. A typical `bootstrap` might also run `libtoolize` or `autoheader`.

It is also important for all developers on a project to have the same versions of the tools installed so that these rules don't inadvertently cause problems due to differences between tool versions. This version skew problem turns out to be fairly significant in the field. So, `automake` provides a way to disable these rules by default, while still allowing users to enable them when they know their environment is set up correctly.

In order to enable this mode, you must first add `AM_MAINTAINER_MODE` to `'configure.in'`. This will add the `--enable-maintainer-mode` option to `'configure'`; when specified this flag will cause these so-called 'maintainer rules' to be enabled.

Note that maintainer mode is a controversial feature. Some people like to use it because it causes fewer bug reports in some situations. For instance, CVS does not preserve relative timestamps on files. If your project has both `'configure.in'` and `'configure'` checked in, and maintainer mode is not in use, then sometimes `make` will decide to rebuild `'configure'` even though it is not really required. This in turn means more headaches for your developers – on a large project most developers won't touch `'configure.in'` and many may not even want to install the GNU Autotools<sup>2</sup>.

The other camp claims that end users should use the same build system that developers use, that maintainer mode is simply unaesthetic, and furthermore that the modality of maintainer mode is dangerous—you can easily forget what mode you are in and thus forget to rebuild, and thus correctly test, a change to the configure or build system. When maintainer mode is not in use, the Automake-supplied `missing` script will be used to warn users when it appears that they need a maintainer tool that they do not have.

The approach you take depends strongly on the social structures surrounding your project.

---

<sup>1</sup> This book is built using `automake` and `autoconf`. We couldn't find a use for `libtool`.

<sup>2</sup> Shock, horror

## 9 A Small GNU Autotools Project

This chapter introduces a small—but real—worked example, to illustrate some of the features, and highlight some of the pitfalls, of the GNU Autotools discussed so far. All of the source can be downloaded from the book’s web page<sup>1</sup>. The text is peppered with my own pet ideas, accumulated over a several years of working with the GNU Autotools and you should be able to easily apply these to your own projects. I will begin by describing some of the choices and problems I encountered during the early stages of the development of this project. Then by way of illustration of the issues covered, move on to showing you a general infrastructure that I use as the basis for all of my own projects, followed by the specifics of the implementation of a portable command line shell library. This chapter then finishes with a sample shell application that uses that library.

Later, in Chapter 12 [A Large GNU Autotools Project], page 123 and Chapter 20 [A Complex GNU Autotools Project], page 209, the example introduced here will be gradually expanded as new features of GNU Autotools are revealed.

### 9.1 GNU Autotools in Practice

This section details some of the specific problems I encountered when starting this project, and is representative of the sorts of things you are likely to want to do in projects of your own, but for which the correct solution may not be immediately evident. You can always refer back to this section for some inspiration if you come across similar situations. I will talk about some of the decisions I made about the structure of the project, and also the trade-offs for the other side of the argument – you might find the opposite choice to the one I make here is more relevant a particular project of yours.

#### 9.1.1 Project Directory Structure

Before starting to write code for any project, you need to decide on the directory structure you will use to organise the code. I like to build each component of a project in its own subdirectory, and to keep the configuration sources separate from the source code. The great majority of GNU projects I have seen use a similar method, so adopting it yourself will likely make your project more familiar to your developers by association.

The top level directory is used for configuration files, such as ‘`configure`’ and ‘`aclocal.m4`’, and for a few other sundry files, ‘`README`’ and a copy of the project license for example.

Any significant libraries will have a subdirectory of their own, containing all of the sources and headers for that library along with a ‘`Makefile.am`’ and anything else that is specific to just that library. Libraries that are part of a small like group, a set of pluggable application modules for example, are kept together in a single directory.

The sources and headers for the project’s main application will be stored in yet another subdirectory, traditionally named ‘`src`’. There are other conventional directories your developers might expect too: A ‘`doc`’ directory for project documentation; and a ‘`test`’ directory for the project self test suite.

---

<sup>1</sup> <http://sources.redhat.com/autobook/>

To keep the project top-level directory as uncluttered as possible, as I like to do, you can take advantage of Autoconf's `AC_CONFIG_AUX_DIR` by creating another directory, say `config`, which will be used to store many of the GNU Autotools intermediate files, such as `install-sh`. I always store all project specific Autoconf M4 macros to this same subdirectory.

So, this is what you should start with:

```
$ pwd
~/mypackage
$ ls -F
Makefile.am  config/      configure.in  lib/  test/
README       configure*   doc/         src/
```

### 9.1.2 C Header Files

There is a small amount of boiler-plate that should be added to all header files, not least of which is a small amount of code to prevent the contents of the header from being scanned multiple times. This is achieved by enclosing the entire file in a preprocessor conditional which evaluates to false after the first time it has been seen by the preprocessor. Traditionally, the macro used is in all upper case, and named after the installation path without the installation prefix. Imagine a header that will be installed to `/usr/local/include/sys/foo.h`, for example. The preprocessor code would be as follows:

```
#ifndef SYS_FOO_H
#define SYS_FOO_H 1
...
#endif /* !SYS_FOO_H */
```

Apart from comments, the entire content of the rest of this header file must be between these few lines. It is worth mentioning that inside the enclosing `ifndef`, the macro `SYS_FOO_H` must be defined before any other files are `#included`. It is a common mistake to not define that macro until the end of the file, but mutual dependency cycles are only stalled if the guard macro is defined before the `#include` which starts that cycle<sup>2</sup>.

If a header is designed to be installed, it must `#include` other installed project headers from the local tree using angle-brackets. There are some implications to working like this:

- You must be careful that the names of header file directories in the source tree match the names of the directories in the install tree. For example, when I plan to install the aforementioned `foo.h` to `/usr/local/include/project/foo.h`, from which it will be included using `#include <project/foo.h>`, then in order for the same include line to work in the source tree, I must name the source directory it is installed from `project` too, or other headers which use it will not be able to find it until after it has been installed.
- When you come to developing the next version of a project laid out in this way, you must be careful about finding the correct header. Automake takes care of that for you by using `-I` options that force the compiler to look for uninstalled headers in the

---

<sup>2</sup> An `#include` cycle is the situation where file `a.h` `#includes` file `b.h`, and `b.h` `#includes` file `a.h` – either directly or through some longer chain of `#includes`.

current source directory before searching the system directories for installed headers of the same name.

- You don't have to install all of your headers to `/usr/include` – you can use subdirectories. And all without having to rewrite the headers at install time.

### 9.1.3 C++ Compilers

In order for a C++ program to use a library compiled with a C compiler, it is necessary for any symbols exported from the C library to be declared between `'extern "C" {'` and `'}'`. This code is important, because a C++ compiler *mangles*<sup>3</sup> all variable and function names, where as a C compiler does not. On the other hand, a C compiler will not understand these lines, so you must be careful to make them invisible to the C compiler.

Sometimes you will see this method used, written out in long hand in every installed header file, like this:

```
#ifdef __cplusplus
extern "C" {
#endif

...

#ifdef __cplusplus
}
#endif
```

But that is a lot of unnecessary typing if you have a few dozen headers in your project. Also the additional braces tend to confuse text editors, such as emacs, which do automatic source indentation based on brace characters.

Far better, then, to declare them as macros in a common header file, and use the macros in your headers:

```
#ifdef __cplusplus
# define BEGIN_C_DECLS extern "C" {
# define END_C_DECLS   }
#else /* !__cplusplus */
# define BEGIN_C_DECLS
# define END_C_DECLS
#endif /* __cplusplus */
```

I have seen several projects that name such macros with a leading underscore – `'_BEGIN_C_DECLS'`. Any symbol with a leading underscore is reserved for use by the compiler implementation, so you shouldn't name **any** symbols of your own in this way. By way of example, I recently ported the Small<sup>4</sup> language compiler to Unix, and almost all of the work was writing a Perl script to rename huge numbers of symbols in the compiler's reserved namespace to something more sensible so that GCC could even parse the sources. Small was originally developed on Windows, and the author had used a lot of symbols with a leading underscore. Although his symbol names didn't clash with his own compiler, in some cases they were the same as symbols used by GCC.

<sup>3</sup> For an explanation of name mangling See [Chapter 16 \[Writing Portable C++\]](#), page 161.

<sup>4</sup> <http://www.compuphase.com/small.htm>

### 9.1.4 Function Definitions

As a stylistic convention, the return types for all function definitions should be on a separate line. The main reason for this is that it makes it very easy to find the functions in source file, by looking for a single identifier at the start of a line followed by an open parenthesis:

```
$ egrep '^[_a-zA-Z][_a-zA-Z0-9]*[ \t]*\(' error.c
set_program_name (const char *path)
error (int exit_status, const char *mode, const char *message)
sic_warning (const char *message)
sic_error (const char *message)
sic_fatal (const char *message)
```

There are emacs lisp functions and various code analysis tools, such as `ansi2knr` (see [Section 9.1.6 \[K&R Compilers\], page 55](#)), which rely on this formatting convention, too. Even if you don't use those tools yourself, your fellow developers might like to, so it is a good convention to adopt.

### 9.1.5 Fallback Function Implementations

Due to the huge number of Unix varieties in common use today, many of the C library functions that you take for granted on your preferred development platform are very likely missing from some of the architectures you would like your code to compile on. Fundamentally there are two ways to cope with this:

- Use only the few library calls that are available everywhere. In reality this is not actually possible because there are two lowest common denominators with mutually exclusive APIs, one rooted in BSD Unix ('`bcopy`', '`rindex`') and the other in SYSV Unix ('`memcpy`', '`strchr`'). The only way to deal with this is to define one API in terms of the other using the preprocessor. The newer POSIX standard deprecates many of the BSD originated calls (with exceptions such as the BSD socket API). Even on non-POSIX platforms, there has been so much cross pollination that often both varieties of a given call may be provided, however you would be wise to write your code using POSIX endorsed calls, and where they are missing, define them in terms of whatever the host platform provides.

This approach requires a lot of knowledge about various system libraries and standards documents, and can leave you with reams of preprocessor code to handle the differences between APIs. You will also need to perform a lot of checking in '`configure.in`' to figure out which calls are available. For example, to allow the rest of your code to use the '`strcpy`' call with impunity, you would need the following code in '`configure.in`':

```
AC_CHECK_FUNCS(strcpy bcopy)
```

And the following preprocessor code in a header file that is seen by every source file:

```
#if !HAVE_STRCPY
#   if HAVE_BCOPY
#       define strcpy(dest, src)    bcopy (src, dest, 1 + strlen (src))
#   else /* !HAVE_BCOPY */
#       error no strcpy or bcopy
#   endif /* HAVE_BCOPY */
#endif /* HAVE_STRCPY */
```



- Alternatively you could provide your own fallback implementations of function calls you know are missing on some platforms. In practice you don't need to be as knowledgeable about problematic functions when using this approach. You can look in GNU libiberty<sup>5</sup> or François Pinard's libit project<sup>6</sup> to see for which functions other GNU developers have needed to implement fallback code. The libit project is especially useful in this respect as it comprises canonical versions of fallback functions, and suitable Autoconf macros assembled from across the entire GNU project. I won't give an example of setting up your package to use this approach, since that is how I have chosen to structure the project described in this chapter.

Rather than writing code to the lowest common denominator of system libraries, I am a strong advocate of the latter school of thought in the majority of cases. As with all things it pays to take a pragmatic approach; don't be afraid of the middle ground – weigh the options on a case by case basis.

### 9.1.6 K&R Compilers

K&R C is the name now used to describe the original C language specified by Brian Kernighan and Dennis Ritchie (hence, 'K&R'). I have yet to see a C compiler that doesn't support code written in the K&R style, yet it has fallen very much into disuse in favor of the newer ANSI C standard. Although it is increasingly common for vendors to *unbundle* their ANSI C compiler, the GCC project<sup>7</sup> is available for all of the architectures I have ever used.

There are four differences between the two C standards:

1. ANSI C expects full type specification in function prototypes, such as you might supply in a library header file:

```
extern int functionname (const char *parameter1, size_t parameter 2);
```

The nearest equivalent in K&R style C is a forward declaration, which allows you to use a function before its corresponding definition:

```
extern int functionname ();
```

As you can imagine, K&R has very bad type safety, and does not perform any checks that only function arguments of the correct type are used.

2. The function headers of each function definition are written differently. Where you might see the following written in ANSI C:

```
int
functionname (const char *parameter1, size_t parameter2)
{
    ...
}
```

K&R expects the parameter type declarations separately, like this:

```
int
```

---

<sup>5</sup> Available at <http://sourceware.cygnum.com/pub/binutils/>.

<sup>6</sup> Distributed from <http://www.imo.umontreal.ca/~pinard/libit>.

<sup>7</sup> GCC must be compilable by K&R compilers so that it can be built and installed in an ANSI compiler free environment.

```

functionname (parameter1, parameter2)
    const char *parameter1;
    size_t parameter2;
{
    ...
}

```

3. There is no concept of an untyped pointer in K&R C. Where you might be used to seeing ‘void \*’ pointers in ANSI code, you are forced to overload the meaning of ‘char \*’ for K&R compilers.
4. Variadic functions are handled with a different API in K&R C, imported with ‘#include <varargs.h>’. A K&R variadic function definition looks like this:

```

int
functionname (va_alist)
    va_dcl
{
    va_list ap;
    char *arg;

    va_start (ap);
    ...
    arg = va_arg (ap, char *);
    ...
    va_end (ap);

    return arg ? strlen (arg) : 0;
}

```

ANSI C provides a similar API, imported with ‘#include <stdarg.h>’, though it cannot express a variadic function with no named arguments such as the one above. In practice, this isn’t a problem since you always need at least one parameter, either to specify the total number of arguments somehow, or else to mark the end of the argument list. An ANSI variadic function definition looks like this:

```

int
functionname (char *format, ...)
{
    va_list ap;
    char *arg;

    va_start (ap, format);
    ...
    arg = va_arg (ap, char *);
    ...
    va_end (ap);

    return format ? strlen (format) : 0;
}

```

Except in very rare cases where you are writing a low level project (GCC for example), you probably don’t need to worry about K&R compilers too much. However, supporting

them can be very easy, and if you are so inclined, can be handled either by employing the `ansi2knr` program supplied with Automake, or by careful use of the preprocessor.

Using `ansi2knr` in your project is described in some detail in [section “Automatic de-ANSI-fication”](#) in *The Automake Manual*, but boils down to the following:

- Add this macro to your ‘`configure.in`’ file:

```
AM_C_PROTOTYPES
```

- Rewrite the contents of ‘`LIBOBJJS`’ and/or ‘`LTLIBOBJJS`’ in the following fashion:

```
# This is necessary so that .o files in LIBOBJJS are also built via
# the ANSI2KNR-filtering rules.
Xsed='sed -e "s/^X/"'
LIBOBJJS='echo X"$LIBOBJJS"|\
[$Xsed -e 's/\.[^.]*/.\$U& /g;s/\.[^.]*/.\$U&/'] '
```

Personally, I dislike this method, since every source file is filtered and rewritten with ANSI function prototypes and declarations converted to K&R style adding a fair overhead in additional files in your build tree, and in compilation time. This would be reasonable were the abstraction sufficient to allow you to forget about K&R entirely, but `ansi2knr` is a simple program, and does not address any of the other differences between compilers that I raised above, and it cannot handle macros in your function prototypes or definitions. If you decide to use `ansi2knr` in your project, you must make the decision before you write any code, and be aware of its limitations as you develop.

For my own projects, I prefer to use a set of preprocessor macros along with a few stylistic conventions so that all of the differences between K&R and ANSI compilers are actually addressed, and so that the unfortunate few who have no access to an ANSI compiler (and who cannot use GCC for some reason) needn’t suffer the overheads of `ansi2knr`.

The four differences in style listed at the beginning of this subsection are addressed as follows:

1. The function prototype argument lists are declared inside a `PARAMS` macro invocation so that K&R compilers will still be able to compile the source tree. `PARAMS` removes ANSI argument lists from function prototypes for K&R compilers. Some developers continue to use `__P` for this purpose, but strictly speaking, macros starting with ‘`_`’ (and especially ‘`__`’) are reserved for the compiler and the system headers, so using ‘`PARAMS`’, as follows, is safer:

```
#if __STDC__
#   ifndef NOPROTOS
#       define PARAMS(args)      args
#   endif
#endif
#ifndef PARAMS
#   define PARAMS(args)          ()
#endif
```

This macro is then used for all function declarations like this:

```
extern int functionname PARAMS((const char *parameter));
```

2. With the `PARAMS` macro is used for all function declarations, ANSI compilers are given all the type information they require to do full compile time type checking. The function definitions proper must then be declared in K&R style so that K&R compilers don’t

choke on ANSI syntax. There is a small amount of overhead in writing code this way, however: The ANSI compile time type checking can only work in conjunction with K&R function definitions if it first sees an ANSI function prototype. This forces you to develop the good habit of prototyping *every single* function in your project. Even the static ones.

3. The easiest way to work around the lack of `void *` pointers, is to define a new type that is conditionally set to `void *` for ANSI compilers, or `char *` for K&R compilers. You should add the following to a common header file:

```
#if __STDC__
typedef void *void_ptr;
#else /* !__STDC__ */
typedef char *void_ptr;
#endif /* __STDC__ */
```

4. The difference between the two variadic function APIs pose a stickier problem, and the solution is ugly. But it *does* work. First you must check for the headers in ‘configure.in’:

```
AC_CHECK_HEADERS(stdarg.h varargs.h, break)
```

Having done this, add the following code to a common header file:

```
#if HAVE_STDARG_H
# include <stdarg.h>
# define VA_START(a, f)      va_start(a, f)
#else
# if HAVE_VARARGS_H
#   include <varargs.h>
#   define VA_START(a, f)    va_start(a)
# endif
#endif
#ifndef VA_START
error no variadic api
#endif
```

You must now supply each variadic function with both a K&R and an ANSI definition, like this:

```
int
#if HAVE_STDARG_H
functionname (const char *format, ...)
#else
functionname (format, va_alist)
    const char *format;
    va_dcl
#endif
{
    va_alist ap;
    char *arg;

    VA_START (ap, format);
    ...
    arg = va_arg (ap, char *);
```

```

...
va_end (ap);

return arg : strlen (arg) ? 0;
}

```

## 9.2 A Simple Shell Builders Library

An application which most developers try their hand at sooner or later is a Unix shell. There is a lot of functionality common to all traditional command line shells, which I thought I would push into a portable library to get you over the first hurdle when that moment is upon you. Before elaborating on any of this I need to name the project. I've called it *sic*, from the Latin *so it is*, because like all good project names it is somewhat pretentious and it lends itself to the recursive acronym *sic is cumulative*.

The gory detail of the minutiae of the source is beyond the scope of this book, but to convey a feel for the need for Sic, some of the goals which influenced the design follow:

- Sic must be very small so that, in addition to being used as the basis for a full blown shell, it can be linked (unadorned) into an application and used for trivial tasks, such as reading startup configuration.
- It must not be tied to a particular syntax or set of reserved words. If you use it to read your startup configuration, I don't want to force you to use my syntax and commands.
- The boundary between the library ('*libsic*') and the application must be well defined. Sic will take strings of characters as input, and internally parse and evaluate them according to registered commands and syntax, returning results or diagnostics as appropriate.
- It must be extremely portable – that is what I am trying to illustrate here, after all.

### 9.2.1 Portability Infrastructure

As I explained in [Section 9.1.1 \[Project Directory Structure\]](#), [page 51](#), I'll first create the project directories, a toplevel directory and a subdirectory to put the library sources into. I want to install the library header files to '*/usr/local/include/sic*', so the library subdirectory must be named appropriately. See [Section 9.1.2 \[C Header Files\]](#), [page 52](#).

```

$ mkdir sic
$ mkdir sic/sic
$ cd sic/sic

```

I will describe the files I add in this section in more detail than the project specific sources, because they comprise an infrastructure that I use relatively unchanged for all of my GNU Autotools projects. You could keep an archive of these files, and use them as a starting point each time you begin a new project of your own.

#### 9.2.1.1 Error Management

A good place to start with any project design is the error management facility. In Sic I will use a simple group of functions to display simple error messages. Here is '*sic/error.h*':

```

#ifndef SIC_ERROR_H
#define SIC_ERROR_H 1

#include <sic/common.h>

BEGIN_C_DECLS

extern const char *program_name;
extern void set_program_name (const char *argv0);

extern void sic_warning      (const char *message);
extern void sic_error        (const char *message);
extern void sic_fatal        (const char *message);

END_C_DECLS

#endif /* !SIC_ERROR_H */

```

This header file follows the principles set out in [Section 9.1.2 \[C Header Files\]](#), page 52.

I am storing the `program_name` variable in the library that uses it, so that I can be sure that the library will build on architectures that don't allow undefined symbols in libraries<sup>8</sup>.

Keeping those preprocessor macro definitions designed to aid code portability together (in a single file), is a good way to maintain the readability of the rest of the code. For this project I will put that code in `'common.h'`:

```

#ifndef SIC_COMMON_H
#define SIC_COMMON_H 1

#if HAVE_CONFIG_H
# include <sic/config.h>
#endif

#include <stdio.h>
#include <sys/types.h>

#if STDC_HEADERS
# include <stdlib.h>
# include <string.h>
#elif HAVE_STRINGS_H
# include <strings.h>
#endif /*STDC_HEADERS*/

#if HAVE_UNISTD_H
# include <unistd.h>
#endif

#if HAVE_ERRNO_H

```

---

<sup>8</sup> AIX and Windows being the main culprits.

```
# include <errno.h>
#endif /*HAVE_ERRNO_H*/
#ifndef errno
/* Some systems #define this! */
extern int errno;
#endif

#endif /* !SIC_COMMON_H */
```

You may recognise some snippets of code from the Autoconf manual here—in particular the inclusion of the project ‘`config.h`’, which will be generated shortly. Notice that I have been careful to conditionally include any headers which are not guaranteed to exist on every architecture. The rule of thumb here is that only ‘`stdio.h`’ is ubiquitous (though I have never heard of a machine that has no ‘`sys/types.h`’). You can find more details of some of these in [section “Existing Tests” in \*The GNU Autoconf Manual\*](#).

Here is a little more code from ‘`common.h`’:

```
#ifndef EXIT_SUCCESS
# define EXIT_SUCCESS 0
# define EXIT_FAILURE 1
#endif
```

The implementation of the error handling functions goes in ‘`error.c`’ and is very straightforward:

```
#if HAVE_CONFIG_H
# include <sic/config.h>
#endif

#include "common.h"
#include "error.h"

static void error (int exit_status, const char *mode,
                  const char *message);

static void
error (int exit_status, const char *mode, const char *message)
{
    fprintf (stderr, "%s: %s: %s.\n", program_name, mode, message);

    if (exit_status >= 0)
        exit (exit_status);
}

void
sic_warning (const char *message)
{
    error (-1, "warning", message);
}
```

```

void
sic_error (const char *message)
{
    error (-1, "ERROR", message);
}

void
sic_fatal (const char *message)
{
    error (EXIT_FAILURE, "FATAL", message);
}

```

I also need a definition of `program_name`; `set_program_name` copies the filename component of `path` into the exported data, `program_name`. The `xstrdup` function just calls `strdup`, but aborts if there is not enough memory to make the copy:

```

const char *program_name = NULL;

void
set_program_name (const char *path)
{
    if (!program_name)
        program_name = xstrdup (basename (path));
}

```

### 9.2.1.2 Memory Management

A useful idiom common to many GNU projects is to wrap the memory management functions to localise *out of memory handling*, naming them with an ‘x’ prefix. By doing this, the rest of the project is relieved of having to remember to check for ‘NULL’ returns from the various memory functions. These wrappers use the `error` API to report memory exhaustion and abort the program. I have placed the implementation code in ‘`xmalloc.c`’:

```

#if HAVE_CONFIG_H
# include <sic/config.h>
#endif

#include "common.h"
#include "error.h"

void *
xmalloc (size_t num)
{
    void *new = malloc (num);
    if (!new)
        sic_fatal ("Memory exhausted");
    return new;
}

```



```

void *
xrealloc (void *p, size_t num)
{
    void *new;

    if (!p)
        return xmalloc (num);

    new = realloc (p, num);
    if (!new)
        sic_fatal ("Memory exhausted");

    return new;
}

void *
xcalloc (size_t num, size_t size)
{
    void *new = xmalloc (num * size);
    bzero (new, num * size);
    return new;
}

```

Notice in the code above, that `xcalloc` is implemented in terms of `xmalloc`, since `calloc` itself is not available in some older C libraries. Also, the `bzero` function is actually deprecated in favour of `memset` in modern C libraries – I’ll explain how to take this into account later in [Section 9.2.3 \[Beginnings of a `configure.in` for Small Project\]](#), page 68.

Rather than create a separate ‘`xmalloc.h`’ file, which would need to be `#included` from almost everywhere else, the logical place to declare these functions is in ‘`common.h`’, since the wrappers will be called from most everywhere else in the code:

```

#ifdef __cplusplus
# define BEGIN_C_DECLS      extern "C" {
# define END_C_DECLS        }
#else
# define BEGIN_C_DECLS
# define END_C_DECLS
#endif

#define XCALLOC(type, num) \
    ((type *) xalloc ((num), sizeof(type))) \
#define XMALLOC(type, num) \
    ((type *) xmalloc ((num) * sizeof(type))) \
#define XREALLOC(type, p, num) \
    ((type *) xrealloc ((p), (num) * sizeof(type))) \
#define XFREE(stale) \
    do { \
        if (stale) { free (stale); stale = 0; } \
    } while (0)

```

```

BEGIN_C_DECLS

extern void *xcalloc      (size_t num, size_t size);
extern void *xmalloc      (size_t num);
extern void *xrealloc     (void *p, size_t num);
extern char *xstrdup      (const char *string);
extern char *xstrerror    (int errnum);

END_C_DECLS

```

By using the macros defined here, allocating and freeing heap memory is reduced from:

```

char **argv = (char **) xmalloc (sizeof (char *) * 3);
do_stuff (argv);
if (argv)
    free (argv);

```

to the simpler and more readable:

```

char **argv = XMALLOC (char *, 3);
do_stuff (argv);
XFREE (argv);

```

In the same spirit, I have borrowed ‘xstrdup.c’ and ‘xstrerror.c’ from project GNU’s libiberty. See [Section 9.1.5 \[Fallback Function Implementations\]](#), page 54.

### 9.2.1.3 Generalised List Data Type

In many C programs you will see various implementations and re-implementations of lists and stacks, each tied to its own particular project. It is surprisingly simple to write a catch-all implementation, as I have done here with a generalised list operation API in ‘list.h’:

```

#ifndef SIC_LIST_H
#define SIC_LIST_H 1

#include <sic/common.h>

BEGIN_C_DECLS

typedef struct list {
    struct list *next;    /* chain forward pointer*/
    void *userdata;       /* incase you want to use raw Lists */
} List;

extern List *list_new      (void *userdata);
extern List *list_cons     (List *head, List *tail);
extern List *list_tail     (List *head);
extern size_t list_length  (List *head);

END_C_DECLS

```

```
#endif /* !SIC_LIST_H */
```

The trick is to ensure that any structures you want to chain together have their forward pointer in the first field. Having done that, the generic functions declared above can be used to manipulate any such chain by casting it to `List *` and back again as necessary.

For example:

```
struct foo {
    struct foo *next;

    char *bar;
    struct baz *qux;
    ...
};

...
struct foo *foo_list = NULL;

foo_list = (struct foo *) list_cons ((List *) new_foo (),
                                     (List *) foo_list);
...
```

The implementation of the list manipulation functions is in ‘list.c’:

```
#include "list.h"

List *
list_new (void *userdata)
{
    List *new = XMALLOC (List, 1);

    new->next = NULL;
    new->userdata = userdata;

    return new;
}

List *
list_cons (List *head, List *tail)
{
    head->next = tail;
    return head;
}

List *
list_tail (List *head)
{
    return head->next;
}

size_t
```

```
list_length (List *head)
{
    size_t n;

    for (n = 0; head; ++n)
        head = head->next;

    return n;
}
```

## 9.2.2 Library Implementation

In order to set the stage for later chapter which expand upon this example, in this subsection I will describe the purpose of the sources that combine to implement the shell library. I will not dissect the code introduced here—you can download the sources from the book’s webpages at <http://sources.redhat.com/autobook/>.

The remaining sources for the library, beyond the support files described in the previous subsection, are divided into four pairs of files:

### 9.2.2.1 ‘sic.c’ & ‘sic.h’

Here are the functions for creating and managing sic parsers.

```
#ifndef SIC_SIC_H
#define SIC_SIC_H 1

#include <sic/common.h>
#include <sic/error.h>
#include <sic/list.h>
#include <sic/syntax.h>

typedef struct sic {
    char *result;           /* result string */
    size_t len;             /* bytes used by result field */
    size_t lim;             /* bytes allocated to result field */
    struct builtintab *builtins; /* tables of builtin functions */
    SyntaxTable **syntax;    /* dispatch table for syntax of input */
    List *syntax_init;       /* stack of syntax state initialisers */
    List *syntax_finish;     /* stack of syntax state finalizers */
    SicState *state;         /* state data from syntax extensions */
} Sic;

#endif /* !SIC_SIC_H */
```

This structure has fields to store registered command (**builtins**) and syntax (**syntax**) handlers, along with other state information (**state**) that can be used to share information between various handlers, and some room to build a result or error string (**result**).

### 9.2.2.2 ‘builtin.c’ & ‘builtin.h’

Here are the functions for managing tables of builtin commands in each Sic structure:

```
typedef int (*builtin_handler) (Sic *sic,
                               int argc, char *const argv[]);

typedef struct {
    const char *name;
    builtin_handler func;
    int min, max;
} Builtin;

typedef struct builtintab BuiltinTab;

extern Builtin *builtin_find (Sic *sic, const char *name);
extern int builtin_install (Sic *sic, Builtin *table);
extern int builtin_remove (Sic *sic, Builtin *table);
```

### 9.2.2.3 ‘eval.c’ & ‘eval.h’

Having created a Sic parser, and populated it with some Builtin handlers, a user of this library must tokenize and evaluate its input stream. These files define a structure for storing tokenized strings (Tokens), and functions for converting char \* strings both to and from this structure type:

```
#ifndef SIC_EVAL_H
#define SIC_EVAL_H 1

#include <sic/common.h>
#include <sic/sic.h>

BEGIN_C_DECLS

typedef struct {
    int argc;           /* number of elements in ARGV */
    char **argv;        /* array of pointers to elements */
    size_t lim;         /* number of bytes allocated */
} Tokens;

extern int eval (Sic *sic, Tokens *tokens);
extern int untokenize (Sic *sic, char **pcommand, Tokens *tokens);
extern int tokenize (Sic *sic, Tokens **ptokens, char **pcommand);

END_C_DECLS

#endif /* !SIC_EVAL_H */
```

These files also define the `eval` function, which examines a `Tokens` structure in the context of the given `Sic` parser, dispatching the `argv` array to a relevant `Builtin` handler, also written by the library user.

#### 9.2.2.4 ‘syntax.c’ & ‘syntax.h’

When `tokenize` splits a `char *` string into parts, by default it breaks the string into words delimited by whitespace. These files define the interface for changing this default behaviour, by registering callback functions which the parser will run when it meets an ‘interesting’ symbol in the input stream. Here are the declarations from ‘syntax.h’:

```
BEGIN_C_DECLS

typedef int SyntaxHandler (struct sic *sic, BufferIn *in,
                          BufferOut *out);

typedef struct syntax {
    SyntaxHandler *handler;
    char *ch;
} Syntax;

extern int syntax_install (struct sic *sic, Syntax *table);
extern SyntaxHandler *syntax_handler (struct sic *sic, int ch);

END_C_DECLS
```

A `SyntaxHandler` is a function called by `tokenize` as it consumes its input to create a `Tokens` structure; the two functions associate a table of such handlers with a given `Sic` parser, and find the particular handler for a given character in that `Sic` parser, respectively.

#### 9.2.3 Beginnings of a ‘configure.in’

Now that I have some code, I can run `autoscan` to generate a preliminary ‘configure.in’. `autoscan` will examine all of the sources in the current directory tree looking for common points of non-portability, adding macros suitable for detecting the discovered problems. `autoscan` generates the following in ‘configure.scan’:

```
# Process this file with autoconf to produce a configure script.
AC_INIT(sic/eval.h)

# Checks for programs.

# Checks for libraries.

# Checks for header files.
AC_HEADER_STDC
AC_CHECK_HEADERS(strings.h unistd.h)

# Checks for typedefs, structures, and compiler characteristics.
AC_C_CONST
```

```
AC_TYPE_SIZE_T
```

```
# Checks for library functions.
```

```
AC_FUNC_VPRINTF
```

```
AC_CHECK_FUNCS(strerror)
```

```
AC_OUTPUT()
```

Since the generated ‘`configure.scan`’ does not overwrite your project’s ‘`configure.in`’, it is a good idea to run `autoscan` periodically even in established project source trees, and compare the two files. Sometimes `autoscan` will find some portability issue you have overlooked, or weren’t aware of.

Looking through the documentation for the macros in this ‘`configure.scan`’, `AC_C_CONST` and `AC_TYPE_SIZE_T` will take care of themselves (provided I ensure that ‘`config.h`’ is included into every source file), and `AC_HEADER_STDC` and `AC_CHECK_HEADERS(unistd.h)` are already taken care of in ‘`common.h`’.

`autoscan` is no silver bullet! Even here in this simple example, I need to manually add macros to check for the presence of ‘`errno.h`’:

```
AC_CHECK_HEADERS(errno.h strings.h unistd.h)
```

I also need to manually add the Autoconf macro for generating ‘`config.h`’; a macro to initialise `automake` support; and a macro to check for the presence of `ranlib`. These should go close to the start of ‘`configure.in`’:

```
...
AC_CONFIG_HEADER(config.h)
AM_INIT_AUTOMAKE(sic, 0.5)
```

```
AC_PROG_CC
AC_PROG_RANLIB
```

```
...
```

Recall that the use of `bzero` in [Section 9.2.1.2 \[Memory Management\]](#), page 62 is not entirely portable. The trick is to provide a `bzero` work-alike, depending on which functions Autoconf detects, by adding the following towards the end of ‘`configure.in`’:

```
...
AC_CHECK_FUNCS(bzero memset, break)
...
```

With the addition of this small snippet of code to ‘`common.h`’, I can now make use of `bzero` even when linking with a C library that has no implementation of its own:

```
#if !HAVE_BZERO && HAVE_MEMSET
# define bzero(buf, bytes)      ((void) memset (buf, 0, bytes))
#endif
```

An interesting macro suggested by `autoscan` is `AC_CHECK_FUNCS(strerror)`. This tells me that I need to provide a replacement implementation of `strerror` for the benefit of architectures which don’t have it in their system libraries. This is resolved by providing a file with a fallback implementation for the named function, and creating a library from

it and any others that ‘configure’ discovers to be lacking from the system library on the target host.

You will recall that ‘configure’ is the shell script the end user of this package will run on their machine to test that it has all the features the package wants to use. The library that is created will allow the rest of the project to be written in the knowledge that any functions required by the project but missing from the installers system libraries will be available nonetheless. GNU ‘libiberty’ comes to the rescue again – it already has an implementation of ‘strerror.c’ that I was able to use with a little modification.

Being able to supply a simple implementation of `strerror`, as the ‘strerror.c’ file from ‘libiberty’ does, relies on there being a well defined `sys_errlist` variable. It is a fair bet that if the target host has no `strerror` implementation, however, that the system `sys_errlist` will be broken or missing. I need to write a configure macro to check whether the system defines `sys_errlist`, and tailor the code in ‘strerror.c’ to use this knowledge.

To avoid clutter in the top-level directory, I am a great believer in keeping as many of the configuration files as possible in their own sub-directory. First of all, I will create a new directory called ‘config’ inside the top-level directory, and put ‘sys\_errlist.m4’ inside it:

```
AC_DEFUN(SIC_VAR_SYS_ERRLIST,
[AC_CACHE_CHECK([for sys_errlist],
sic_cv_var_sys_errlist,
[AC_TRY_LINK([int *p;], [extern int sys_errlist; p = &sys_errlist;],
sic_cv_var_sys_errlist=yes, sic_cv_var_sys_errlist=no)])
if test x"$sic_cv_var_sys_errlist" = xyes; then
AC_DEFINE(HAVE_SYS_ERRLIST, 1,
[Define if your system libraries have a sys_errlist variable.])
fi])
```

I must then add a call to this new macro in the ‘configure.in’ file being careful to put it in the right place – somewhere between *typedefs and structures* and *library functions* according to the comments in ‘configure.scan’:

```
SIC_VAR_SYS_ERRLIST
```

GNU Autotools can also be set to store most of their files in a subdirectory, by calling the `AC_CONFIG_AUX_DIR` macro near the top of ‘configure.in’, preferably right after `AC_INIT`:

```
AC_INIT(sic/eval.c)
AC_CONFIG_AUX_DIR(config)
AM_CONFIG_HEADER(config.h)
...
```

Having made this change, many of the files added by running `autoconf` and `automake --add-missing` will be put in the `aux_dir`.

The source tree now looks like this:

```
sic/
+-- configure.scan
+-- config/
|   +-- sys_errlist.m4
+-- replace/
|   +-- strerror.c
```



```

+-- sic/
    +-- builtin.c
    +-- builtin.h
    +-- common.h
    +-- error.c
    +-- error.h
    +-- eval.c
    +-- eval.h
    +-- list.c
    +-- list.h
    +-- sic.c
    +-- sic.h
    +-- syntax.c
    +-- syntax.h
    +-- xmalloc.c
    +-- xstrdup.c
    +-- xstrerror.c

```

In order to correctly utilise the fallback implementation, `AC_CHECK_FUNCS(strerror)` needs to be removed and `strerror` added to `AC_REPLACE_FUNCS`:

```

# Checks for library functions.
AC_REPLACE_FUNCS(strerror)

```

This will be clearer if you look at the ‘`Makefile.am`’ for the ‘`replace`’ subdirectory:

```

## Makefile.am -- Process this file with automake to produce Makefile.in

INCLUDES                = -I$(top_builddir) -I$(top_srcdir)

noinst_LIBRARIES        = libreplace.a
libreplace_a_SOURCES    =
libreplace_a_LIBADD     = @LIBOBJS@

```

The code tells `automake` that I want to build a library for use within the build tree (i.e. not installed – ‘`noinst`’), and that has no source files by default. The clever part here is that when someone comes to install Sic, they will run `configure` which will test for `strerror`, and add ‘`strerror.o`’ to `LIBOBJS` if the target host environment is missing its own implementation. Now, when ‘`configure`’ creates ‘`replace/Makefile`’ (as I asked it to with `AC_OUTPUT`), ‘`@LIBOBJS@`’ is replaced by the list of objects required on the installer’s machine.

Having done all this at configure time, when my user runs `make`, the files required to replace functions missing from their target machine will be added to ‘`libreplace.a`’.

Unfortunately this is not quite enough to start building the project. First I need to add a top-level ‘`Makefile.am`’ from which to ultimately create a top-level ‘`Makefile`’ that will descend into the various subdirectories of the project:

```

## Makefile.am -- Process this file with automake to produce Makefile.in

SUBDIRS = replace sic

```

And ‘`configure.in`’ must be told where it can find instances of `Makefile.in`:

```
AC_OUTPUT(Makefile replace/Makefile sic/Makefile)
```

I have written a bootstrap script for Sic, for details see [Chapter 8 \[Bootstrapping\]](#), [page 49](#):

```
#!/bin/sh

set -x
aclocal -I config
autoheader
automake --foreign --add-missing --copy
autoconf
```

The ‘--foreign’ option to automake tells it to relax the GNU standards for various files that should be present in a GNU distribution. Using this option saves me from having to create empty files as we did in [Chapter 5 \[A Minimal GNU Autotools Project\]](#), [page 29](#).

Right. Let’s build the library! First, I’ll run bootstrap:

```
$ ./bootstrap
+ aclocal -I config
+ autoheader
+ automake --foreign --add-missing --copy
automake: configure.in: installing config/install-sh
automake: configure.in: installing config/mkinstalldirs
automake: configure.in: installing config/missing
+ autoconf
```

The project is now in the same state that an end-user would see, having unpacked a distribution tarball. What follows is what an end user might expect to see when building from that tarball:

```
$ ./configure
creating cache ./config.cache
checking for a BSD compatible install... /usr/bin/install -c
checking whether build environment is sane... yes
checking whether make sets ${MAKE}... yes
checking for working aclocal... found
checking for working autoconf... found
checking for working automake... found
checking for working autoheader... found
checking for working makeinfo... found
checking for gcc... gcc
checking whether the C compiler (gcc ) works... yes
checking whether the C compiler (gcc ) is a cross-compiler... no
checking whether we are using GNU C... yes
checking whether gcc accepts -g... yes
checking for ranlib... ranlib
checking how to run the C preprocessor... gcc -E
checking for ANSI C header files... yes
checking for unistd.h... yes
checking for errno.h... yes
checking for string.h... yes
```

```

checking for working const... yes
checking for size_t... yes
checking for strerror... yes
updating cache ./config.cache
creating ./config.status
creating Makefile
creating replace/Makefile
creating sic/Makefile
creating config.h

```

Compare this output with the contents of ‘`configure.in`’, and notice how each macro is ultimately responsible for one or more consecutive tests (via the Bourne shell code generated in ‘`configure`’). Now that the ‘`Makefile`’s have been successfully created, it is safe to call `make` to perform the actual compilation:

```

$ make
make all-recursive
make[1]: Entering directory '/tmp/sic'
Making all in replace
make[2]: Entering directory '/tmp/sic/replace'
rm -f libreplace.a
ar cru libreplace.a
ranlib libreplace.a
make[2]: Leaving directory '/tmp/sic/replace'
Making all in sic
make[2]: Entering directory '/tmp/sic/sic'
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c builtin.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c error.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c eval.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c list.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c sic.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c syntax.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c xmalloc.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c xstrdup.c
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -g -O2 -c xstrerror.c
rm -f libsic.a
ar cru libsic.a builtin.o error.o eval.o list.o sic.o syntax.o xmalloc.o
xstrdup.o xstrerror.o
ranlib libsic.a
make[2]: Leaving directory '/tmp/sic/sic'
make[1]: Leaving directory '/tmp/sic'

```

On this machine, as you can see from the output of `configure` above, I have no need of the fallback implementation of `strerror`, so ‘`libreplace.a`’ is empty. On another machine this might not be the case. In any event, I now have a compiled ‘`libsic.a`’ – so far, so good.

## 9.3 A Sample Shell Application

What I need now, is a program that uses ‘`libsic.a`’, if only to give me confidence that it is working. In this section, I will write a simple shell which uses the library. But first, I’ll create a directory to put it in:

```
$ mkdir src
$ ls -F
COPYING  Makefile.am  aclocal.m4  configure*  config/  sic/
INSTALL  Makefile.in  bootstrap*  configure.in  replace/  src/
$ cd src
```

In order to put this shell together, we need to provide just a few things for integration with ‘`libsic.a`’...

### 9.3.1 ‘`sic_repl.c`’

In ‘`sic_repl.c`’<sup>9</sup> there is a loop for reading strings typed by the user, evaluating them and printing the results. GNU readline is ideally suited to this, but it is not always available – or sometimes people simply may not wish to use it.

With the help of GNU Autotools, it is very easy to cater for building with and without GNU readline. ‘`sic_repl.c`’ uses this function to read lines of input from the user:

```
static char *
getline (FILE *in, const char *prompt)
{
    static char *buf = NULL;          /* Always allocated and freed
                                       from inside this function. */

    XFREE (buf);

    buf = (char *) readline ((char *) prompt);

#ifdef HAVE_ADD_HISTORY
    if (buf && *buf)
        add_history (buf);
#endif

    return buf;
}
```

To make this work, I must write an Autoconf macro which adds an option to ‘`configure`’, so that when the package is installed, it will use the readline library if ‘`--with-readline`’ is used:

```
AC_DEFUN(SIC_WITH_READLINE,
[AC_ARG_WITH(readline,
[ --with-readline      compile with the system readline library],
[if test x"${withval-no}" != xno; then
    sic_save_LIBS=$LIBS
    AC_CHECK_LIB(readline, readline)
```

---

<sup>9</sup> Read Eval Print Loop.

```

    if test x"${ac_cv_lib_readline_readline}" = xno; then
        AC_MSG_ERROR(libreadline not found)
    fi
    LIBS=$sic_save_LIBS
fi])
AM_CONDITIONAL(WITH_READLINE, test x"${with_readline-no}" != xno)
])

```

Having put this macro in the file ‘config/readline.m4’, I must also call the new macro (SIC\_WITH\_READLINE) from ‘configure.in’.

### 9.3.2 ‘sic\_syntax.c’

The syntax of the commands in the shell I am writing is defined by a set of syntax handlers which are loaded into ‘libsic’ at startup. I can get the C preprocessor to do most of the repetitive code for me, and just fill in the function bodies:

```

#ifdef HAVE_CONFIG_H
# include <sic/config.h>
#endif

#include "sic.h"

/* List of builtin syntax. */
#define syntax_functions \
    SYNTAX(escape, "\\") \
    SYNTAX(space, " \f\n\r\t\v") \
    SYNTAX(comment, "#") \
    SYNTAX(string, "\"") \
    SYNTAX(endcmd, ";") \
    SYNTAX(endstr, "")

/* Prototype Generator. */
#define SIC_SYNTAX(name) \
    int name (Sic *sic, BufferIn *in, BufferOut *out)

#define SYNTAX(name, string) \
    extern SIC_SYNTAX (CONC (syntax_, name));
syntax_functions
#undef SYNTAX

/* Syntax handler mappings. */
Syntax syntax_table[] = {

#define SYNTAX(name, string) \
    { CONC (syntax_, name), string },
    syntax_functions
#undef SYNTAX

    { NULL, NULL }

```

```
};
```

This code writes the prototypes for the syntax handler functions, and creates a table which associates each with one or more characters that might occur in the input stream. The advantage of writing the code this way is that when I want to add a new syntax handler later, it is a simple matter of adding a new row to the `syntax_functions` macro, and writing the function itself.

### 9.3.3 ‘sic\_builtin.c’

In addition to the syntax handlers I have just added to the Sic shell, the language of this shell is also defined by the builtin commands it provides. The infrastructure for this file is built from a table of functions which is fed into various C preprocessor macros, just as I did for the syntax handlers.

One builtin handler function has special status, `builtin_unknown`. This is the builtin that is called, if the Sic library cannot find a suitable builtin function to handle the current input command. At first this doesn’t sound especially important – but it is the key to any shell implementation. When there is no builtin handler for the command, the shell will search the users command path, ‘\$PATH’, to find a suitable executable. And this is the job of `builtin_unknown`:

```
int
builtin_unknown (Sic *sic, int argc, char *const argv[])
{
    char *path = path_find (argv[0]);
    int status = SIC_ERROR;

    if (!path)
    {
        sic_result_append (sic, "command \"");
        sic_result_append (sic, argv[0]);
        sic_result_append (sic, "\" not found");
    }
    else if (path_execute (sic, path, argv) != SIC_OKAY)
    {
        sic_result_append (sic, "command \"");
        sic_result_append (sic, argv[0]);
        sic_result_append (sic, "\" failed: ");
        sic_result_append (sic, strerror (errno));
    }
    else
        status = SIC_OKAY;

    return status;
}

static char *
path_find (const char *command)
{
```

```

char *path = xstrdup (command);

if (*command == '/')
{
    if (access (command, X_OK) < 0)
        goto notfound;
}
else
{
    char *PATH = getenv ("PATH");
    char *pbeg, *pend;
    size_t len;

    for (pbeg = PATH; *pbeg != '\0'; pbeg = pend)
    {
        pbeg += strspn (pbeg, ":");
        len = strcspn (pbeg, ":");
        pend = pbeg + len;
        path = XREALLOC (char, path, 2 + len + strlen(command));
        *path = '\0';
        strncat (path, pbeg, len);
        if (path[len-1] != '/') strcat (path, "/");
        strcat (path, command);

        if (access (path, X_OK) == 0)
            break;
    }

    if (*pbeg == '\0')
        goto notfound;
}

return path;

notfound:
XFREE (path);
return NULL;
}

```

Running ‘autoscan’ again at this point adds `AC_CHECK_FUNCS(strcspn strspn)` to ‘configure.scan’. This tells me that these functions are not truly portable. As before I provide fallback implementations for these functions in case they are missing from the target host – and as it turns out, they are easy to write:

```

/* strcspn.c -- implement strcspn() for architectures without it */

#ifdef HAVE_CONFIG_H
# include <sic/config.h>
#endif

```

```

#include <sys/types.h>

#if STDC_HEADERS
# include <string.h>
#elif HAVE_STRINGS_H
# include <strings.h>
#endif

#if !HAVE_STRCHR
# ifndef strchr
#   define strchr index
# endif
#endif

size_t
strcspn (const char *string, const char *reject)
{
    size_t count = 0;
    while (strchr (reject, *string) == 0)
        ++count, ++string;

    return count;
}

```

There is no need to add any code to ‘`Makefile.am`’, because the `configure` script will automatically add the names of the missing function sources to ‘`@LIBOBJ@`’.

This implementation uses the `autoconf` generated ‘`config.h`’ to get information about the availability of headers and type definitions. It is interesting that `autoscan` reports that `strchr` and `strrchr`, which are used in the fallback implementations of `strcspn` and `strspn` respectively, are themselves not portable! Luckily, the `Autoconf` manual tells me exactly how to deal with this: by adding some code to my ‘`common.h`’ (paraphrased from the literal code in the manual):

```

#if !STDC_HEADERS
# if !HAVE_STRCHR
#   define strchr index
#   define strrchr rindex
# endif
#endif

```

And another macro in ‘`configure.in`’:

```
AC_CHECK_FUNCS(strchr strrchr)
```

### 9.3.4 ‘`sic.c`’ & ‘`sic.h`’

Since the application binary has no installed header files, there is little point in maintaining a corresponding header file for every source, all of the structures shared by these files, and non-static functions in these files are declared in ‘`sic.h`’:



```

#ifndef SIC_H
#define SIC_H 1

#include <sic/common.h>
#include <sic/sic.h>
#include <sic/builtin.h>

BEGIN_C_DECLS

extern Syntax syntax_table[];
extern Builtin builtin_table[];
extern Syntax syntax_table[];

extern int evalstream      (Sic *sic, FILE *stream);
extern int evalline       (Sic *sic, char **pline);
extern int source         (Sic *sic, const char *path);
extern int syntax_init    (Sic *sic);
extern int syntax_finish  (Sic *sic, BufferIn *in, BufferOut *out);

END_C_DECLS

#endif /* !SIC_H */

```

To hold together everything you have seen so far, the `main` function creates a Sic parser and initialises it by adding syntax handler functions and builtin functions from the two tables defined earlier, before handing control to `evalstream` which will eventually exit when the input stream is exhausted.

```

int
main (int argc, char * const argv[])
{
    int result = EXIT_SUCCESS;
    Sic *sic = sic_new ();

    /* initialise the system */
    if (sic_init (sic) != SIC_OKAY)
        sic_fatal ("sic initialisation failed");
    signal (SIGINT, SIG_IGN);
    setbuf (stdout, NULL);

    /* initial symbols */
    sicstate_set (sic, "PS1", "]" , NULL);
    sicstate_set (sic, "PS2", "- " , NULL);

    /* evaluate the input stream */
    evalstream (sic, stdin);

    exit (result);
}

```

Now, the shell can be built and used:

```
$ bootstrap
...
$ ./configure --with-readline
...
$ make
...
make[2]: Entering directory '/tmp/sic/src'
gcc -DHAVE_CONFIG_H -I. -I.. -I../sic -I.. -I../sic -g -c sic.c
gcc -DHAVE_CONFIG_H -I. -I.. -I../sic -I.. -I../sic -g -c sic_builtin.c
gcc -DHAVE_CONFIG_H -I. -I.. -I../sic -I.. -I../sic -g -c sic_repl.c
gcc -DHAVE_CONFIG_H -I. -I.. -I../sic -I.. -I../sic -g -c sic_syntax.c
gcc -g -O2 -o sic sic.o sic_builtin.o sic_repl.o sic_syntax.o \
../sic/libsic.a ../replace/libreplace.a -lreadline
make[2]: Leaving directory '/tmp/sic/src'
...
$ ./src/sic
] pwd
/tmp/sic
] ls -F
Makefile      aclocal.m4    config.cache   configure*     sic/
Makefile.am   bootstrap*    config.log     configure.in   src/
Makefile.in   config/       config.status* replace/
] exit
$
```

This chapter has developed a solid foundation of code, which I will return to in [Chapter 12 \[A Large GNU Autotools Project\]](#), page 123, when Libtool will join the fray. The chapters leading up to that explain what Libtool is for, how to use it and integrate it into your own projects, and the advantages it offers over building shared libraries with Automake (or even just Make) alone.

## 10 Introducing GNU Libtool

Libtool takes care of all the peculiarities of creating, linking and loading shared and static libraries across a great number of platforms, providing a uniform command line interface to the developer. By using Libtool to manage your project libraries, you only need to concern yourself with *Libtool's* interface: when someone else builds your project on a platform with a different library architecture, Libtool invokes that platform's compiler and linker with the correct environment and command line switches. It will install libraries and library using binaries according to the conventions of the host platform, and follows that platform's rules for library versioning and library interdependencies.

Libtool empowers you to treat a library as an implementation of a well defined interface of your choosing. This *Libtool library* may be manifest as a collection of compiler objects, a static `ar` archive, or a position independent runtime loadable object. By definition, native libraries are fully supported by Libtool since they are an implementation detail of the Libtool library abstraction. It's just that until Libtool achieves complete world domination, you might need to bear in mind what is going on behind the command line interface when you first add Libtool support to your project.

The sheer number of uses of the word 'library' in this book could be easily very confusing. In this chapter and throughout the rest of the book, I will refer to various kinds of libraries as follows:

- 'native'      Low level libraries, that is, libraries provided by the host architecture.
- 'Libtool library'      The kind of library built by Libtool. This encompasses both the shared and static native components of the implementation of the named library.
- 'pseudo-library'      The high level '`.la`' file produced by Libtool. The 'pseudo-library' is not a library in its own right, but is treated as if it were from outside the Libtool interface.

Furthermore, in the context of Libtool, there is another subtle (but important) distinction to be drawn:

- 'static *library*'      A Libtool library which has no shared archive component.
- 'static *archive*'      The static component of a Libtool library.

Many developers use Libtool as a black box which requires adding a few macros to '`configure.in`' and tweaking a project's '`Makefile.am`'. The next chapter addresses that school of thought in more detail. In this chapter I will talk a little about the inner workings of Libtool, and show you how it can be used directly from your shell prompt – how to build various kinds of library, and how those libraries can be used by an application. Before you can do any of this, you need to create a `libtool` script that is tailored to the platform you are using it from.

## 10.1 Creating libtool

When you install a distribution of Libtool on your development machine, a host specific `libtool` program is installed. The examples in the rest of this chapter use this installed instance of `libtool`.

When you start to use Libtool in the build process of your own projects, you shouldn't require that `libtool` be installed on the user's machine, particularly since they may have a different `libtool` version to the one used to develop your project. Instead, distribute some of the files installed by the Libtool distribution along with your project, and custom build a `libtool` script on the user's machine before invoking `./libtool` to build any objects. If you use Autoconf and Automake, these details are taken care of automatically (see [Chapter 11 \[Using GNU Libtool with configure.in and Makefile.am\]](#), page 103). Otherwise you should copy the following files from your own Libtool installation into the source tree of your own project:

```
$ ls /usr/local/share/libtool
config.guess  config.sub  libltdl  ltconfig  ltmain.in
$ cp /usr/local/share/libtool/config.* /usr/local/share/libtool/lt* .
$ ls
config.guess  config.sub  ltconfig  ltmain.in
```

You must then arrange for your project build process to create an instance of `libtool` on the user's machine, so that it is dependent on their target system and not your development machine. The creation process requires the four files you just added to your project. Let's create a `libtool` instance by hand, so that you can see what is involved:

```
$ ./config.guess
hppa1.1-hp-hpux10.20
```

```

$ ./ltconfig --disable-static --with-gcc ./ltmain.sh hppa1.1-hp-hpux10.20
checking host system type... hppa1.1-hp-hpux10.20
checking build system type... hppa1.1-hp-hpux10.20
checking whether ln -s works... yes
checking for ranlib... ranlib
checking for BSD-compatible nm... /usr/bin/nm -p
checking for strip... strip
checking for gcc... gcc
checking whether we are using GNU C... yes
checking for objdir... .libs
checking for object suffix... o
checking for executable suffix... no
checking for gcc option to produce PIC... -fPIC
checking if gcc PIC flag -fPIC works... yes
checking if gcc static flag -static works... yes
checking if gcc supports -c -o file.o... yes
checking if gcc supports -c -o file.lo... yes
checking if gcc supports -fno-rtti -fno-exceptions ... no
checking for ld used by GCC... /opt/gcc-lib/hp821/2.7.0/ld
checking if the linker (/opt/gcc-lib/hp821/2.7.0/ld) is GNU ld... no
checking whether the linker (/opt/gcc-lib/hp821/2.7.0/ld) supports \
shared libraries... yes
checking how to hardcode library paths into programs... relink
checking whether stripping libraries is possible... yes
checking for /opt/gcc-lib/hp821/2.7.0/ld option to reload object \
files... -r
checking dynamic linker characteristics... hpux10.20 dld.sl
checking command to parse /usr/bin/nm -p output... ok
checking if libtool supports shared libraries... yes
checking whether to build shared libraries... yes
checking whether to build static libraries... yes
creating libtool
$ ls
config.guess  config.sub  ltconfig
config.log    libtool     ltmain.sh
$ ./libtool --version
ltmain.sh (GNU libtool) 1.3c (1.629 1999/11/02 12:33:04)

```

The examples in this chapter are all performed on a HP-UX system, but the principles depicted are representative of any of the platforms to which Libtool has been ported (see [Appendix B \[PLATFORMS\]](#), page 307).

Often you don't need to specify any options, and if you omit the configuration triplet (see [Section 3.4 \[Configuration Names\]](#), page 23), `ltconfig` will run `config.guess` itself. There are several options you can specify which affect the generated `libtool`. See [section "Invoking ltconfig" in \*The Libtool Manual\*](#). Unless your project has special requirements, you can usually use the simplified:

```
$ ./ltconfig ./ltmain.sh
```

With the current release of Libtool, you must be careful that `$CC` is set to the same value when you call `ltconfig` as when you invoke the `libtool` it generates, otherwise

`libtool` will use the compiler specified in ‘`$CC`’ currently, but with the semantics probed by `ltconfig` for the compiler specified in ‘`$CC`’ at the time *it* was executed.

## 10.2 The Libtool Library

A Libtool library is built from Libtool objects in the same way that a native (non-Libtool) library is built from native objects. Building a Libtool library with `libtool` is as easy as building an old style static archive. Generally, each of the sources is compiled to a *Libtool object*, and then these objects are combined to create the library.

If you want to try this to see what `libtool` does on your machine, put the following code in a file ‘`hello.c`’, in a directory of its own, and run the example shell commands from there:

```
#include <stdio.h>

void
hello (char *who)
{
    printf ("Hello, %s!\n", who);
}
```

The traditional way to make a (native) static library is as follows:

```
$ gcc -c hello.c
$ ls
hello.c  hello.o
$ ar cru libhello.a hello.o
$ ranlib libhello.a
$ ls
hello.c  hello.o  libhello.a
```

Notice that even when I just want to build an old static archive, I need to know that, in common with most Unices, I have to *bless*<sup>1</sup> my library with `ranlib` to make it work optimally on HP-UX.

Essentially, Libtool supports the building of three types of library: shared libraries; static libraries; and convenience libraries. In the following sections I will talk about each in turn, but first you will need to understand how to create and use *position independent* code, as explained in the next section.

### 10.2.1 Position Independent Code

On most architectures, when you compile source code to object code, you need to specify whether the object code should be *position independent* or not. There are occasional architectures which don’t make the distinction, usually because all object code is position

---

<sup>1</sup> Generally this involves indexing the symbols exported from the archive for faster linking, and to allow the archived objects to reference symbols from other objects earlier in the same archive.

independent by virtue of the ABI<sup>2</sup>, or less often because the load address of the object is fixed at compile time (which implies that shared libraries are not supported by such a platform). If an object is compiled as position independent code (PIC), then the operating system can load the object at *any* address in preparation for execution. This involves a time overhead, in replacing direct address references with relative addresses at compile time, and a space overhead, in maintaining information to help the runtime loader fill in the unresolved addresses at runtime. Consequently, PIC objects are usually slightly larger and slower at runtime than the equivalent non-PIC object. The advantage of sharing library code on disk and in memory outweigh these problems as soon as the PIC object code in shared libraries is reused.

PIC compilation is exactly what is required for objects which will become part of a shared library. Consequently, `libtool` builds PIC objects for use in shared libraries and non-PIC objects for use in static libraries. Whenever `libtool` instructs the compiler to generate a PIC object, it also defines the preprocessor symbol, ‘PIC’, so that assembly code can be aware of whether it will reside in a PIC object or not.

Typically, as `libtool` is compiling sources, it will generate a ‘.lo’ object, as PIC, and a ‘.o’ object, as non-PIC, and then it will use the appropriate one of the pair when linking executables and libraries of various sorts. On architectures where there is no distinction, the ‘.lo’ file is just a soft link to the ‘.o’ file.

In practice, you can link PIC objects into a static archive for a small overhead in execution and load speed, and often you can similarly link non-PIC objects into shared archives. If you find that you need to do this, `libtool` provides several ways to override the default behavior (see [Section 10.1 \[Creating libtool\]](#), page 82).

## 10.2.2 Creating Shared Libraries

From Libtool’s point of view, the term ‘shared library’ is somewhat of a misnomer. Since Libtool is intended to abstract away the details of library building, it doesn’t matter whether Libtool is building a shared library or a static archive. Of course, Libtool will always try to build a shared library by default on the platforms to which it has been ported (see [Appendix B \[PLATFORMS\]](#), page 307), but will equally fall back to building a static archive if the host architecture does not support shared libraries, or if the project developer deliberately configures Libtool to always build static archives only. These libraries are more properly called ‘*Libtool libraries*’; the underlying native library will usually be a shared library, except as described above.

To create a Libtool library on my HP-UX host, or indeed anywhere else that `libtool` works, run the following commands:

```
$ rm hello.o libhello.a
$ libtool gcc -c hello.c
mkdir .libs
gcc -c -fPIC -DPIC hello.c -o .libs/hello.lo
gcc -c hello.c -o hello.o >/dev/null 2>&1
mv -f .libs/hello.lo hello.lo
```

---

<sup>2</sup> Application Binary Interface: the layout of the bytes that comprise binary objects and executables: 32 or 64 bit words; procedure calling conventions; memory alignment rules; system call interface; order and type of the binary sections (data, code etc) and so on.

```

$ ls
hello.c  hello.lo  hello.o
$ libtool gcc -rpath /usr/local/lib -o libhello.la hello.lo
rm -fr .libs/libhello.la .libs/libhello.* .libs/libhello.*
/opt/gcc-lib/hp821/2.7.0/ld -b +h libhello.sl.0 +b /usr/local/lib \
-o .libs/libhello.sl.0.0 hello.lo
(cd .libs && rm -f libhello.sl.0 && ln -s libhello.sl.0.0 libhello.sl.0)
(cd .libs && rm -f libhello.sl && ln -s libhello.sl.0.0 libhello.sl)
ar cru .libs/libhello.a hello.o
ranlib .libs/libhello.a
creating libhello.la
(cd .libs && rm -f libhello.la && ln -s ../libhello.la libhello.la)
$ ls
hello.c  hello.lo  hello.o  libhello.la

```

This example illustrates several features of `libtool`. Compare the command line syntax with the previous example (see [Section 10.2 \[The Libtool Library\]](#), page 84). They are both very similar. Notice, however, that when compiling the ‘`hello.c`’ source file, `libtool` creates *two* objects. The first, ‘`hello.lo`’, is the *Libtool object* which we use for Libtool libraries, and the second, ‘`hello.o`’ is a standard object. On HP-UX, `libtool` knows that Libtool objects should be compiled with *position independent code*, hence the extra switches when creating the first object.

When you run `libtool` from the command line, you must also specify a compiler for it to call. Similarly when you create a `libtool` script with `ltconfig`, a compiler is chosen and interrogated to discover what characteristics it has. See [Section 10.1 \[Creating libtool\]](#), page 82.

Prior to release 1.4 of Libtool, `ltconfig` probed the build machine for a suitable compiler, by searching first for `gcc` and then `cc`. The functionality of `ltconfig` is being migrated into the ‘`AC_PROG_LIBTOOL`’ macro, such that there will be no `ltconfig` script in Libtool release 1.5. The current release is part way between the two. In all cases, you can specify a particular compiler by setting the ‘`CC`’ environment variable.

It is important to continue to use the same compiler when you run `libtool` as the compiler that was used when you created the `libtool` script. If you create the script with ‘`CC`’ set to `gcc`, and subsequently try to compile using, say:

```
$ libtool c89 -rpath /usr/local/lib -c hello.c
```

`libtool` will try to call `c89` using the options it discovered for `gcc`. Needless to say, that doesn’t work!

The link command specifies a Libtool library target, ‘`libhello.la`’, compiled from a single Libtool object, ‘`hello.lo`’. Even so, `libtool` knows how to build both static and shared archives on HP-UX – underneath the `libtool` abstraction both are created. `libtool` also understands the particulars of library linking on HP-UX: the static archive, ‘`libhello.a`’, is *blessed*; the system (and compiler) dependent compiler and linker flags, versioning scheme and `.sl` extension are utilised for the shared archive, ‘`libhello.sl`’. On another host, all of these details may be completely different, yet with exactly the same invocation, `libtool` will call the native tools with the appropriate options to achieve the same result. Try it on your own machines to see any differences.



It is the ‘`-rpath`’ switch that tells `libtool` that you want to build a Libtool library (with both the shared and static components where possible). If you omit the ‘`-rpath`’ switch, `libtool` will build a convenience library instead, see [Section 10.2.4 \[Creating convenience Libraries\]](#), page 87. The ‘`-rpath`’ switch is doubly important, because it tells `libtool` that you intend to install ‘`libhello.la`’ in ‘`/usr/local/lib`’. This allows `libtool` to finalize the library correctly after installation on the architectures that need it, see [Section 10.6 \[Installing a Library\]](#), page 96.

Finally, notice that only the Libtool library, ‘`libhello.la`’, is visible after a successful link. The various files which form the local implementation details of the Libtool library are in a hidden subdirectory, but in order for the abstraction to work cleanly you shouldn’t need to worry about these too much.

### 10.2.3 Creating Static Libraries

In contrast, `libtool` will create a static library if either the ‘`-static`’ or ‘`-all-static`’ switches are specified on the link line for a Libtool library:

```
$ libtool gcc -static -o libhello.la hello.lo
rm -fr .libs/libhello.la .libs/libhello.* .libs/libhello.*
ar cru .libs/libhello.a hello.o
ranlib .libs/libhello.a
creating libhello.la
(cd .libs && rm -f libhello.la && ln -s ../libhello.la libhello.la)
```

Note that since `libtool` will only create a static archive, the ‘`-rpath`’ switch is not required: once a static library has been installed, there is no need to perform additional finalization for the library to be used from the installed location<sup>3</sup>, or to track runtime search paths when installing a static archive.

When you link an executable against this ‘`libhello.la`’, the objects from the static archive will be statically linked into the executable. The advantage of such a library over the traditional native static archive is that all of the dependency information from the Libtool library is used. For an example, See [Section 10.2.4 \[Creating Convenience Libraries\]](#), page 87.

`libtool` is useful as a **general** library building toolkit, yet people still seem to regress to the old way of building libraries whenever they want to use static archives. You should exploit the consistent interface of `libtool` even for static archives. If you don’t want to use shared archives, use the ‘`-static`’ switch to build a static Libtool library.

### 10.2.4 Creating Convenience Libraries

The third type of library which can be built with `libtool` is the *convenience library*. Modern compilers are able to create *partially linked* objects: intermediate compilation units which comprise several compiled objects, but are neither an executable or a library. Such partially linked objects must be subsequently linked into a library or executable to be useful.

<sup>3</sup> As is often the case, AIX is peculiar in this respect – `ranlib` adds path information to a static archive, and must be run again after the archive is installed. `libtool` knows about this, and will automatically *bless* the installed library again on AIX.

Libtool convenience libraries *are* partially linked objects, but are emulated by `libtool` on platforms with no native implementation.

If you want to try this to see what `libtool` does on your machine, put the following code in a file `'trim.c'`, in the same directory as `'hello.c'` and `'libhello.la'`, and run the example shell commands from there:

```
#include <string.h>

#define WHITESPACE_STR  " \f\n\r\t\v"

/**
 * Remove whitespace characters from both ends of a copy of
 * '\0' terminated STRING and return the result.
 */
char *
trim (char *string)
{
    char *result = 0;

    /* Ignore NULL pointers.  */
    if (string)
    {
        char *ptr = string;

        /* Skip leading whitespace.  */
        while (strchr (WHITESPACE_STR, *ptr))
            ++ptr;

        /* Make a copy of the remainder.  */
        result = strdup (ptr);

        /* Move to the last character of the copy.  */
        for (ptr = result; *ptr; ++ptr)
            /* NOWORK */;
        --ptr;

        /* Remove trailing whitespace.  */
        for (--ptr; strchr (WHITESPACE_STR, *ptr); --ptr)
            *ptr = '\0';
    }

    return result;
}
```

To compile the convenience library with `libtool`, you would do this:

```

$ libtool gcc -c trim.c
rm -f .libs/trim.lo
gcc -c -fPIC -DPIC trim.c -o .libs/trim.lo
gcc -c trim.c -o trim.o >/dev/null 2>&1
mv -f .libs/trim.lo trim.lo
$ libtool gcc -o libtrim.la trim.lo
rm -fr .libs/libtrim.la .libs/libtrim.* .libs/libtrim.*
ar cru .libs/libtrim.al trim.lo
ranlib .libs/libtrim.al
creating libtrim.la
(cd .libs && rm -f libtrim.la && ln -s ../libtrim.la libtrim.la)

```

Additionally, you can use a convenience library as an alias for a set of zero or more object files and some dependent libraries. If you need to link several objects against a long list of libraries, it is much more convenient to create an alias:

```

$ libtool gcc -o libgraphics.la -lpng -ltiff -ljpeg -lz
rm -fr .libs/libgraphics.la .libs/libgraphics.* .libs/libgraphics.*
ar cru .libs/libgraphics.al
ranlib .libs/libgraphics.al
creating libgraphics.la
(cd .libs && rm -f libgraphics.la && \
ln -s ../libgraphics.la libgraphics.la)

```

Having done this, whenever you link against ‘libgraphics.la’ with libtool, all of the dependent libraries will be linked too. In this case, there are no actual objects compiled into the convenience library, but you can do that too, if need be.

### 10.3 Linking an Executable

Continuing the parallel between the syntax used to compile with libtool and the syntax used when building old static libraries, linking an executable is a matter of combining compilation units into a binary in both cases. We tell the compiler which objects and libraries are required, and it creates an executable for us.

If you want to try this to see what libtool does on your machine, put the following code in a file ‘main.c’, in the same directory as ‘hello.c’ and ‘libhello.la’, and run the example shell commands from there:

```

void hello ();

int
main (int argc, char *argv[])
{
    hello ("World");
    exit (0);
}

```

To compile an executable which uses the non-Libtool ‘libhello.a’ library built previously (see [Section 10.2 \[The Libtool Library\]](#), page 84), I would use the following commands:

```
$ gcc -o hello main.c libhello.a
$ ./hello
Hello, World!
```

To create a similar executable on the HP-UX host, using `libtool` this time:

```
$ libtool gcc -o hello main.c libhello.la
libtool: link: warning: this platform does not like uninstalled
libtool: link: warning: shared libraries.
libtool: link: hello will be relinked during installation
gcc -o .libs/hello main.c /tmp/hello/.libs/libhello.sl \
-Wl,+b -Wl,/tmp/hello/.libs:/usr/local/lib
creating hello
$ ls
hello      hello.lo  libhello.la
hello.c    hello.o   main.c
$ ./hello
Hello, World!
```

Notice that you linked against the Libtool library, ‘`libhello.la`’, but otherwise the link command you used was not really very different from non-Libtool static library link command used earlier. Still, `libtool` does several things for you: it links with the shared archive rather than the static archive; and it sets the compiler options so that the program can be run in place, even though it is linked against the uninstalled Libtool library. Using a `make` rule *without* the benefit of `libtool`, it would be almost impossible to reliably link a program against an uninstalled shared library in this way, since the particular switches needed would be different between the various platforms you want the project to work with. Also without the extra compiler options `libtool` adds for you, the program will search only the standard library directories for a shared ‘`libhello`’.

The link warning tells you that `libtool` knows that on HP-UX the program will stop working if it is copied directly to the installation directory; To prevent it breaking, `libtool` will relink the program when it is installed, see [Section 10.6 \[Installing a Library\]](#), page 96.

I discussed the creation of static Libtool libraries in [Section 10.2.3 \[Creating Static Libraries\]](#), page 87. If you link an executable against such a library, the library objects, by definition, can only be statically linked into your executable. Often this is what you want if the library is not intended for installation, or if you have temporarily disabled building of shared libraries in your development tree to speed up compilation while you are debugging.

Sometimes, this isn’t what you want. You might need to install a complete Libtool library with shared and static components, but need to generate a static executable linked against the same library, like this:

```
$ libtool gcc -static -o hello main.c libhello.la
gcc -o hello main.c ./.libs/libhello.a
```

In this case, the ‘`-static`’ switch instructs `libtool` to choose the static component of any uninstalled Libtool library.

You could have specified ‘`-all-static`’ instead, which instructs `libtool` to link the executable with only static libraries (wherever possible), for any Libtool or native libraries used.

Finally, you can also link executables against convenience libraries. This makes sense when the convenience library is being used as an alias (see [Section 10.2.4 \[Creating Conve-](#)

nience Libraries], page 87). Notice how ‘libgraphics.la’ expands to its own dependencies in the link command:

```
$ libtool gcc -o image loader.o libgraphics.la
libtool: link: warning: this platform does not like uninstalled
libtool: link: warning: shared libraries
libtool: link: image will be relinked during installation
gcc -o .libs/image loader.o -lpng -ltiff -ljpeg -lz \
-Wl,+b -Wl,/tmp/image/.libs:/usr/local/lib
creating image
```

You can also link against convenience libraries being used as partially linked objects, so long as you are careful that each is linked only once. Remember that a partially linked object is just the same as any other object, and that if you load it twice (even from different libraries), you will get multiple definition errors when you try to link your executable. This is almost the same as using the ‘-static’ switch on the libtool link line to link an executable with the static component of a normal Libtool library, except that the convenience library comprises PIC objects. When statically linking an executable, PIC objects are best avoided however, see [Section 10.2.1 \[Position Independent Code\]](#), page 84.

## 10.4 Linking a Library

Libraries often rely on code in other libraries. Traditionally the way to deal with this is to *know* what the dependencies are and, when linking an executable, be careful to list all of the dependencies on the link line in the correct order. If you have ever built an X Window application using a widget library, you will already be familiar with this notion.

Even though you only use the functions in the widget library directly, a typical link command would need to be:

```
$ gcc -o Xtest -I/usr/X11R6/include Xtest.c -L/usr/X11R6/lib \
-lXm -lXp -lXaw -lXmu -lX11 -lnsl -lsocket
```

With modern architectures, this problem has been solved by allowing libraries to be linked into other libraries, but this feature is not yet particularly portable. If you are trying to write a portable project, it is not safe to rely on native support for inter-library dependencies, especially if you want to have dependencies between static and shared archives. Some of the features discussed in this section were not fully implemented before Libtool 1.4, so you should make sure that you are using this version or newer if you need these features.

If you want to try the examples in this section to see what libtool does on your machine, you will first need to modify the source of ‘hello.c’ to introduce a dependency on ‘trim.c’:

```
#include <stdio.h>

extern char *trim ();
extern void free ();

void
hello (char *who)
{
```

```

    char *trimmed = trim (who);
    printf ("Hello, %s!\n", trimmed);
    free (trimmed);
}

```

You might also want to modify the ‘main.c’ file to exercise the new ‘trim’ functionality to prove that the newly linked executable is working:

```

void hello ();

int
main (int argc, char *argv[])
{
    hello ("\tWorld \r\n");
    exit (0);
}

```

Suppose I want to make two libraries, ‘libtrim’ and ‘libhello’. ‘libhello’ uses the ‘trim’ function in ‘libtrim’ but the code in ‘main’ uses only the ‘hello’ function in ‘libhello’. Traditionally, the two libraries are built like this:

```

$ rm hello *.a *.la *.o *.lo
$ gcc -c trim.c
$ ls
hello.c  main.c  trim.c  trim.o
$ ar cru libtrim.a trim.o
$ ranlib libtrim.a
$ gcc -c hello.c
$ ls
hello.c  hello.o  libtrim.a  main.c  trim.c  trim.o
$ ar cru libhello.a hello.o
$ ranlib libhello.a
$ ls
hello.c  libhello.a  main.c  trim.o
hello.o  libtrim.a  trim.c

```

Notice that there is no way to specify that ‘libhello.a’ won’t work unless it is also linked with ‘libtrim.a’. Because of this I need to list both libraries when I link the application. What’s more, I need to list them in the correct order:

```

$ gcc -o hello main.c libtrim.a libhello.a
/usr/bin/ld: Unsatisfied symbols:
    trim (code)
collect2: ld returned 1 exit status
$ gcc -o hello main.c libhello.a libtrim.a
$ ls
hello      hello.o      libtrim.a  trim.c
hello.c    libhello.a  main.c     trim.o
$ ./hello
Hello, World!

```

### 10.4.1 Inter-library Dependencies

libtool's inter-library dependency support will use the native implementation if there is one available. If there is no native implementation, or if the native implementation is broken or incomplete, libtool will use an implementation of its own.

To build 'libtrim' as a standard Libtool library (see [Section 10.2 \[The Libtool Library\]](#), [page 84](#)), as follows:

```
$ rm hello *.a *.o
$ ls
hello.c  main.c  trim.c
$ libtool gcc -c trim.c
rm -f .libs/trim.lo
gcc -c -fPIC -DPIC trim.c -o .libs/trim.lo
gcc -c trim.c -o trim.o >/dev/null 2>&1
mv -f .libs/trim.lo trim.lo
$ libtool gcc -rpath /usr/local/lib -o libtrim.la trim.lo
rm -fr .libs/libtrim.la .libs/libtrim.* .libs/libtrim.*
/opt/gcc-lib/hp821/2.7.0/ld -b +h libtrim.sl.0 +b /usr/local/lib \
-o .libs/libtrim.sl.0.0 trim.lo
(cd .libs && rm -f libtrim.sl.0 && ln -s libtrim.sl.0.0 libtrim.sl.0)
(cd .libs && rm -f libtrim.sl && ln -s libtrim.sl.0.0 libtrim.sl)
ar cru .libs/libtrim.a trim.o
ranlib .libs/libtrim.a
creating libtrim.la
(cd .libs && rm -f libtrim.la && ln -s ../libtrim.la libtrim.la)
```

When you build 'libhello', you can specify the libraries it depends on at the command line, like so:

```
$ libtool gcc -c hello.c
rm -f .libs/hello.lo
gcc -c -fPIC -DPIC hello.c -o .libs/hello.lo
gcc -c hello.c -o hello.o >/dev/null 2>&1
mv -f .libs/hello.lo hello.lo
$ libtool gcc -rpath /usr/local/lib -o libhello.la hello.lo libtrim.la
rm -fr .libs/libhello.la .libs/libhello.* .libs/libhello.*

*** Warning: inter-library dependencies are not known to be supported.
*** All declared inter-library dependencies are being dropped.
*** The inter-library dependencies that have been dropped here will be
*** automatically added whenever a program is linked with this library
*** or is declared to -dlopen it.
/opt/gcc-lib/hp821/2.7.0/ld -b +h libhello.sl.0 +b /usr/local/lib \
-o .libs/libhello.sl.0.0 hello.lo
(cd .libs && rm -f libhello.sl.0 && ln -s libhello.sl.0.0 libhello.sl.0)
(cd .libs && rm -f libhello.sl && ln -s libhello.sl.0.0 libhello.sl)
ar cru .libs/libhello.a hello.o
ranlib .libs/libhello.a
creating libhello.la
(cd .libs && rm -f libhello.la && ln -s ../libhello.la libhello.la)
```

```
$ ls
hello.c    hello.o      libtrim.la   trim.c    trim.o
hello.lo   libhello.la  main.c      trim.lo
```

Although, on HP-UX, `libtool` warns that it doesn't know how to use the native inter-library dependency implementation, it will track the dependencies and make sure they are added to the final link line, so that you only need to specify the libraries that you use directly.

Now, you can rebuild 'hello' exactly as in the earlier example (see [Section 10.3 \[Linking an Executable\]](#), page 89), as in:

```
$ libtool gcc -o hello main.c libhello.la
libtool: link: warning: this platform does not like uninstalled
libtool: link: warning: shared libraries
libtool: link: hello will be relinked during installation
gcc -o .libs/hello main.c /tmp/intro-hello/.libs/libhello.sl \
/tmp/intro-hello/.libs/libtrim.sl \
-Wl,+b -Wl,/tmp/intro-hello/.libs:/usr/local/lib
creating hello
$ ./hello
Hello, World!
```

Notice that even though you only specified the 'libhello.la' library at the command line, `libtool` remembers that 'libhello.sl' depends on 'libtrim.sl' and links that library too.

You can also link a static executable, and the dependencies are handled similarly:

```
$ libtool gcc -o hello-again -static main.c libhello.la
gcc -o hello main.c ./.libs/libhello.a /tmp/intro-hello/.libs/libtrim.a
$ ./hello-again
Hello, World!
```

For your own projects, provided that you use `libtool`, and that you specify the libraries you wish to link using the '.la' pseudo-libraries, these dependencies can be nested as deeply as you like. You can also register dependencies on native libraries, though you will of course need to specify any dependencies that the native library itself has at the same time.

### 10.4.2 Using Convenience Libraries

To rebuild 'libtrim' as a convenience library (see [Section 10.2.4 \[Creating Convenience Libraries\]](#), page 87), use the following commands:

```
$ rm hello *.la
$ ls
hello.c  hello.lo  hello.o  main.c  trim.c  trim.lo  trim.o
$ libtool gcc -o libtrim.la trim.lo
rm -fr .libs/libtrim.la .libs/libtrim.* .libs/libtrim.*
ar cru .libs/libtrim.al trim.lo
ranlib .libs/libtrim.al
creating libtrim.la
(cd .libs && rm -f libtrim.la && ln -s ../libtrim.la libtrim.la)
```

Then, rebuild 'libhello', with an inter-library dependency on 'libtrim' (see [Section 10.4.1 \[Inter-library Dependencies\]](#), page 93), like this:



```

$ libtool gcc -rpath 'pwd'/_inst -o libhello.la hello.lo libtrim.la
rm -fr .libs/libhello.la .libs/libhello.* .libs/libhello.*

*** Warning: inter-library dependencies are not known to be supported.
*** All declared inter-library dependencies are being dropped.
*** The inter-library dependencies that have been dropped here will be
*** automatically added whenever a program is linked with this library
*** or is declared to -dlopen it.
rm -fr .libs/libhello.lax
mkdir .libs/libhello.lax
rm -fr .libs/libhello.lax/libtrim.al
mkdir .libs/libhello.lax/libtrim.al
(cd .libs/libhello.lax/libtrim.al && ar x /tmp/./.libs/libtrim.al)
/opt/gcc-lib/hp821/2.7.0/ld -b +h libhello.sl.0 +b /tmp/hello/_inst \
-o .libs/libhello.sl.0.0 hello.lo .libs/libhello.lax/libtrim.al/trim.lo
(cd .libs && rm -f libhello.sl.0 && ln -s libhello.sl.0.0 libhello.sl.0)
(cd .libs && rm -f libhello.sl && ln -s libhello.sl.0.0 libhello.sl)
rm -fr .libs/libhello.lax
mkdir .libs/libhello.lax
rm -fr .libs/libhello.lax/libtrim.al
mkdir .libs/libhello.lax/libtrim.al
(cd .libs/libhello.lax/libtrim.al && ar x /tmp/hello/./.libs/libtrim.al)
ar cru .libs/libhello.a hello.o .libs/libhello.lax/libtrim.al/trim.lo
ranlib .libs/libhello.a
rm -fr .libs/libhello.lax .libs/libhello.lax
creating libhello.la
(cd .libs && rm -f libhello.la && ln -s ../libhello.la libhello.la)
$ ls
hello.c      hello.o      libtrim.la   trim.c       trim.o
hello.lo     libhello.la  main.c       trim.lo

```

Compare this to the previous example of building ‘libhello’ and you can see that things are rather different. On HP-UX, partial linking is not known to work, so libtool extracts the objects from the convenience library, and links them directly into ‘libhello’. That is, ‘libhello’ is comprised of its own objects *and* the objects in ‘libtrim’. If ‘libtrim’ had had any dependencies, ‘libhello’ would have inherited them too. This technique is especially useful for grouping source files into subdirectories, even though all of the objects compiled in the subdirectories must eventually reside in a big library: compile the sources in each into a convenience library, and in turn link all of these into a single library which will then contain all of the constituent objects and dependencies of the various convenience libraries.

When you relink the `hello` executable, notice that ‘libtrim’ is **not** linked, because the ‘libtrim’ objects are already present in ‘libhello’:

```
$ libtool gcc -o hello main.c libhello.la
libtool: link: warning: this platform does not like uninstalled
libtool: link: warning: shared libraries
libtool: link: hello will be relinked during installation
gcc -o .libs/hello main.c /tmp/intro-hello/.libs/libhello.sl \
-Wl,+b -Wl,/tmp/intro-hello/.libs:/usr/local/lib
creating hello
$ ./hello
Hello, World!
```

## 10.5 Executing Uninstalled Binaries

If you look at the contents of the `hello` program you built in the last section, you will see that it is not actually a binary at all, but a shell script which sets up the environment so that when the real binary is called it finds its the shared libraries in the correct locations. Without this script, the runtime loader might not be able to find the uninstalled libraries. Or worse, it might find an old version and load that by mistake!

In practice, this is all part of the unified interface `libtool` presents so you needn't worry about it most of the time. The exception is when you need to look at the binary with another program, to debug it for example:

```
$ ls
hello      hello.lo  libhello.la  main.c  trim.lo
hello.c    hello.o  libtrim.la   trim.c  trim.o
$ libtool gdb hello
GDB is free software and you are welcome to distribute copies of it
under certain conditions; type "show copying" to see the conditions.
There is absolutely no warranty for GDB; type "show warranty" for
details.
GDB 4.18 (hppa1.0-hp-hpux10.20),
Copyright 1999 Free Software Foundation, Inc...
(gdb) bre main
Breakpoint 1 at 0x5178: file main.c, line 6.
(gdb) run
Starting program: /tmp/intro-hello/.libs/hello
Breakpoint 1, main (argc=1, argv=0x7b03aa70) at main.c:6
6          return hello("World");
...
```

## 10.6 Installing a Library

Now that the library and an executable which links with it have been successfully built, they can be installed. For the sake of this example I will `cp` the objects to their destination, though `libtool` would be just as happy if I were to use `install` with the long, requisite list of parameters.

It is important to install the library to the `‘-rpath’` destination which was specified when it was linked earlier, or at least that it be visible from that location when the runtime loader searches for it. This rule is not enforced by `libtool`, since it is often desirable to install

libraries to a *staging*<sup>4</sup> area. Of course, the package must ultimately install the library to the specified ‘-rpath’ destination for it to work correctly, like this:

```
$ libtool cp libtrim.la /usr/local/lib
cp .libs/libtrim.sl.0.0 /usr/local/lib/libtrim.sl.0.0
(cd /usr/local/lib && rm -f libtrim.sl.0 && \
ln -s libtrim.sl.0.0 libtrim.sl.0)
(cd /usr/local/lib && rm -f libtrim.sl && \
ln -s libtrim.sl.0.0 libtrim.sl)
chmod 555 /usr/local/lib/libtrim.sl.0.0
cp .libs/libtrim.lai /usr/local/lib/libtrim.la
cp .libs/libtrim.a /usr/local/lib/libtrim.a
ranlib /usr/local/lib/libtrim.a
chmod 644 /usr/local/lib/libtrim.a
```

---

Libraries have been installed in:  
/usr/local/lib

If you ever happen to want to link against installed libraries in a given directory, LIBDIR, you must either use libtool, and specify the full pathname of the library, or use -LLIBDIR flag during linking and do at least one of the following:

- add LIBDIR to the SHLIB\_PATH environment variable during execution
- use the -Wl,+b -Wl,LIBDIR linker flag

See any operating system documentation about shared libraries for more information, such as the ld(1) and ld.so(8) manual pages.

---

Again, libtool takes care of the details for you. Both the static and shared archives are copied into the installation directory and their access modes are set appropriately. libtool *blesses* the static archive again with ranlib, which would be easy to forget without the benefit of libtool, especially if I develop on a host where the library will continue to work without this step. Also, libtool creates the necessary links for the shared archive to conform with HP-UX's library versioning rules. Compare this to what you see with the equivalent commands running on GNU/Linux to see how libtool applies these rules according to the requirements of its host. The block of text libtool shows at the end of the installation serves to explain how to link executables against the newly installed library on HP-UX and how to make sure that the executables linked against it will work. Of course, the best way to ensure this is to use libtool to perform the linking. I'll leave the details of linking against an installed Libtool library as an exercise - everything you need to know can be extrapolated from the example of linking against an uninstalled Libtool library, See [Section 10.3 \[Linking an Executable\]](#), page 89.

On some architectures, even shared archives need to be *blessed* on installation. For example, GNU/Linux requires that ldconfig be run when a new library is installed. Typically, a library will be installed to its target destination after being built, in which case libtool will perform any necessary *blessing* during installation. Sometimes, when building a binary

---

<sup>4</sup> When making a binary package from a virtual root directory for example.

package for installation on another machine, for example, it is not desirable to perform the *blessing* on the build machine. No problem, `libtool` takes care of this too! `libtool` will detect if you install the library to a destination other than the one specified in the `‘-rpath’` argument passed during the archive link, and will simply remind you what needs to be done before the library can be used:

```
$ mkdir -p /usr/local/stow/hello-1.0/lib
$ libtool cp libtrim.la /usr/local/stow/hello-1.0/lib
cp .libs/libtrim.sl.0.0 /usr/local/stow/hello-1.0/lib/libtrim.sl.0.0
(cd /usr/local/stow/hello-1.0/lib && rm -f libtrim.sl.0 && \
ln -s libtrim.sl.0.0 libtrim.sl.0)
(cd /usr/local/stow/hello-1.0/lib && rm -f libtrim.sl && \
ln -s libtrim.sl.0.0 libtrim.sl)
chmod 555 /usr/local/stow/hello-1.0/lib/libtrim.sl.0.0
cp .libs/libtrim.lai /usr/local/stow/hello-1.0/lib/libtrim.la
cp .libs/libtrim.a /usr/local/stow/hello-1.0/lib/libtrim.a
ranlib /usr/local/stow/hello-1.0/lib/libtrim.a
chmod 644 /usr/local/stow/hello-1.0/lib/libtrim.a
libtool: install: warning: remember to run
libtool: install: warning: libtool --finish /usr/local/lib
```

If you will make the installed libraries visible in the destination directory with symbolic links, you need to do whatever it is you do to make the library visible, and then *bless* the library in *that* location with the `libtool --finish /usr/local/lib` command:

```
$ cd /usr/local/stow
$ stow hello-1.0
$ libtool --finish /usr/local/lib
```

If you are following the examples so far, you will also need to install the Libtool library, `‘libhello.la’`, before you move on to the next section:

```
$ libtool cp libhello.la /usr/local/lib
cp .libs/libhello.sl.0.0 /usr/local/lib/libhello.sl.0.0
(cd /usr/local/lib && rm -f libhello.sl.0 && \
ln -s libhello.sl.0.0 libhello.sl.0)
(cd /usr/local/lib && rm -f libhello.sl && \
ln -s libhello.sl.0.0 libhello.sl)
chmod 555 /usr/local/lib/libhello.sl.0.0
cp .libs/libhello.lai /usr/local/lib/libhello.la
cp .libs/libhello.a /usr/local/lib/libhello.a
ranlib /usr/local/lib/libhello.a
chmod 644 /usr/local/lib/libhello.a
```

---

```
Libraries have been installed in:
    /usr/local/lib
```

```
If you ever happen to want to link against installed libraries
in a given directory, LIBDIR, you must either use libtool, and
specify the full pathname of the library, or use -LLIBDIR
flag during linking and do at least one of the following:
```

- add LIBDIR to the SHLIB\_PATH environment variable
 during execution
- use the -Wl,+b -Wl,LIBDIR linker flag

```
See any operating system documentation about shared libraries for
more information, such as the ld(1) and ld.so(8) manual pages.
```

---

Once a Libtool library is installed, binaries which link against it will hardcode the path to the Libtool library, as specified with the ‘`-rpath`’ switch when the library was built. `libtool` always encodes the installation directory into a Libtool library for just this purpose. Hardcoding directories in this way is a good thing, because binaries linked against such libraries will continue to work if there are several incompatible versions of the library visible to the runtime loader (say a Trojan ‘`libhello`’ in a user’s `LD_LIBRARY_PATH`, or a test build of the next release). The disadvantage to this system is that if you move libraries to new directories, executables linked in this way will be unable to find the libraries they need. Moving any library is a bad idea however, doubly so for a Libtool library which has its installation directory encoded internally, so the way to avoid problems of this nature is to not move libraries around after installation!

## 10.7 Installing an Executable

Installing an executable uses exactly the same command line that I used to install the library earlier:

```
$ libtool cp hello /usr/local/bin
gcc -o /tmp/libtool-28585/hello main.c /usr/local/lib/libhello.sl \
/usr/local/lib/libtrim.sl -Wl,+b -Wl,/usr/local/lib
cp /tmp/libtool-28585/hello /usr/local/bin/hello
$ /usr/local/bin/hello
Hello, World!
```

As `libtool` said earlier, during the initial linking of the `hello` program in the build directory, `hello` must be rebuilt before installation. This is a peculiarity of HP-UX (and a few other architectures) which you won’t see if you are following the examples on a GNU/Linux system. In the shell trace above, `libtool` has built an installable version of the `hello` program, saving me the trouble of remembering (or worse – coding for) the particulars of HP-UX, which runs correctly from the installed location.

As a matter of interest, if you look at the attributes of the installed program using HP-UX’s `chatr` command:

```

$ chatr /usr/local/bin/hello
/usr/local/bin/hello:
    shared executable
    shared library dynamic path search:
        SHLIB_PATH      disabled    second
        embedded path    enabled     first  /usr/local/lib
    internal name:
        /tmp/libtool-28585/hello
    shared library list:
        static    /usr/local/lib/libhello.sl.0
        static    /usr/local/lib/libtrim.sl.0
        dynamic   /lib/libc.1
    shared library binding:
        deferred
...

```

You can see that the runtime library search path for the installed **hello** program has been set to find the installed ‘**libhello.sl.0**’ shared archive, preventing it from accidentally loading a different library (with the same name) from the default load path. This is a feature of **libtool**, and a very important one at that, and although it may not seem like the right way to do things initially, it saves a **lot** of trouble when you end up with several versions of a library installed in several locations, since each program will continue to use the version that it was linked with, subject to library versioning rules, see [Section 11.4 \[Library Versioning\]](#), page 112.

Without the help of **libtool**, it is very difficult to prevent programs and libraries in the build tree from loading earlier (compatible) versions of a shared archive that were previously installed without an intimate knowledge of the build hosts architecture. Making it work portably would be nigh impossible! You should experiment with changes to the uninstalled library and satisfy yourself that the previously installed program continues to load the installed library at runtime, whereas the uninstalled program picks up the modifications in the uninstalled version of the library.

This example introduces the concept of Libtool modes. Most of the time **libtool** can infer a mode of operation from the contents of the command line, but sometimes (as in this example) it needs to be told. In [Section 10.5 \[Executing Uninstalled Binaries\]](#), page 96 we already used **libtool** in **execute** mode to run **gdb** against an uninstalled binary. In this example I am telling **libtool** that I want to pass the **hello** binary to the **chatr** command, particularly since I know that the ‘**hello**’ file is a script to set the local execution environment before running the real binary.

The various modes that **libtool** has are described in the Libtool reference documentation, and are listed in the Libtool help text:

```
$ libtool --help
```

```
...
```

```
MODE must be one of the following:
```

clean	remove files from the build directory
compile	compile a source file into a libtool object
execute	automatically set library path, then run a program
finish	complete the installation of libtool libraries
install	install libraries or executables
link	create a library or an executable
uninstall	remove libraries from an installed directory

MODE-ARGS vary depending on the MODE. Try 'libtool --help --mode=MODE' for a more detailed description of MODE.

## 10.8 Uninstalling

Having installed all of these files to '/usr/local', it might be difficult to remember which particular files belong to each installation. In the case of an executable, the uninstallation requires no magic, but when uninstalling a Libtool library all of the files which comprise the implementation of the Libtool library in question must be uninstalled:

```
$ libtool rm -f /usr/local/bin/hello
rm -f /usr/local/bin/hello
$ libtool rm -f /usr/local/lib/libhello.la
rm -f /usr/local/lib/libhello.la /usr/local/lib/libhello.sl.0.0 \
/usr/local/lib/libhello.sl.0 /usr/local/lib/libhello.sl \
/usr/local/lib/libhello.a
$ libtool rm -f /usr/local/lib/libtrim.la
rm -f /usr/local/lib/libtrim.la /usr/local/lib/libtrim.sl.0.0 \
/usr/local/lib/libtrim.sl.0 /usr/local/lib/libtrim.sl \
/usr/local/lib/libtrim.a
```

Using libtool to perform the uninstallation in this way ensures that all of the files that it installed, including any additional soft links required by the architecture versioning scheme for shared archives, are removed with a single command.

Having explored the use of libtool from the command line, the next chapter will discuss how to integrate libtool into the configury of your GNU Autotools based projects.





## 11 Using GNU Libtool with ‘configure.in’ and ‘Makefile.am’

Although Libtool is usable by itself, either from the command line or from a non-`make` driven build system, it is also tightly integrated into Autoconf and Automake. This chapter discusses how to use Libtool with Autoconf and Automake and explains how to set up the files you write (‘`Makefile.am`’ and ‘`configure.in`’) to take advantage of libtool. For a more in depth discussion of the workings of Libtool, particularly its command line interface, See [Chapter 10 \[Introducing GNU Libtool\]](#), page 81. Using `libtool` for dynamic runtime loading is described in See [Chapter 18 \[Using GNU libltdl\]](#), page 185.

Using `libtool` to build the libraries in a project, requires declaring your use of `libtool` inside the project’s ‘`configure.in`’ and adding the Libtool support scripts to the distribution. You will also need to amend the build rules in either ‘`Makefile.am`’ or ‘`Makefile.in`’, depending on whether you are using Automake.

### 11.1 Integration with ‘configure.in’

Declaring your use of `libtool` in the project’s ‘`configure.in`’ is a simple matter of adding the ‘`AC_PROG_LIBTOOL`’<sup>1</sup> somewhere near the top of the file. I always put it immediately after the other ‘`AC_PROG_...`’ macros. If you are converting an old project to use `libtool`, then you will also need to remove any calls to ‘`AC_PROG_RANLIB`’. Since Libtool will be handling all of the libraries, *it* will decide whether or not to call `ranlib` as appropriate for the build environment.

The code generated by ‘`AC_PROG_LIBTOOL`’ relies on the shell variable `$top_builddir` to hold the relative path to the directory which contains the `configure` script. If you are using Automake, `$top_builddir` is set in the environment by the generated ‘`Makefile`’. If you use Autoconf without Automake then you must ensure that `$top_builddir` is set before the call to ‘`AC_PROG_LIBTOOL`’ in ‘`configure.in`’.

Adding the following code to ‘`configure.in`’ is often sufficient:

```
for top_builddir in . . . ../.. $ac_auxdir $ac_auxdir/..; do
  test -f $top_builddir/configure && break
done
```

Having made these changes to add `libtool` support to your project, you will need to regenerate the ‘`aclocal.m4`’ file to pick up the macro definitions required for ‘`AC_PROG_LIBTOOL`’, and then rebuild your `configure` script with these new definitions in place. After you have done that, there will be some new options available from `configure`:

```
$ aclocal
$ autoconf
```

---

<sup>1</sup> ‘`AM_PROG_LIBTOOL`’ if you have an older `automake` or `libtool` installation.

```
$ ./configure --help
...
--enable and --with options recognized:
  --enable-shared[=PKGS]  build shared libraries [yes]
  --enable-static[=PKGS]  build static libraries [yes]
  --enable-fast-install[=PKGS]  optimize for fast installation [yes]
  --with-gnu-ld            assume the C compiler uses GNU ld [no]
  --disable-libtool-lock   avoid locking (might break parallel builds)
  --with-pic              try to use only PIC/non-PIC objects [both]
```

These new options allow the end user of your project some control over how they want to build the project's libraries. The opposites of each of these switches are also accepted, even though they are not listed by `configure --help`. You can equally pass, `--disable-fast-install` or `--without-gnu-ld` for example.

### 11.1.1 Extra Configure Options

What follows is a list that describes the more commonly used options that are automatically added to `configure`, by virtue of using `AC_PROG_LIBTOOL` in your `configure.in`. The Libtool Manual distributed with Libtool releases always contains the most up to date information about libtool options:

```
'--enable-shared'
'--enable-static'
```

More often invoked as `--disable-shared` or equivalently `--enable-shared=no` these switches determine whether libtool should build shared and/or static libraries in this package. If the installer is short of disk space, they might like to build entirely without static archives. To do this they would use:

```
$ ./configure --disable-static
```

Sometimes it is desirable to configure several related packages with the same command line. From a scheduled build script or where subpackages with their own `configure` scripts are present, for example. The `--enable-shared` and `--enable-static` switches also accept a list of package names, causing the option to be applied to packages whose name is listed, and the opposite to be applied to those not listed.

By specifying:

```
$ ./configure --enable-static=libsnprintfv,autoopts
```

libtool would pass `--enable-static` to only the packages named *libsnprintfv* and *autoopts* in the current tree. Any other packages configured would effectively be passed `--disable-static`. Note that this doesn't necessarily mean that the packages must honour these options. Enabling static libraries for a package which consists of only dynamic modules makes no sense, and the package author would probably have decided to ignore such requests, See [Section 11.1.2 \[Extra Macros for Libtool\]](#), page 106.

**‘--enable-fast-install’**

On some machines, `libtool` has to relink executables when they are installed, See [Section 10.7 \[Installing an Executable\]](#), page 99. Normally, when an end user builds your package, they will probably type:

```
$ ./configure
$ make
$ make install
```

`libtool` will build executables suitable for copying into their respective installation destinations, obviating the need for relinking them on those hosts which would have required it. Whenever `libtool` links an executable which uses shared libraries, it also creates a *wrapper script* which ensures that the environment is correct for loading the correct libraries, See [Section 10.5 \[Executing Uninstalled Binaries\]](#), page 96. On those hosts which require it, the wrapper script will also relink the executable in the build tree if you attempt to run it from there before installation.

Sometimes this behaviour is not what you want, particularly if you are developing the package and not installing between test compilations. By passing ‘--disable-fast-install’, the default behaviour is reversed; executables will be built so that they can be run from the build tree without relinking, but during installation they may be relinked.

You can pass a list of executables as the argument to ‘--enable-fast-install’ to determine which set of executables will not be relinked at installation time (on the hosts that require it). By specifying:

```
$ ./configure --enable-fast-install=autogen
```

The `autogen` executable will be linked for fast installation (without being relinked), and any other executables in the build tree will be linked for fast execution from their build location. This is useful if the remaining executables are for testing only, and will never be installed.

Most machines do not require that executables be relinked in this way, and in these cases `libtool` will link each executable once only, no matter whether ‘--disable-fast-install’ is used.

**‘--with-gnu-ld’**

This option is used to inform `libtool` that the C compiler is using GNU `ld` as its linker. It is more often used in the opposite sense when both `gcc` and GNU `ld` are installed, but `gcc` was built to use the native linker. `libtool` will probe the system for GNU `ld`, and assume that it is used by `gcc` if found, unless ‘--without-gnu-ld’ is passed to configure.

**‘--disable-libtool-lock’**

In normal operation, `libtool` will build two objects for every source file in a package, one PIC<sup>2</sup> and one non-PIC. With `gcc` and some other compilers, `libtool` can specify a different output location for the PIC object:

---

<sup>2</sup> Position Independent Code – suitable for shared libraries which might be loaded to different addresses when linked by the runtime loader.

```
$ libtool gcc -c shell.c
gcc -c -pic -DPIC shell.c -o .libs/shell.lo
gcc -c foo.c -o shell.o >/dev/null 2>&1
```

When using a compiler that doesn't accept both `'-o'` and `'-c'` in the same command, `libtool` must compile first the PIC and then the non-PIC object to the same destination file and then move the PIC object before compiling the non-PIC object. This would be a problem for parallel builds, since one file might overwrite the other. `libtool` uses a simple shell locking mechanism to avoid this eventuality.

If you find yourself building in an environment that has such a compiler, and not using parallel `make`, then the locking mechanism can be safely turned off by using `'--disable-libtool-lock'` to gain a little extra speed in the overall compilation.

#### `'--with-pic'`

In normal operation, Libtool will build shared libraries from PIC objects and static archives from non-PIC objects, except where one or the other is not provided by the target host. By specifying `'--with-pic'` you are asking `libtool` to build static archives from PIC objects, and similarly by specifying `'--without-pic'` you are asking `libtool` to build shared libraries from non-PIC objects.

`libtool` will only honour this flag where it will produce a working library, otherwise it reverts to the default.

### 11.1.2 Extra Macros for Libtool

There are several macros which can be added to `'configure.in'` which will change the default behaviour of `libtool`. If they are used they must appear before the call to the `'AC_PROG_LIBTOOL'` macro. Note that these macros only change the default behaviour, and options passed in to `configure` on the command line will always override the defaults. The most up to date information about these macros is available from the Libtool Manual.

#### `'AC_DISABLE_FAST_INSTALL'`

This macro tells `libtool` that on platforms which require relinking at install time, it should build executables so that they can be run from the build tree at the expense of relinking during installation, as if `'--disable-fast-install'` had been passed on the command line.

#### `'AC_DISABLE_SHARED'`

#### `'AC_DISABLE_STATIC'`

These macros tell `libtool` to *not* try and build either shared or static libraries respectively. `libtool` will always try to build *something* however, so even if you turn off static library building in `'configure.in'`, building your package for a target host without shared library support will fallback to building static archives.

The time spent waiting for builds during development can be reduced a little by including these macros temporarily. Don't forget to remove them before you release the project though!

In addition to the macros provided with ‘AC\_PROG\_LIBTOOL’, there are a few shell variables that you may need to set yourself, depending on the structure of your project:

#### ‘LTLIBOBJS’

If your project uses the ‘AC\_REPLACE\_FUNCS’ macro, or any of the other macros which add object names to the ‘LIBOBJS’ variable, you will also need to provide an equivalent ‘LTLIBOBJS’ definition. At the moment, you must do it manually, but needing to do that is considered to be a bug and will be fixed in a future release of Autoconf. The manual generation of ‘LTLIBOBJS’ is a simple matter of replacing the names of the objects mentioned in ‘LIBOBJS’ with equivalent .lo suffixed Libtool object names. The easiest way to do this is to add the following snippet to your ‘configure.in’ near the end, just before the call to ‘AC\_OUTPUT’.

```
Xsed="sed -e s/^X/"
LTLIBOBJS='echo X"$LIBOBJS"|\
    [$Xsed -e "s,\.[^.]* ,.lo ,g;s,\.[^.]*$, .lo,"]'
AC_SUBST(LTLIBOBJS)
```

The Xsed is not usually necessary, though it can prevent problems with the echo command in the event that one of the ‘LIBOBJS’ files begins with a ‘-’ character. It is also a good habit to write shell code like this, as it will avoid problems in your programs.

#### ‘LTALLOCA’

If your project uses the ‘AC\_FUNC\_ALLOCA’ macro, you will need to provide a definition of ‘LTALLOCA’ equivalent to the ‘ALLOCA’ value provided by the macro.

```
Xsed="sed -e s/^X/"
LTALLOCA='echo X"$ALLOCA"|[$Xsed -e "s,\.$[^.]* ,.lo,g"]'
AC_SUBST(LTALLOCA)
```

Obviously you don’t need to redefine Xsed if you already use it for ‘LTLIBOBJS’ above.

#### ‘LIBTOOL\_DEPS’

To help you write make rules for automatic updating of the Libtool configuration files, you can use the value of ‘LIBTOOL\_DEPS’ after the call to ‘AC\_PROG\_LIBTOOL’:

```
AC_PROG_LIBTOOL
AC_SUBST(LIBTOOL_DEPS)
```

Then add the following to the top level ‘Makefile.in’:

```
libtool: @LIBTOOL_DEPS@
    cd $(srcdir) && \
        $(SHELL) ./config.status --recheck
```

If you are using automake in your project, it will generate equivalent rules automatically. You don’t need to use this except in circumstances where you want to use libtool and autoconf, but not automake.

## 11.2 Integration with ‘Makefile.am’

Automake supports Libtool libraries in two ways. It can help you to build the Libtool libraries themselves, and also to build executables which link against Libtool libraries.

### 11.2.1 Creating Libtool Libraries with Automake

Continuing in the spirit of making Libtool library management look like native static archive management, converting a ‘Makefile.am’ from static archive use to Libtool library use is a matter of changing the name of the library, and adding a Libtool prefix somewhere. For example, a ‘Makefile.am’ for building a static archive might be:

```
lib_LIBRARIES      = libshell.a
libshell_a_SOURCES = object.c subr.c symbol.c
```

This would build a static archive called ‘libshell.a’ consisting of the objects ‘object.o’, ‘subr.o’ and ‘bar.o’. To build an equivalent Libtool library from the same objects, you change this to:

```
lib_LTLIBRARIES    = libshell.la
libshell_la_SOURCES = object.c subr.c symbol.c
```

The only changes are that the library is now named with a .la suffix, and the Automake primary is now ‘LTLIBRARIES’. Note that since the name of the library has changed, you also need to use ‘libshell\_la\_SOURCES’, and similarly for any other Automake macros which used to refer to the old archive. As for native libraries, Libtool library names should begin with the letters ‘lib’, so that the linker will be able to find them when passed ‘-l’ options.

Often you will need to add extra objects to the library as determined by `configure`, but this is also a mechanical process. When building native libraries, the ‘Makefile.am’ would have contained:

```
libshell_a_LDADD = xmalloc.o @LIBOBJ@
```

To add the same objects to an equivalent Libtool library would require:

```
libshell_la_LDADD = xmalloc.lo @LTLIBOBJ@
```

That is, objects added to a Libtool library must be Libtool objects (with a .lo) suffix. You should add code to ‘configure.in’ to ensure that ‘LTALLOCA’ and ‘LTLIBOBJ’ are set appropriately, See [Section 11.1.2 \[Extra Macros for Libtool\], page 106](#). Automake will take care of generating appropriate rules for building the Libtool objects mentioned in an ‘LDADD’ macro.

If you want to pass any additional flags to `libtool` when it is building, you use the ‘LDFLAGS’ macro for that library, like this:

```
libshell_la_LDFLAGS = -version-info 1:0:1
```

For a detailed list of all the available options, see [section “Link mode” in \*The Libtool Manual\*](#).

Libtool’s use of ‘-rpath’ has been a point of contention for some users, since it prevents you from moving shared libraries to another location in the library search path. Or, at least, if you do, all of the executables that were linked with ‘-rpath’ set to the old location will need to be relinked.

We (the Libtool maintainers) assert that always using ‘-rpath’ is a good thing: Mainly because you can guarantee that any executable linked with ‘-rpath’ will find the correct version of the library, in the rpath directory, that was intended when the executable was linked. Library versions can still be managed correctly, and will be found by the run time loader, by installing newer versions to the same directory. Additionally, it is much harder for a malicious user to leave a modified copy of system library in a directory that someone might wish to list in their ‘LD\_LIBRARY\_PATH’ in the hope that some code they have written will be executed unexpectedly.

The argument against ‘-rpath’ was instigated when one of the GNU/Linux distributions moved some important system libraries to another directory to make room for a different version, and discovered that all of the executables that relied on these libraries and were linked with Libtool no longer worked. Doing this was, arguably, bad system management – the new libraries should have been placed in a new directory, and the old libraries left alone. Refusing to use ‘-rpath’ in case you want to restructure the system library directories is a very weak argument.

The ‘-rpath’ option (which is required for Libtool libraries) is automatically supplied by `automake` based on the installation directory specified with the library primary.

```
lib_LTLIBRARIES = libshell.la
```

The example would use the value of the make macro `$(libdir)` as the argument to ‘-rpath’, since that is where the library will be installed.

A few of the other options you can use in the library ‘LDFLAGS’ are:

‘-no-undefined’

Modern architectures allow us to create shared libraries with undefined symbols, provided those symbols are resolved (usually by the executable which loads the library) at runtime. Unfortunately, there are some architectures (notably AIX and Windows) which require that *all* symbols are resolved when the library is linked. If you know that your library has no unresolved symbols at link time, then adding this option tells `libtool` that it will be able to build a shared library, even on architectures which have this requirement.

‘-static’ Using this option will force `libtool` to build only a static archive for this library.

‘-release’

On occasion, it is desirable to encode the release number of a library into its name. By specifying the release number with this option, `libtool` will build a library that does this, but will break binary compatibility for each change of the release number. By breaking binary compatibility this way, you negate the possibility of fixing bugs in installed programs by installing an updated shared library. You should probably be using ‘-version-info’ instead.

```
libshell_la_LDFLAGS = -release 27
```

The above fragment might create a library called ‘libshell-27.so.0.0.0’ for example.

‘-version-info’

Set the version number of the library according to the native versioning rules based on the numbers supplied, See [Section 11.4 \[Library Versioning\]](#), page 112.



You need to be aware that the library version number is for the use of the run-time loader, and is completely unrelated to the release number of your project. If you really want to encode the project release into the library, you can use `‘-release’` to do it.

If this option is not supplied explicitly, it defaults to `‘-version-info 0:0:0’`.

Historically, the default behaviour of Libtool was as if `‘-no-undefined’` was always passed on the command line, but it proved to be annoying to developers who had to constantly turn it off so that their ELF libraries could be featureful. Now it has to be defined explicitly if you need it.

There is a tradeoff:

- If you don’t specify `‘-no-undefined’`, then Libtool will not build shared libraries on platforms which don’t allow undefined symbols at link time for such a library.
- It is only safe to specify this flag when you know for certain that *all* of the libraries symbols are defined at link time, otherwise the `‘-no-undefined’` link will appear to work until it is tried on a platform which requires all symbols to be defined. Libtool will try to link the shared library in this case (because you told it that you have not left any undefined symbols), but the link will fail, because there **are** undefined symbols in spite of what you told Libtool.

For more information about this topic, see [Section 18.3 \[Portable Library Design\]](#), page 196.

### 11.2.2 Linking against Libtool Libraries with Automake

Once you have set up your `‘Makefile.am’` to create some Libtool libraries. you will want to link an executable against them. You can do this easily with `automake` by using the program’s qualified `‘LDADD’` macro:

```
bin_PROGRAMS = shell
shell_SOURCES = shell.c token.1
shell_LDADD   = libshell.la
```

This will choose either the static or shared archive from the `‘libshell.la’` Libtool library depending on the target host and any Libtool mode switches mentioned in the `‘Makefile.am’`, or passed to `configure`. The chosen archive will be linked with any objects generated from the listed sources to make an executable. Note that the executable itself is a hidden file, and that in its place `libtool` creates a wrapper script, See [Section 10.5 \[Executing Uninstalled Binaries\]](#), page 96.

As with the Libtool libraries, you can pass additional switches for the `libtool` invocation in the qualified `‘LDFLAGS’` macros to control how the `shell` executable is linked:

`‘-all-static’`

Always choose static libraries where possible, and try to create a completely statically linked executable.

`‘-no-fast-install’`

If you really want to use this flag on some targets, you can pass it in an `‘LDFLAGS’` macro. This is not overridden by the `configure ‘--enable-fast-install’`



switch. Executables built with this flag will not need relinking to be executed from the build tree on platforms which might have otherwise required it.

**‘-no-install’**

You should use this option for any executables which are used only for testing, or for generating other files and are consequently never installed. By specifying this option, you are telling Libtool that the executable it links will only ever be executed from where it is built in the build tree. Libtool is usually able to considerably speed up the link process for such executables.

**‘-static’** This switch is similar to ‘-all-static’, except that it applies to only the uninstalled Libtool libraries in the build tree. Where possible the static archive from these libraries is used, but the default linking mode is used for libraries which are already installed.

When debugging an executable, for example, it can be useful to temporarily use:

```
shell_LDFLAGS = -all-static
```

You can pass Libtool link options to all of the targets in a given directory by using the unadorned ‘LDFLAGS’ macro:

```
LDFLAGS = -static
```

This is best reserved for directories which have targets of the same type, all Libtool libraries or all executables for instance. The technique still works in a mixed target type directory, and `libtool` will ignore switches which don’t make sense for particular targets. It is less maintainable, and makes it harder to understand what is going on if you do that though.

## 11.3 Using libtoolize

Having made the necessary editions in ‘configure.in’ and ‘Makefile.am’, all that remains is to add the Libtool infrastructure to your project.

First of all you must ensure that the correct definitions for the new macros you use in ‘configure.in’ are added to ‘aclocal.m4’, See [Appendix C \[Generated File Dependencies\]](#), [page 313](#). At the moment, the safest way to do this is to copy ‘libtool.m4’ from the installed `libtool` to ‘acinclude.m4’ in the toplevel source directory of your package. This is to ensure that when your package ships, there will be no mismatch errors between the M4 macros you provided in the version of `libtool` you built the distribution with, versus the version of the Libtool installation in another developer’s environment. In a future release, `libtool` will check that the macros in `aclocal.m4` are from the same Libtool distribution as the generated `libtool` script.

```
$ cp /usr/share/libtool/libtool.m4 ./acinclude.m4
$ aclocal
```

By naming the file ‘acinclude.m4’ you ensure that `aclocal` can see it and will use macros from it, and that `automake` will add it to the distribution when you create the tarball.

Next, you should run `libtoolize`, which adds some files to your distribution that are required by the macros from ‘`libtool.m4`’. In particular, you will get ‘`ltconfig`’<sup>3</sup> and ‘`ltmain.sh`’ which are used to create a custom `libtool` script on the installer’s machine.

If you do not yet have them, `libtoolize` will also add ‘`config.guess`’ and ‘`config.sub`’ to your distribution. Sometimes you don’t need to run `libtoolize` manually, since `automake` will run it for you when it sees the changes you have made to ‘`configure.in`’, as follows:

```
$ automake --add-missing
automake: configure.in: installing ./install-sh
automake: configure.in: installing ./mkinstalldirs
automake: configure.in: installing ./missing
configure.in: 8: required file ./ltconfig not found
```

The error message in the last line is an aberration. If it were consistent with the other lines, it would say:

```
automake: configure.in: installing ./ltconfig
automake: configure.in: installing ./ltmain.sh
automake: configure.in: installing ./config.guess
automake: configure.in: installing ./config.sub
```

But the effect is the same, and the files are correctly added to the distribution despite the misleading message.

Before you release a distribution of your project, it is wise to get the latest versions of ‘`config.guess`’ and ‘`config.sub`’ from the GNU site<sup>4</sup>, since they may be newer than the versions automatically added by `libtoolize` and `automake`. Note that `automake --add-missing` will give you its own version of these two files if ‘`AC_PROG_LIBTOOL`’ is not used in the project ‘`configure.in`’, but will give you the versions shipped with `libtool` if that macro is present!

## 11.4 Library Versioning

It is important to note from the outset that the version number of your project is a very different thing to the version number of any libraries shipped with your project. It is a common error for maintainers to try to force their libraries to have the same version number as the current release version of the package as a whole. At best, they will break binary compatibility unnecessarily, so that their users won’t gain the benefits of the changes in their latest revision without relinking all applications that use it. At worst, they will allow the runtime linker to load binary incompatible libraries, causing applications to crash.

Far better, the Libtool versioning system will build native shared libraries with the correct *native* library version numbers. Although different architectures use various numbering schemes, Libtool abstracts these away behind the system described here. The various native library version numbering schemes are designed so that when an executable is started, the runtime loader can, where appropriate, choose a more recent installed library version than the one with which the executable was actually built. This allows you to fix bugs in your

<sup>3</sup> The functionality of ‘`ltconfig`’ is slated for migration into ‘`libtool.m4`’ for a future release of `libtool`, whereupon this file will no longer be necessary.

<sup>4</sup> [ftp://ftp.gnu.org/gnu/config/](http://ftp.gnu.org/gnu/config/)

library, and having built it with the correct Libtool version number, have those fixes propagate into any executables that were built with the old buggy version. This can only work if the runtime loader can tell whether it can load the new library into the old executable and expect them to work together. The library version numbers give this information to the runtime loader, so it is very important to set them correctly.

The version scheme used by Libtool tracks *interfaces*, where an interface is the set of exported entry points into the library. All Libtool libraries start with ‘-version-info’ set to ‘0:0:0’ – this will be the default version number if you don’t explicitly set it on the Libtool link command line. The meaning of these numbers (from left to right) is as follows:

<i>current</i>	The number of the current interface exported by the library. A <i>current</i> value of ‘0’, means that you are calling the interface exported by this library <i>interface</i> 0.
<i>revision</i>	The implementation number of the most recent interface exported by this library. In this case, a <i>revision</i> value of ‘0’ means that this is the first implementation of the interface.  If the next release of this library exports the same interface, but has a different implementation (perhaps some bugs have been fixed), the <i>revision</i> number will be higher, but <i>current</i> number will be the same. In that case, when given a choice, the library with the highest <i>revision</i> will always be used by the runtime loader.
<i>age</i>	The number of previous additional interfaces supported by this library. If <i>age</i> were ‘2’, then this library can be linked into executables which were built with a release of this library that exported the current interface number, <i>current</i> , or any of the previous two interfaces.  By definition <i>age</i> must be less than or equal to <i>current</i> . At the outset, only the first ever interface is implemented, so <i>age</i> can only be ‘0’.

For later releases of a library, the ‘-version-info’ argument needs to be set correctly depending on any interface changes you have made. This is quite straightforward when you understand what the three numbers mean:

1. If you have changed any of the sources for this library, the *revision* number must be incremented. **This is a new revision of the current interface.**
2. If the interface has changed, then *current* must be incremented, and *revision* reset to ‘0’. **This is the first revision of a new interface.**
3. If the new interface is a superset of the previous interface (that is, if the previous interface has not been broken by the changes in this new release), then *age* must be incremented. **This release is backwards compatible with the previous release.**
4. If the new interface has removed elements with respect to the previous interface, then you have broken backward compatibility and *age* must be reset to ‘0’. **This release has a new, but backwards incompatible interface.**

For example, if the next release of the library included some new commands for an existing socket protocol, you would use `-version-info 1:0:1`. **This is the first revision of a new interface. This release is backwards compatible with the previous release.**

Later, you implement a faster way of handling part of the algorithm at the core of the library, and release it with `-version-info 1:1:1`. **This is a new revision of the current interface.**

Unfortunately the speed of your new implementation can only be fully exploited by changing the API to access the structures at a lower level, which breaks compatibility with the previous interface, so you release it as `-version-info 2:0:0`. **This release has a new, but backwards incompatible interface.**

When deciding which numbers to change in the `-version-info` argument for a new release, you must remember that an interface change is not limited to the API of the library. The notion of an interface must include any method by which a user (code or human) can interact with the library: adding new builtin commands to a shell library; the format used in an output file; the handshake protocol required for a client connecting over a socket, and so on.

Additionally, If you use a development model which has both a stable and an unstable tree being developed in parallel, for example, and you don't mind forcing your users to relink all of the applications which use one of your Libtool libraries every time you make a release, then libtool provides the `'-release'` flag to encode the project version number in the name of the library, See [Section 11.2.1 \[Creating Libtool Libraries with Automake\]](#), page 108. This can save you library compatibility problems later if you need to, say, make a patch release of an older revision of your library, but the library version number that you should use has already been taken by another earlier release. In this case, you could be fairly certain that library releases from the unstable branch will not be binary compatible with the stable releases, so you could make all the stable releases with `'-release 1.0'` and begin the first unstable release with `'-release 1.1'`.

## 11.5 Convenience Libraries

Sometimes it is useful to group objects together in an intermediate stage of a project's compilation to provide a useful handle for that group without having to specify all of the individual objects every time. Convenience libraries are a portable way of creating such a *partially linked* object: Libtool will handle all of the low level details in a way appropriate to the target host. This section describes the use of convenience libraries in conjunction with Automake. The principles of convenience libraries are discussed in [Section 10.2.4 \[Creating Convenience Libraries\]](#), page 87.

The key to creating Libtool convenience libraries with Automake is to use the `'noinst_LTLIBRARIES'` macro. For the Libtool libraries named in this macro, Automake will create Libtool convenience libraries which can subsequently be linked into other Libtool libraries.

In this section I will create two convenience libraries, each in their own subdirectory, and link them into a third Libtool library, which is ultimately linked into an application.

If you want to follow this example, you should create a directory structure to hold the sources by running the following shell commands:

```
$ mkdir convenience
$ cd convenience
$ mkdir lib
$ mkdir replace
```

The first convenience library is built from two source files in the ‘lib’ subdirectory.

1. ‘source.c’:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#if HAVE_MATH_H
# include <math.h>
#endif

void
foo (double argument)
{
    printf ("cos (%g) => %g\n", argument, cos (argument));
}
```

This file defines a single function to display the cosine of its argument on standard output, and consequently relies on an implementation of the `cos` function from the system libraries. Note the conditional inclusion of ‘`config.h`’, which will contain a definition of ‘`HAVE_MATH_H`’ if ‘`configure`’ discovers a ‘`math.h`’ system header (the usual location for the declaration of `cos`). The ‘`HAVE_CONFIG_H`’ guard is by convention, so that the source can be linked by passing the preprocessor macro definitions to the compiler on the command line – if ‘`configure.in`’ does not use ‘`AM_CONFIG_HEADER`’ for instance.

2. ‘source.h’:

```
extern void foo      (double argument);
```

For brevity, there is no `#ifndef SOURCE_H` guard. The header is not installed, so you have full control over where it is `#include`d, and in any case, function declarations can be safely repeated if the header is accidentally processed more than once. In a real program, it would be better to list the function parameters in the declaration so that the compiler can do type checking. This would limit the code to working only with ANSI compilers, unless you also use a `PARAMS` macro to conditionally preprocess away the parameters when a K&R compiler is used. These details are beyond the scope of this convenience library example, but are described in full in [Section 9.1.6 \[K&R Compilers\]](#), page 55.

You also need a ‘`Makefile.am`’ to hold the details of how this convenience library is linked:

```
## Makefile.am -- Process this file with automake to produce Makefile.in

noinst_LTLIBRARIES      = library.la
library_la_SOURCES      = source.c source.h
library_la_LIBADD       = -lm
```

The `'noinst_LTLIBRARIES'` macro names the Libtool convenience libraries to be built in this directory, `'library.la'`. Although not required for compilation, `'source.h'` is listed in the `'SOURCES'` macro of `'library.la'` so that correct source dependencies are generated, and so that it is added to the distribution tarball by `automake's 'dist'` rule.

Finally, since the `foo` function relies on the `cos` function from the system math library, `'-lm'` is named as a required library in the `'LIBADD'` macro. As with all Libtool libraries, interlibrary dependencies are maintained for convenience libraries so that you need only list the libraries you are using directly when you link your application later. The libraries used by those libraries are added by Libtool.

The parent directory holds the sources for the main executable, `'main.c'`, and for a (non-convenience) Libtool library, `'error.c'` & `'error.h'`.

Like `'source.h'`, the functions exported from the Libtool library `'liberror.la'` are listed in `'error.h'`:

```
extern void gratuitous      (void);
extern void set_program_name (char *path);
extern void error           (char *message);
```

The corresponding function definitions are in `'error.c'`:

```
#include <stdio.h>

#include "source.h"

static char *program_name = NULL;

void
gratuitous (void)
{
    /* Gratuitous display of convenience library functionality! */
    double argument = 0.0;
    foo (argument);
}

void
set_program_name (char *path)
{
    if (!program_name)
        program_name = basename (path);
}

void
error (char *message)
{
    fprintf (stderr, "%s: ERROR: %s\n", program_name, message);
    exit (1);
}
```

The `gratuitous()` function calls the `foo()` function defined in the ‘library.la’ convenience library in the ‘lib’ directory, hence ‘source.h’ is included.

The definition of `error()` displays an error message to standard error, along with the name of the program, `program_name`, which is set by calling `set_program_name()`. This function, in turn, extracts the basename of the program from the full path using the system function, `basename()`, and stores it in the library private variable, `program_name`.

Usually, `basename()` is part of the system C library, though older systems did not include it. Because of this, there is no portable header file that can be included to get a declaration, and you might see a harmless compiler warning due to the use of the function without a declaration. The alternative would be to add your own declaration in ‘error.c’. The problem with this approach is that different vendors will provide slightly different declarations (with or without `const` for instance), so compilation will fail on those architectures which *do* provide a declaration in the system headers that is different from the declaration you have guessed.

For the benefit of architectures which do not have an implementation of the `basename()` function, a fallback implementation is provided in the ‘replace’ subdirectory. The file ‘basename.c’ follows:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#if HAVE_STRING_H
# include <string.h>
#elif HAVE_STRINGS_H
# include <strings.h>
#endif

#if !HAVE_STRCHR
# ifndef strchr
#   define strchr rindex
# endif
#endif

char*
basename (char *path)
{
    /* Search for the last directory separator in PATH. */
    char *basename = strchr (path, '/');

    /* If found, return the address of the following character,
       or the start of the parameter passed in. */
    return basename ? ++basename : path;
}
```

For brevity, the implementation does not use any `const` declarations which would be good style for a real project, but would need to be checked at configure time in case the end user needs to compile the package with a K&R compiler.

The use of `strchr()` is noteworthy. Sometimes it is declared in `'string.h'`, otherwise it might be declared in `'strings.h'`. BSD based Unices, on the other hand, do not have this function at all, but provide an equivalent function, `rindex()`. The preprocessor code at the start of the file is designed to cope with all of these eventualities. The last block of preprocessor code assumes that if `strchr` is already defined that it holds a working macro, and does not redefine it.

'Makefile.am' contains:

```
## Makefile.am -- Process this file with automake to produce Makefile.in

noinst_LTLIBRARIES      = libreplace_la
libreplace_la_SOURCES    =
libreplace_la_LIBADD     = @LTLIBOBJS@
```

Once again, the `'noinst_LTLIBRARIES'` macro names the convenience library, `'libreplace_la'`. By default there are no sources, since we expect to have a system definition of `basename()`. Additional Libtool objects which should be added to the library based on tests at configure time are handled by the `'LIBADD'` macro. `'LTLIBOBJS'` will contain `'basename.lo'` if the system does not provide `basename`, and will be empty otherwise. Illustrating another feature of convenience libraries: on many architectures, `'libreplace_la'` will contain no objects.

Back in the toplevel project directory, all of the preceding objects are combined by another 'Makefile.am':

```
## Makefile.am -- Process this file with automake to produce Makefile.in

AUTOMAKE_OPTIONS        = foreign

SUBDIRS                  = replace lib .

CPPFLAGS                  = -I$(top_srcdir)/lib

include_HEADERS           = error.h

lib_LTLIBRARIES           = liberror_la
liberror_la_SOURCES       = error.c
liberror_la_LDFLAGS       = -no-undefined -version-info 0:0:0
liberror_la_LIBADD        = replace/libreplace_la lib/library_la

bin_PROGRAMS              = convenience
convenience_SOURCES       = main.c
convenience_LDADD         = liberror_la
```

The initial `'SUBDIRS'` macro is necessary to ensure that the libraries in the subdirectories are built before the final library and executable in this directory.



Notice that I have not listed ‘error.h’ in ‘liberror\_la\_SOURCES’ this time, since ‘liberror.la’ is an installed library, and ‘error.h’ defines the public interface to that library. Since the ‘liberror.la’ Libtool library is installed, I have used the ‘-version-info’ option, and I have also used ‘-no-undefined’ so that the project will compile on architectures which require all library symbols to be defined at link time – the reason `program_name` is maintained in ‘liberror’ rather than ‘main.c’ is so that the library does not have a run-time dependency on the executable which links it.

The key to this example is that by linking the ‘libreplace.la’ and ‘library.la’ convenience libraries into ‘liberror.la’, all of the objects in both convenience libraries are compiled into the single installed library, ‘liberror.la’. Additionally, all of the inter-library dependencies of the convenience libraries (‘-lm’, from ‘library.la’) are propagated to ‘liberror.la’.

A common difficulty people experience with Automake is knowing when to use a ‘LIBADD’ primary versus a ‘LDADD’ primary. A useful mnemonic is: ‘LIBADD’ is for **ADDITIONAL LIBRARY** objects. ‘LDADD’ is for **ADDITIONAL linker (LD) objects**.

The executable, ‘convenience’, is built from ‘main.c’, and requires only ‘liberror.la’. All of the other implicit dependencies are encoded within ‘liberror.la’. Here is ‘main.c’:

```
#include <stdio.h>
#include "error.h"

int
main (int argc, char *argv[])
{
    set_program_name (argv[0]);
    gratuitous ();
    error ("This program does nothing!");
}
```

The only file that remains before you can compile the example is ‘configure.in’:

```
# Process this file with autoconf to create configure.

AC_INIT(error.c)
AM_CONFIG_HEADER(config.h)
AM_INIT_AUTOMAKE(convenience, 1.0)

AC_PROG_CC
AM_PROG_LIBTOOL

AC_CHECK_HEADERS(math.h)
AC_CHECK_HEADERS(string.h strings.h, break)

AC_CHECK_FUNCS(strrchr)
AC_REPLACE_FUNCS(basename)

Xsed="sed -e s/^X//"
LTLIBOBJS=echo X"$LIBOBJS" | \
    $Xsed -e "s,\.[^.]* ,.lo ,g;s,\.[^.]*\$, .lo,""
```

```
AC_SUBST(LTLIBOBJ)
```

```
AC_OUTPUT(replace/Makefile lib/Makefile Makefile)
```

There are checks for all of the features used by the sources in the project: ‘math.h’ and either ‘string.h’ or ‘strings.h’; the existence of `strchr` (*after* the tests for string headers); adding ‘basename.o’ to ‘LIBOBJ’ if there is no system implementation; and the shell code to set ‘LTLIBOBJ’.

With all the files in place, you can now bootstrap the project:

```
$ ls -R
.:
Makefile.am  configure.in  error.c  error.h  lib  main.c  replace
lib:
Makefile.am  source.c  source.h

replace:
Makefile.am  basename.c
$ aclocal
$ autoheader
$ automake --add-missing --copy
automake: configure.in: installing ./install-sh
automake: configure.in: installing ./mkinstalldirs
automake: configure.in: installing ./missing
configure.in: 7: required file ./ltconfig not found
$ autoconf
$ ls -R
.:
Makefile.am  config.h.in  error.c  ltconfig  mkinstalldirs
Makefile.in  config.sub  error.h  ltmain.sh  replace
aclocal.m4    configure    install-sh  main.c
config.guess  configure.in  lib        missing
lib:
Makefile.am  Makefile.in  source.c  source.h

replace:
Makefile.am  Makefile.in  basename.c
```

With these files in place, the package can now be configured:

```
$ ./configure
...
checking how to run the C preprocessor... gcc -E
checking for math.h... yes
checking for string.h... yes
checking for strchr... yes
checking for basename... yes
updating cache ./config.cache
creating ./config.status
creating replace/Makefile
```

```
creating lib/Makefile
creating Makefile
creating config.h
```

Notice that my host has an implementation of `basename()`.

Here are the highlights of the compilation itself:

```
$ make
Making all in replace
make[1]: Entering directory /tmp/replace
/bin/sh ../libtool --mode=link gcc -g -O2 -o libreplace.la
rm -fr .libs/libreplace.la .libs/libreplace.* .libs/libreplace.*
ar cru .libs/libreplace.al
ranlib .libs/libreplace.al
creating libreplace.la
(cd .libs && rm -f libreplace.la && ln -s ../libreplace.la \
libreplace.la)
make[1]: Leaving directory /tmp/replace
```

Here the build descends into the ‘replace’ subdirectory and creates ‘libreplace.la’, which is empty on my host since I don’t need an implementation of `basename()`:

```
Making all in lib
make[1]: Entering directory /tmp/lib
/bin/sh ../libtool --mode=compile gcc -DHAVE_CONFIG_H -I. -I. \
-g -O2 -c source.c
rm -f .libs/source.lo
gcc -DHAVE_CONFIG_H -I. -I. -g -O2 -c -fPIC -DPIC source.c \
-o .libs/source.lo
gcc -DHAVE_CONFIG_H -I. -I. -g -O2 -c source.c \
-o source.o >/dev/null 2>&1
mv -f .libs/source.lo source.lo
/bin/sh ../libtool --mode=link gcc -g -O2 -o library.la source.lo -lm
rm -fr .libs/library.la .libs/library.* .libs/library.*
ar cru .libs/library.al source.lo
ranlib .libs/library.al
creating library.la
(cd .libs && rm -f library.la && ln -s ../library.la library.la)
make[1]: Leaving directory /tmp/lib
```

Next, the build enters the ‘lib’ subdirectory to build ‘library.la’. The ‘configure’ preprocessor macros are passed on the command line, since no ‘config.h’ was created by `AC_CONFIG_HEADER`:

Here, ‘main.c’ is compiled (not to a Libtool object, since it is not compiled using `libtool`), and linked with the ‘liberror.la’ Libtool library:

```
gcc -DHAVE_CONFIG_H -I. -I. -I./lib -g -O2 -c main.c
/bin/sh ../libtool --mode=link gcc -g -O2 -o convenience main.o \
liberror.la
gcc -g -O2 -o .libs/convenience main.o ../libs/liberror.so -lm \
-Wl,--rpath -Wl,/usr/local/lib
creating convenience
make[1]: Leaving directory /tmp/convenience
```

libtool calls `gcc` to link the convenience executable from `'main.o'` and the shared library component of `'liberror.la'`. libtool also links with `'-lm'`, the propagated inter-library dependency of the `'library.la'` convenience library. Since `'libreplace.la'` and `'library.la'` were convenience libraries, their objects are already present in `'liberror.la'`, so they are not listed again in the final link line – the whole point of convenience archives.

This just shows that it all works:

```
$ ls
Makefile      config.h      configure.in  install-sh   main.c
Makefile.am   config.h.in   convenience   lib          main.o
Makefile.in   config.log    error.c       liberror.la  missing
aclocal.m4    config.status error.h       libtool      mkinstalldirs
config.cache  config.sub    error.lo      ltconfig     replace
config.guess  configure     error.o       ltmain.sh

$ libtool --mode=execute ldd convenience
      liberror.so.0 => /tmp/.libs/liberror.so.0 (0x40014000)
      libm.so.6 => /lib/libm.so.6 (0x4001c000)
      libc.so.6 => /lib/libc.so.6 (0x40039000)
      /lib/ld-linux.so.2 => /lib/ld-linux.so.2 (0x40000000)

$ ./convenience
cos (0) => 1
lt-convenience: ERROR: This program does nothing!
```

Notice that you are running the uninstalled executable, which is in actual fact a wrapper script, See [Section 10.5 \[Executing Uninstalled Binaries\]](#), page 96. That is why you need to use libtool to run `ldd` on the real executable. The uninstalled executable called by the wrapper script is called `lt-convenience`, hence the output from `basename()`.

Finally, you can see from the output of `ldd`, that `convenience` really isn't linked against either `'library.la'` and `'libreplace.la'`.

## 12 A Large GNU Autotools Project

This chapter develops the worked example described in [Chapter 9 \[A Small GNU Autotools Project\]](#), [page 51](#). Again, the example is heavily colored by my own views, and there certainly are other, very different, but equally valid ways of achieving the same objectives.

I will explain how I incorporated `libtool` into the Sic project, and how to put the project documentation and test suite under the control of GNU Autotools. I pointed out some problems with the project when I first introduced it – this chapter will address those issues, and present my favored solution to each.

### 12.1 Using Libtool Libraries

As you have seen, It is very easy to convert `automake` built static libraries to `automake` built Libtool libraries. In order to build ‘`libsic`’ as a Libtool library, I have changed the name of the library from ‘`libsic.a`’ (the *old archive* name in Libtool terminology) to ‘`libsic.la`’ (the *pseudo-library*), and must use the `LTLIBRARIES` Automake primary:

```
lib_LTLIBRARIES      = libsic.la
libsic_la_LIBADD     = $(top_builddir)/replace/libreplace.la
libsic_la_SOURCES    = builtin.c error.c eval.c list.c sic.c \
                      syntax.c xmalloc.c xstrdup.c xstrerror.c
```

Notice the ‘`la`’ in `libsic_la_SOURCES` is new too.

It is similarly easy to take advantage of Libtool *convenience* libraries. For the purposes of Sic, ‘`libreplace`’ is an ideal candidate for this treatment – I can create the library as a separate entity from selected sources in their own directory, and add those objects to ‘`libsic`’. This technique ensures that the installed library has all of the support functions it needs without having to link ‘`libreplace`’ as a separate object.

In ‘`replace/Makefile.am`’, I have again changed the name of the library from ‘`libreplace.a`’ to ‘`libreplace.la`’, and changed the automake primary from ‘`LIBRARIES`’ to ‘`LTLIBRARIES`’. Unfortunately, those changes alone are insufficient. Libtool libraries are compiled from Libtool objects (which have the ‘`.lo`’ suffix), so I cannot use ‘`LIBOBJS`’ which is a list of ‘`.o`’ suffixed objects<sup>1</sup>. See [Section 11.1.2 \[Extra Macros for Libtool\]](#), [page 106](#), for more details. Here is ‘`replace/Makefile.am`’:

```
MAINTAINERCLEANFILES = Makefile.in

noinst_LTLIBRARIES    = libreplace.la
libreplace_la_SOURCES =
libreplace_la_LIBADD   = @LTLIBOBJS@
```

And not forgetting to set and use the ‘`LTLIBOBJS`’ configure substitution (see [Section 11.1.2 \[Extra Macros for Libtool\]](#), [page 106](#)):

```
Xsed="sed -e s/^X//"
LTLIBOBJS=echo X"$LTLIBOBJS" | \
```

---

<sup>1</sup> Actually the suffix will be whatever is appropriate for the target host: such as ‘`.obj`’ on Windows for example.

```

[$Xsed -e s,\.[^.]* ,.lo ,g;s,\.[^.]*$, .lo,']
AC_SUBST(LTLIBOBJ)

```

As a consequence of using `libtool` to build the project libraries, the increasing number of configuration files being added to the ‘`config`’ directory will grow to include ‘`ltconfig`’ and ‘`ltmain.sh`’. These files will be used on the installer’s machine when `Sic` is configured, so it is important to distribute them. The naive way to do it is to give the ‘`config`’ directory a ‘`Makefile.am`’ of its own; however, it is not too difficult to distribute these files from the top ‘`Makefile.am`’, and it saves clutter, as you can see here:

```

AUX_DIST                = $(ac_aux_dir)/config.guess \
                        $(ac_aux_dir)/config.sub \
                        $(ac_aux_dir)/install-sh \
                        $(ac_aux_dir)/ltconfig \
                        $(ac_aux_dir)/ltmain.sh \
                        $(ac_aux_dir)/mdate-sh \
                        $(ac_aux_dir)/missing \
                        $(ac_aux_dir)/mkinstalldirs
AUX_DIST_EXTRA          = $(ac_aux_dir)/readline.m4 \
                        $(ac_aux_dir)/sys_errlist.m4 \
                        $(ac_aux_dir)/sys_siglist.m4
EXTRA_DIST              = bootstrap

MAINTAINERCLEANFILES    = Makefile.in aclocal.m4 configure config-h.in \
                        stamp-h.in $(AUX_DIST)

dist-hook:
    (cd $(distdir) && mkdir $(ac_aux_dir))
    for file in $(AUX_DIST) $(AUX_DIST_EXTRA); do \
        cp $$file $(distdir)/$$file; \
    done

```

The ‘`dist-hook`’ rule is used to make sure the ‘`config`’ directory and the files it contains are correctly added to the distribution by the ‘`make dist`’ rules, see [Section 13.1 \[Introduction to Distributions\]](#), page 139.

I have been careful to use the `configure` script’s location for `ac_aux_dir`, so that it is defined (and can be changed) in only one place. This is achieved by adding the following macro to ‘`configure.in`’:

```
AC_SUBST(ac_aux_dir)
```

There is no need to explicitly set a macro in the ‘`Makefile.am`’, because Automake automatically creates macros for every value that you ‘`AC_SUBST`’ from ‘`configure.in`’.

I have also added the `AC_PROG_LIBTOOL` macro to ‘`configure.in`’ in place of `AC_PROG_RANLIB` as described in [Chapter 11 \[Using GNU Libtool\]](#), page 103.

Now I can upgrade the `configury` to use `libtool` – the greater part of this is running the `libtoolize` script that comes with the Libtool distribution. The `bootstrap` script then needs to be updated to run `libtoolize` at the correct juncture:

```
#! /bin/sh
```

```

set -x
aclocal -I config
libtoolize --force --copy
autoheader
automake --add-missing --copy
autoconf

```

Now I can re-bootstrap the entire project so that it can make use of libtool:

```

$ ./bootstrap
+ aclocal -I config
+ libtoolize --force --copy
Putting files in AC_CONFIG_AUX_DIR, config.
+ autoheader
+ automake --add-missing --copy
automake: configure.in: installing config/install-sh
automake: configure.in: installing config/mkinstalldirs
automake: configure.in: installing config/missing
+ autoconf

```

The new macros are evident by the new output seen when the newly regenerated `configure` script is executed:

```

$ ./configure --with-readline
...
checking host system type... i586-pc-linux-gnu
checking build system type... i586-pc-linux-gnu
checking for ld used by GCC... /usr/bin/ld
checking if the linker (/usr/bin/ld) is GNU ld... yes
checking for /usr/bin/ld option to reload object files... -r
checking for BSD-compatible nm... /usr/bin/nm -B
checking whether ln -s works... yes
checking how to recognise dependent libraries... pass_all
checking for object suffix... o
checking for executable suffix... no
checking for ranlib... ranlib
checking for strip... strip
...
checking if libtool supports shared libraries... yes
checking whether to build shared libraries... yes
checking whether to build static libraries... yes
creating libtool
...
$ make
...
gcc -g -O2 -o .libs/sic sic.o sic_builtin.o sic_repl.o sic_syntax.o \
../sic/.libs/libsic.so -lreadline -Wl,--rpath -Wl,/usr/local/lib
creating sic
...

```

```
$ src/sic
] libtool --mode=execute ldd src/sic
    libsic.so.0 => /tmp/sic/sic/.libs/libsic.so.0 (0x40014000)
    libreadline.so.4 => /lib/libreadline.so.4 (0x4001e000)
    libc.so.6 => /lib/libc.so.6 (0x40043000)
    libncurses.so.5 => /lib/libncurses.so.5 (0x40121000)
    /lib/ld-linux.so.2 => /lib/ld-linux.so.2 (0x40000000)
] exit
$
```

As you can see, `sic` is now linked against a shared library build of ‘`libsic`’, but not directly against the convenience library, ‘`libreplace`’.

## 12.2 Removing ‘`--foreign`’

Now that I have the bulk of the project in place, I want it to adhere to the GNU standard layout. By removing the ‘`--foreign`’ option from the call to `automake` in the `bootstrap` file, `automake` is able to warn me about missing, or in some cases<sup>2</sup>, malformed files, as follows:

```
$ ./bootstrap
+ aclocal -I config
+ libtoolize --force --copy
Putting files in AC_CONFIG_AUX_DIR, config.
+ autoheader
+ automake --add-missing --copy
automake: Makefile.am: required file ./NEWS not found
automake: Makefile.am: required file ./README not found
automake: Makefile.am: required file ./AUTHORS not found
automake: Makefile.am: required file ./THANKS not found
+ autoconf
```

The GNU standards book<sup>3</sup> describes the contents of these files in more detail. Alternatively, take a look at a few other GNU packages from [ftp://ftp.gnu.org/gnu](http://ftp.gnu.org/gnu).

## 12.3 Installing Header Files

One of the more difficult problems with GNU Autotools driven projects is that each of them depends on ‘`config.h`’ (or its equivalent) and the project specific symbols that it defines. The purpose of this file is to be `#included` from all of the project source files. The preprocessor can tailor then the code in these files to the target environment.

It is often difficult and sometimes impossible to not introduce a dependency on ‘`config.h`’ from one of the project’s installable header files. It would be nice if you could simply install the generated ‘`config.h`’, but even if you name it carefully or install it to a subdirectory to avoid filename problems, the macros it defines will clash with those from any other GNU Autotools based project which also installs *its* ‘`config.h`’.

<sup>2</sup> For example, when I come to using the ‘`make dist`’ rule.

<sup>3</sup> The GNU standard is distributed from <http://www.gnu.org/prep/standards.html>.



For example, if Sic installed its `config.h` as `/usr/include/sic/config.h`, and had `#include <sic/config.h>` in the installed `common.h`, when another GNU Autotools based project came to use the Sic library it might begin like this:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#if HAVE_SIC_H
# include <sic.h>
#endif

static const char version_number[] = VERSION;
```

But, `sic.h` says `#include <sic/common.h>`, which in turn says `#include <sic/config.h>`. Even though the other project has the correct value for `VERSION` in its own `config.h`, by the time the preprocessor reaches the `version_number` definition, it has been redefined to the value in `sic/config.h`. Imagine the mess you could get into if you were using several libraries which each installed their own `config.h` definitions. GCC issues a warning when a macro is redefined to a different value which would help you to catch this error. Some compilers do not issue a warning, and perhaps worse, other compilers will warn even if the repeated definitions have the same value, flooding you with hundreds of warnings for each source file that reads multiple `config.h` headers.

The Autoconf macro `AC_OUTPUT_COMMANDS`<sup>4</sup> provides a way to solve this problem. The idea is to generate a system specific but installable header from the results of the various tests performed by `configure`. There is a 1-to-1 mapping between the preprocessor code that relied on the configure results written to `config.h`, and the new shell code that relies on the configure results saved in `config.cache`.

The following code is a snippet from `configure.in`, in the body of the `AC_OUTPUT_COMMANDS` macro:

```
# Add the code to include these headers only if autoconf has
# shown them to be present.
if test x$ac_cv_header_stdlib_h = xyes; then
    echo '#include <stdlib.h>' >> $tmpfile
fi
if test x$ac_cv_header_unistd_h = xyes; then
    echo '#include <unistd.h>' >> $tmpfile
fi
if test x$ac_cv_header_sys_wait_h = xyes; then
    echo '#include <sys/wait.h>' >> $tmpfile
fi
if test x$ac_cv_header_errno_h = xyes; then
    echo '#include <errno.h>' >> $tmpfile
fi
```

---

<sup>4</sup> This is for Autoconf version 2.13. Autoconf version 2.50 recommends `AC_CONFIG_COMMANDS`.

```

        cat >> $tmpfile << '_EOF_'
#ifndef errno
/* Some systems #define this! */
extern int errno;
#endif
_EOF_
    if test x$ac_cv_header_string_h = xyes; then
        echo '#include <string.h>' >> $tmpfile
    elif test x$ac_cv_header_strings_h = xyes; then
        echo '#include <strings.h>' >> $tmpfile
    fi
    if test x$ac_cv_header_assert_h = xyes; then
        cat >> $tmpfile << '_EOF_'

#include <assert.h>
#define SIC_ASSERT assert

_EOF_
    else
        echo '#define SIC_ASSERT(expr) ((void) 0)' >> $tmpfile
    fi

```

Compare this with the equivalent C pre-processor code from 'sic/common.h', which it replaces:

```

#if STDC_HEADERS || HAVE_STDLIB_H
# include <stdlib.h>
#endif

#if HAVE_UNISTD_H
# include <unistd.h>
#endif

#if HAVE_SYS_WAIT_H
# include <sys/wait.h>
#endif

#if HAVE_ERRNO_H
# include <errno.h>
#endif
#ifndef errno
/* Some systems #define this! */
extern int errno;
#endif

#if HAVE_STRING_H
# include <string.h>
#else
# if HAVE_STRINGS_H
#   include <strings.h>

```

```
# endif
#endif

#if HAVE_ASSERT_H
# include <assert.h>
# define SIC_ASSERT assert
#else
# define SIC_ASSERT(expr) ((void) 0)
#endif
```

Apart from the mechanical process of translating the preprocessor code, there is some plumbing needed to ensure that the ‘common.h’ file generated by the new code in ‘configure.in’ is functionally equivalent to the old code, and is generated in a correct and timely fashion.

Taking my lead from some of the Automake generated `make` rules to regenerate ‘Makefile’ from ‘Makefile.in’ by calling ‘config.status’, I have added some similar rules to ‘sic/Makefile.am’ to regenerate ‘common.h’ from ‘common-h.in’.

```
# Regenerate common.h with config.status whenever common-h.in changes.
common.h: stamp-common
    @:
stamp-common: $(srcdir)/common-h.in $(top_builddir)/config.status
    cd $(top_builddir) \
        && CONFIG_FILES= CONFIG_HEADERS= CONFIG_OTHER=sic/common.h \
        $(SHELL) ./config.status
    echo timestamp > $@
```

The way that `AC_OUTPUT_COMMANDS` works, is to copy the contained code into `config.status` (see [Appendix C \[Generated File Dependencies\]](#), page 313). It is actually `config.status` that creates the generated files – for example, automake generated ‘Makefile’s are able to regenerate themselves from corresponding ‘Makefile.in’s by calling `config.status` if they become out of date. Unfortunately, this means that `config.status` doesn’t have direct access to the cache values generated while `configure` was running (because it has finished its work by the time `config.status` is called). It is tempting to read in the cache file at the top of the code inside `AC_OUTPUT_COMMANDS`, but that only works if you know where the cache file is saved. Also the package installer can use the ‘--cache-file’ option of `configure` to change the location of the file, or turn off caching entirely with ‘--cache-file=/dev/null’.

`AC_OUTPUT_COMMANDS` accepts a second argument which can be used to pass the variable settings discovered by `configure` into `config.status`. It’s not pretty, and is a little error prone. In the first argument to `AC_OUTPUT_COMMANDS`, you must be careful to check that **every single** `configure` variable referenced is correctly set somewhere in the second argument.

A slightly stripped down example from the sic project ‘configure.in’ looks like this:

```
# -----
# Add code to config.status to create an installable host dependent
# configuration file.
# -----
AC_OUTPUT_COMMANDS([
```

```

if test -n "$CONFIG_FILES" && test -n "$CONFIG_HEADERS"; then
  # If both these vars are non-empty, then config.status wasn't run by
  # automake rules (which always set one or the other to empty).
  CONFIG_OTHER=${CONFIG_OTHER-sic/common.h}
fi
case "$CONFIG_OTHER" in
*sic/common.h*)
  outfile=sic/common.h
  stampfile=sic/stamp-common
  tmpfile=${outfile}T
  dirname="sed s,^.*/, ,g"

  echo creating $outfile
  cat > $tmpfile << _EOF_
/*  -*- Mode: C -*-
* -----
* DO NOT EDIT THIS FILE!  It has been automatically generated
* from:      configure.in and 'echo $outfile|$dirname'.in
* on host: '(hostname || uname -n) 2>/dev/null | sed 1q'
* -----
*/

#ifdef SIC_COMMON_H
#define SIC_COMMON_H 1

#include <stdio.h>
#include <sys/types.h>
_EOF_

  if test x$ac_cv_func_bzero = xno && \
      test x$ac_cv_func_memset = xyes; then
    cat >> $tmpfile << '_EOF_'
#define bzero(buf, bytes) ((void) memset (buf, 0, bytes))
_EOF_
  fi
  if test x$ac_cv_func_strchr = xno; then
    echo '#define strchr index' >> $tmpfile
  fi
  if test x$ac_cv_func_strrchr = xno; then
    echo '#define strrchr rindex' >> $tmpfile
  fi

  # The ugly but portable cpp stuff comes from here
  infile=$srcdir/sic/'echo $outfile | sed 's,.*/, ,g;s,\..*$, ,g' '-h.in
  sed '/^##.*$/d' $infile >> $tmpfile

],[
srcdir=$srcdir
ac_cv_func_bzero=$ac_cv_func_bzero

```

```

ac_cv_func_memset=$ac_cv_func_memset
ac_cv_func_strchr=$ac_cv_func_strchr
ac_cv_func_strrchr=$ac_cv_func_strrchr
])

```

You will notice that the contents of ‘common-h.in’ are copied into ‘common.h’ verbatim as it is generated. It’s just an easy way of collecting together the code that belongs in ‘common.h’, but which doesn’t rely on configuration tests, without cluttering ‘configure.in’ any more than necessary.

I should point out that, although this method has served me well for a number of years now, it is inherently fragile because it relies on undocumented internals of both Autoconf and Automake. There is a very real possibility that if you also track the latest releases of GNU Autotools, it may stop working. Future releases of GNU Autotools will address the interface problems that force us to use code like this, for the lack of a better way to do things.

## 12.4 Including Texinfo Documentation

Automake provides a few facilities to make the maintenance of Texinfo documentation within projects much simpler than it used to be. Writing a ‘Makefile.am’ for Texinfo documentation is extremely straightforward:

```

## Process this file with automake to produce Makefile.in

MAINTAINERCLEANFILES    = Makefile.in
info_TEXINFOS            = sic.texi

```

The ‘TEXINFOS’ primary will not only create rules for generating ‘.info’ files suitable for browsing with the GNU info reader, but also for generating ‘.dvi’ and ‘.ps’ documentation for printing.

You can also create other formats of documentation by adding the appropriate **make** rules to ‘Makefile.am’. For example, because the more recent Texinfo distributions have begun to support generation of HTML documentation from the ‘.texi’ format master document, I have added the appropriate rules to the ‘Makefile.am’:

```

SUFFIXES                = .html

html_docs                = sic.html

.texi.html:
    $(MAKEINFO) --html $<

.PHONY: html
html: version.texi $(html_docs)

```

For ease of maintenance, these **make** rules employ a suffix rule which describes how to generate HTML from equivalent ‘.texi’ source – this involves telling make about the ‘.html’ suffix using the automake **SUFFIXES** macro. I haven’t defined ‘MAKEINFO’ explicitly (though

I could have done) because I know that Automake has already defined it for use in the ‘.info’ generation rules.

The ‘html’ target is for convenience; typing ‘make html’ is a little easier than typing ‘make sic.html’. I have also added a .PHONY target so that featureful make programs will know that the ‘html’ target doesn’t actually generate a file called literally, ‘html’. As it stands, this code is not quite complete, since the toplevel ‘Makefile.am’ doesn’t know how to call the ‘html’ rule in the ‘doc’ subdirectory.

There is no need to provide a general solution here in the way Automake does for its ‘dvi’ target, for example. A simple recursive call to ‘doc/Makefile’ is much simpler:

```
docdir                = $(top_builddir)/doc

html:
    @echo Making $@ in $(docdir)
    @cd $(docdir) && make $@
```

Another useful management function that Automake can perform for you with respect to Texinfo documentation is to automatically generate the version numbers for your Texinfo documents. It will add make rules to generate a suitable ‘version.texi’, so long as automake sees ‘@include version.texi’ in the body of the Texinfo source:

```
\input texinfo    @c -*-texinfo-*-
@c %**start of header
@setfilename sic.info
@settitle Dynamic Modular Interpreter Prototyping
@setchapternewpage odd
@c %**end of header
@headings          double

@include version.texi

@dircategory Programming
@direntry
* sic: (sic).    The dynamic, modular, interpreter prototyping tool.
@end direntry

@ifinfo
This file documents sic.

@end ifinfo

@titlepage
@sp 10
@title Sic
@subtitle Edition @value{EDITION}, @value{UPDATED}
@subtitle $Id: sic.texi,v 1.1 2004/03/16 07:08:18 joostvb Exp $
@author Gary V. Vaughan

@page
@vskip 0pt plus 1filll
```

```
@end titlepage
```

‘version.texi’ sets Texinfo variables, ‘VERSION’, ‘EDITION’ and ‘UPDATE’, which can be expanded elsewhere in the main Texinfo documentation by using @value{EDITION} for example. This makes use of another auxiliary file, `mdate-sh` which will be added to the scripts in the `$ac_aux_dir` subdirectory by Automake after adding the ‘version.texi’ reference to ‘sic.texi’:

```
$ ./bootstrap
+ aclocal -I config
+ libtoolize --force --copy
Putting files in AC_CONFIG_AUX_DIR, config.
+ autoheader
+ automake --add-missing --copy
doc/Makefile.am:22: installing config/mdate-sh
+ autoconf
$ make html
/bin/sh ./config.status --recheck
...
Making html in ./doc
make[1]: Entering directory /tmp/sic/doc
Updating version.texi
makeinfo --html sic.texi
make[1]: Leaving directory /tmp/sic/doc
```

Hopefully, it now goes without saying that I also need to add the ‘doc’ subdirectory to ‘AC\_OUTPUT’ in ‘configure.in’ and to ‘SUBDIRS’ in the top-level ‘Makefile.am’.

## 12.5 Adding a Test Suite

Automake has very flexible support for automated test-suites within a project distribution, which are discussed more fully in the Automake manual. I have added a simple shell script based testing facility to Sic using this support – this kind of testing mechanism is perfectly adequate for command line projects. The tests themselves simply feed prescribed input to the uninstalled `sic` interpreter and compare the actual output with what is expected.

Here is one of the test scripts:

```
## -*- sh -*-
## incomplete.test -- Test incomplete command handling

# Common definitions
if test -z "$srcdir"; then
  srcdir=echo "$0" | sed s,[^/]*$,.,'
  test "$srcdir" = "$0" && srcdir=.
  test -z "$srcdir" && srcdir=.
  test "${VERBOSE+set}" != set && VERBOSE=1
fi
. $srcdir/defs
```

```

# this is the test script
cat <<\EOF > in.sic
echo "1
2
3"
EOF

# this is the output we should expect to see
cat <<\EOF >ok
1
2
3
EOF

cat <<\EOF >errok
EOF

# Run the test saving stderr to a file, and showing stdout
# if VERBOSE == 1
$RUNSIC in.sic 2> err | tee -i out >&2

# Test against expected output
if ${CMP} -s out ok; then
:
else
    echo "ok:" >&2
    cat ok >&2
    exit 1
fi

# Munge error output to remove leading directories, 'lt-' or
# trailing '.exe'
sed -e "s,^[^:]*[lt-]*sic[.ex]*:,sic:," err >sederr && mv sederr err

# Show stderr if doesnt match expected output if VERBOSE == 1
if "$CMP" -s err errok; then
:
else
    echo "err:" >&2
    cat err >&2
    echo "errok:" >&2
    cat errok >&2
    exit 1
fi

```

The tricky part of this script is the first part which discovers the location of (and loads) `'$srcdir/defs'`. It is a little convoluted because it needs to work if the user has compiled the project in a separate build tree – in which case the `'defs'` file is in a separate source tree and not in the actual directory in which the test is executed.



The 'defs' file allows me to factor out the common definitions from each of the test files so that it can be maintained once in a single file that is read by all of the tests:

```
#!/bin/sh

# Make sure srcdir is an absolute path. Supply the variable
# if it does not exist. We want to be able to run the tests
# stand-alone!!
#
srcdir=${srcdir-.}
if test ! -d $srcdir ; then
    echo "defs: installation error" 1>&2
    exit 1
fi

# IF the source directory is a Unix or a DOS root directory, ...
#
case "$srcdir" in
    /* | [A-Za-z]:\*) ;;
    *) srcdir='\cd $srcdir && pwd' ;;
esac

case "$top_builddir" in
    /* | [A-Za-z]:\*) ;;
    *) top_builddir='\cd ${top_builddir-..} && pwd' ;;
esac

progname='echo "$0" | sed 's,^./,,'
testname='echo "$progname" | sed 's,-.*$,,'
testsubdir=${testsubdir-testSubDir}

SIC_MODULE_PATH=$top_builddir/modules
export SIC_MODULE_PATH

# User can set VERBOSE to prevent output redirection
case x$VERBOSE in
    xNO | xno | x0 | x)
        exec > /dev/null 2>&1
        ;;
esac

rm -rf $testsubdir > /dev/null 2>&1
mkdir $testsubdir
cd $testsubdir \
    || { echo "Cannot make or change into $testsubdir"; exit 1; }

echo "=== Running test $progname"

CMP="${CMP-cmp}"
RUNSIC="${top_builddir}/src/sic"
```

Having written a few more test scripts, and made sure that they are working by running them from the command line, all that remains is to write a suitable ‘Makefile.am’ so that automake can run the test suite automatically.

```
## Makefile.am -- Process this file with automake to produce Makefile.in

EXTRA_DIST          = defs $(TESTS)
MAINTAINERCLEANFILES = Makefile.in

testsubdir          = testSubDir

TESTS_ENVIRONMENT   = top_builddir=$(top_builddir)

TESTS               =
                    empty-eval.test      \
                    empty-eval-2.test     \
                    empty-eval-3.test     \
                    incomplete.test       \
                    multicmd.test

distclean-local:
    -rm -rf $(testsubdir)
```

I have used the ‘testsubdir’ macro to run the tests in their own subdirectory so that the directory containing the actual test scripts is not polluted with lots of fallout files generated by running the tests. For completeness I have used a *hook target*<sup>5</sup> to remove this subdirectory when the user types:

```
$ make distclean
...
rm -rf testSubDir
...
```

Adding more tests is accomplished by creating a new test script and adding it to the list in `noinst_SCRIPTS`. Remembering to add the new ‘tests’ subdirectory to ‘configure.in’ and the top-level ‘Makefile.am’, and reconfiguring the project to propagate the changes into the various generated files, I can run the whole test suite from the top directory with:

```
$ make check
```

It is often useful run tests in isolation, either when developing new tests, or to examine more closely why a test has failed unexpectedly. Having set this test suite up as I did, individual tests can be executed with:

```
$ VERBOSE=1 make check TESTS=incomplete.test
make check-TESTS
make[1]: Entering directory
/tmp/sic/tests
=== Running test incomplete.test
1
```

---

<sup>5</sup> This is a sort of callback function which will be called by the `make` rules generated by Automake.

```
2
3
PASS: incomplete.test
=====
All 1 tests passed
=====
make[1]: Leaving directory /tmp/sic/tests
$ ls testSubDir/
err  errok  in.sic  ok  out
```

The ‘testSubDir’ subdirectory now contains the expected and actual output from that particular test for both ‘stdout’ and ‘stderr’, and the input file which generated the actual output. Had the test failed, I would be able to look at these files to decide whether there is a bug in the program or simply a bug in the test script. Being able to examine individual tests like this is invaluable, especially when the test suite becomes very large – because you will, naturally, add tests every time you add features to a project or find and fix a bug.

Another alternative to the pure shell based test mechanism I have presented here is the Autotest facility by François Pinard, as used in Autoconf after release 2.13.

Later in [Chapter 20 \[A Complex GNU Autotools Project\]](#), [page 209](#), the Sic project will be revisited to take advantage of some of the more advanced features of GNU Autotools. But first these advanced features will be discussed in the next several chapters – starting, in the next chapter, with a discussion of how GNU Autotools can help you to make a tarred distribution of your own projects.



## 13 Rolling Distribution Tarballs

There's something about the word 'tarballs' that make you want to avoid them altogether, let alone get involved in the disgusting process of rolling one. And, in the past, that was apparently the attitude of most developers, as witnessed by the strange ways distribution tar archives were created and unpacked. Automake largely automates this tedious process, in a sense providing you with the obliviousness you crave.

### 13.1 Introduction to Distributions

The basic approach to creating a tar distribution is to run

```
make
make dist
```

The generated tar file is named *package-version.tar.gz*, and will unpack into a directory named *package-version*. These two rules are mandated by the GNU Coding Standards, and are just good ideas in any case, because it is convenient for the end user to have the version information easily accessible while building a package. It removes any doubt when she goes back to an old tree after some time away from it. Unpacking into a fresh directory is always a good idea – in the old days some packages would unpack into the current directory, requiring an annoying clean-up job for the unwary system administrator.

The unpacked archive is completely portable, to the extent of Automake's ability to enforce this. That is, all the generated files (e.g., 'configure') are newer than their inputs (e.g., 'configure.in'), and the distributed 'Makefile.in' files should work with any version of **make**. Of course, some of the responsibility for portability lies with you: you are free to introduce non-portable code into your 'Makefile.am', and Automake can't diagnose this. No special tools beyond the minimal tool list (see [section "Utilities in Makefiles" in \*The GNU Coding Standards\*](#)) plus whatever your own 'Makefile' and 'configure' additions use, will be required for the end user to build the package.

By default Automake creates a '.tar.gz' file. It notices if you are using GNU **tar** and arranges to create portable archives in this case.<sup>1</sup>

People do sometimes want to make other sorts of distributions. Automake allows this through the use of options.

#### dist-bzip2

Add a **dist-bzip2** target, which creates a '.tar.bz2' file. These files are frequently smaller than the corresponding '.tar.gz' file.

#### dist-shar

Add a **dist-shar** target, which creates a **shar** archive.

**dist-zip** Add a **dist-zip** target, which creates a **zip** file. These files are popular for Windows distributions.

#### dist-tarZ

Add a **dist-tarZ** target, which creates a '.tar.Z' file. This exists mostly for die-hard old-time Unix hackers; the rest of the world has moved on to **gzip** or **bzip2**.

---

<sup>1</sup> By default, GNU **tar** can create non-portable archives in certain (rare) situations. To be safe, Automake arranges to use the '-o' compatibility flag when GNU **tar** is used.

## 13.2 What goes in

Automake tries to make creating a distribution as easy as possible. The rules are set up by default to distribute those things which Automake knows belong in a distribution. For instance, Automake always distributes your ‘configure’ script and your ‘NEWS’ file. All the files Automake automatically distributes are shown by `automake --help`:

```
$ automake --help
...
Files which are automatically distributed, if found:
  ABOUT-GNU      README      config.guess      ltconfig
  ABOUT-NLS      THANKS      config.h.bot      ltmain.sh
  AUTHORS        TODO        config.h.top      mdate-sh
  BACKLOG        acconfig.h   config.sub        missing
  COPYING        acinclude.m4  configure         mkinstalldirs
  COPYING.LIB    aclocal.m4   configure.in      stamp-h.in
  ChangeLog      ansi2knr.1   elisp-comp        stamp-vti
  INSTALL        ansi2knr.c   install-sh        texinfo.tex
  NEWS          compile     libversion.in     ywrap
...
```

Automake also distributes some files about which it has no built-in knowledge, but about which it learns from your ‘Makefile.am’. For instance, the source files listed in a ‘\_SOURCES’ variable go into the distribution. This is why you ought to list uninstalled header files in the ‘\_SOURCES’ variable: otherwise you’ll just have to introduce another variable to distribute them – Automake will only know about them if you tell it.

Not all primaries are distributed by default. The rule is arbitrary, but pretty simple: of all the primaries, only ‘\_TEXINFOS’ and ‘\_HEADERS’ are distributed by default. (Sources that make up programs and libraries are also distributed by default, but, perhaps confusingly, ‘\_SOURCES’ is not considered a primary.)

While there is no rhyme, there is a reason: defaults were chosen based on feedback from users. Typically, ‘enough’ reports of the form ‘I auto-generate my ‘\_SCRIPTS’. How do I prevent them from ending up in the distribution?’ would cause a change in the default.

Although the defaults are adequate in many situations, sometimes you have to distribute files which aren’t covered automatically. It is easy to add additional files to a distribution; simply list them in the macro ‘EXTRA\_DIST’. You can list files in subdirectories here. You can also list a directory’s name here and the entire contents will be copied into the distribution by `make dist`. Use this last feature with care. A typical failure is that you’ll put a ‘temporary’ file in the directory and then it will end up in the distribution when you forget to remove it. Similarly, version control files, such as a ‘CVS’ subdirectory, can easily end up in a distribution this way.

If a primary is not distributed by default, but in your case it ought to be, you can easily correct it with ‘EXTRA\_DIST’:

```
EXTRA_DIST = $(bin_SCRIPTS)
```

The next major Automake release<sup>2</sup> will have a better method for controlling whether primaries do or do not go into the distribution. In 1.5 you will be able to use the ‘dist’

---

<sup>2</sup> Probably numbered 1.5.

and ‘**nodist**’ prefixes to control distribution on a per-variable basis. You will even be able to simultaneously use both prefixes with a given primary to include some files and omit others:

```
dist_bin_SCRIPTS = distribute-this
nodist_bin_SCRIPTS = but-not-this
```

### 13.3 The **distcheck** rule

The **make dist** documentation sounds nice, and **make dist** did do something, but how do you know it really works? It is a terrible feeling when you realize your carefully crafted distribution is missing a file and won’t compile on a user’s machine.

I wouldn’t write such an introduction unless Automake provided a solution. The solution is a smoke test known as **make distcheck**. This rule performs a **make dist** as usual, but it doesn’t stop there. Instead, it then proceeds to untar the new archive into a fresh directory, build it in a fresh build directory separate from the source directory, install it into a third fresh directory, and finally run **make check** in the build tree. If any step fails, **distcheck** aborts, leaving you to fix the problem before it will create a distribution.

While not a complete test – it only tries one architecture, after all – **distcheck** nevertheless catches most packaging errors (as opposed to portability bugs), and its use is highly recommended.

### 13.4 Some caveats

Earlier, if you were awake, you noticed that I recommended the use of **make** before **make dist** or **make distcheck**. This practice ensures that all the generated files are newer than their inputs. It also solves some problems related to dependency tracking (see [Chapter 19 \[Advanced GNU Automake Usage\]](#), page 205).

Note that currently Automake will allow you to make a distribution when maintainer mode is off, or when you do not have all the required maintainer tools. That is, you can make a subtly broken distribution if you are motivated or unlucky. This will be addressed in a future version of Automake.

### 13.5 Implementation

In order to understand how to use the more advanced **dist**-related features, you must first understand how **make dist** is implemented. For most packages, what we’ve already covered will suffice. Few packages will need the more advanced features, though I note that many use them anyway.

The **dist** rules work by building a copy of the source tree and then archiving that copy. This copy is made in stages: a ‘**Makefile**’ in a particular directory updates the corresponding directory in the shadow tree. In some cases, **automake** is run to create a new ‘**Makefile.in**’ in the new distribution tree.

After each directory’s ‘**Makefile**’ has had a chance to update the distribution directory, the appropriate command is run to create the archive. Finally, the temporary directory is removed.

If your `'Makefile.am'` defines a `dist-hook` rule, then Automake will arrange to run this rule when the copying work for this directory is finished. This rule can do literally anything to the distribution directory, so some care is required – careless use will result in an unusable distribution. For instance, Automake will create the shadow tree using links, if possible. This means that it is inadvisable to modify the files in the `'dist'` tree in a dist hook. One common use for this rule is to remove files that erroneously end up in the distribution (in rare situations this can happen). The variable `'distdir'` is defined during the `dist` process and refers to the corresponding directory in the distribution tree; `'top_distdir'` refers to the root of the distribution tree.

Here is an example of removing a file from a distribution:

```
dist-hook:
    -rm $(distdir)/remove-this-file
```



## 14 Installing and Uninstalling Configured Packages

Have you ever seen a package where, once built, you were expected to keep the build tree around forever, and always `cd` there before running the tool? You might have to cast your mind way, way back to the bad old days of 1988 to remember such a horrible thing.

The GNU Autotools provides a canned solution to this problem. While not without flaws, it does provide a reasonable and easy-to-use framework. In this chapter we discuss how the GNU Autotools installation model, how to convince `automake` to install files where you want them, and finally we conclude with some information about uninstalling, including a brief discussion of its flaws.

### 14.1 Where files are installed

If you've ever run `configure --help`, you've probably been frightened by the huge number of options offered. Although nobody ever uses more than two or three of these, they are still important to understand when writing your package; their proper use will help you figure out where each file should be installed. For a background on these standard directories and their uses, refer to [Chapter 3 \[Invoking configure\]](#), page 17.

We do recommend using the standard directories as described. While most package builders only use `--prefix` or perhaps `--exec-prefix`, some packages (eg. GNU/Linux distributions) require more control. For instance, if your package `'quux'` puts a file into `sysconfigdir`, then in the default configuration it will end up in `'/usr/local/var'`. However, for a GNU/Linux distribution it would make more sense to configure with `'--sysconfigdir=/var/quux'`.

Automake makes it very easy to use the standard directories. Each directory, such as `'bindir'`, is mapped onto a `'Makefile'` variable of the same name. Automake adds three useful variables to the standard list:

`pkgincludedir`

This is a convenience variable whose value is `'$(includedir)/$(PACKAGE)'`.

`pkgdatadir`

A convenience variable whose value is `'$(datadir)/$(PACKAGE)'`.

`pkglibdir`

A variable whose value is `'$(libdir)/$(PACKAGE)'`.

These cannot be set on the `configure` command line but are always defined as above.<sup>1</sup>

In Automake, a directory variable's name, without the `'dir'` suffix, can be used as a prefix to a primary to indicate install location. Confused yet? An example will help: items listed in `'bin_PROGRAMS'` are installed in `'bindir'`.

Automake's rules are actually a bit more precise than this: the directory and the primary must agree. It doesn't make sense to install a library in `'datadir'`, so Automake won't let you. Here is a complete list showing primaries and the directories which can be used with them:

---

<sup>1</sup> There has been some debate in the Autoconf community about extending Autoconf to allow new directories to be set on the `configure` command line. Currently the consensus seems to be that there are too many arguments to `configure` already.

```

‘PROGRAMS’
    ‘bindir’, ‘sbindir’, ‘libexecdir’, ‘pkglibdir’.

‘LIBRARIES’
    ‘libdir’, ‘pkglibdir’.

‘LTLIBRARIES’
    ‘libdir’, ‘pkglibdir’.

‘SCRIPTS’  ‘bindir’, ‘sbindir’, ‘libexecdir’, ‘pkgdatadir’.

‘DATA’      ‘datadir’, ‘sysconfdir’, ‘sharedstatedir’, ‘localstatedir’, ‘pkgdatadir’.

‘HEADERS’   ‘includedir’, ‘oldincludedir’, ‘pkgincludedir’.

‘TEXINFOS’
    ‘infodir’.

‘MANS’      ‘man’, ‘man0’, ‘man1’, ‘man2’, ‘man3’, ‘man4’, ‘man5’, ‘man6’, ‘man7’, ‘man8’, ‘man9’,
            ‘mann’, ‘man1’.
```

There are two other useful prefixes which, while not directory names, can be used in their place. These prefixes are valid with any primary. The first of these is `‘noinst’`. This prefix tells Automake that the listed objects should not be installed, but should be built anyway. For instance, you can use `‘noinst_PROGRAMS’` to list programs which will not be installed.

The second such non-directory prefix is `‘check’`. This prefix tells Automake that this object should not be installed, and furthermore that it should only be built when the user runs `make check`.

Early in Automake history we discovered that even Automake’s extended built-in list of directories was not enough – basically anyone who had written a `‘Makefile.am’` sent in a bug report about this. Now Automake lets you extend the list of directories.

First you must define your own directory variable. This is a macro whose name ends in `‘dir’`. Define this variable however you like. We suggest that you define it relative to an autoconf directory variable; this gives the user some control over the value. Don’t hardcode it to something like `‘/etc’`; absolute hardcoded paths are rarely portable.

Now you can attach the base part of the new variable to a primary just as you can with the built-in directories:

```

foodir = $(datadir)/foo
foo_DATA = foo.txt
```

Automake lets you attach such a variable to any primary, so you can do things you ordinarily wouldn’t want to do or be allowed to do. For instance, Automake won’t diagnose this piece of code that tries to install a program in an architecture-independent location:

```

foodir = $(datadir)/foo
foo_PROGRAMS = foo
```

## 14.2 Fine-grained control of install

The second most common way<sup>2</sup> to configure a package is to set `prefix` and `exec-prefix` to different values. This way, a system administrator on a heterogeneous network can arrange to have the architecture-independent files shared by all platforms. Typically this doesn't save very much space, but it does make in-place bug fixing or platform-independent runtime configuration a lot easier.

To this end, Automake provides finer control to the user than a simple `make install`. For instance, the user can strip all the package executables at install time by running `make install-strip` (though we recommend setting the various 'INSTALL' environment variables instead; this is discussed later). More importantly, Automake provides a way to install the architecture-dependent and architecture-independent parts of a package independently.

In the above scenario, installing the architecture-independent files more than once is just a waste of time. Our hypothetical administrator can install those pieces exactly once, with `make install-data`, and then on each type of build machine install only the architecture-dependent files with `make install-exec`.

Nonstandard directories specified in 'Makefile.am' are also separated along 'data' and 'exec' lines, giving the user complete control over installation. If, and only if, the directory variable name contains the string 'exec', then items ending up in that directory will be installed by `install-exec` and not `install-data`.

At some sites, the paths referred to by software at runtime differ from those used to actually install the software. For instance, suppose '/usr/local' is mounted read-only throughout the network. On the server, where new packages are built, the file system is available read-write as '/w/usr/local' – a directory which is not mounted anywhere else. In this situation the sysadmin can configure and build using the *runtime* values, but use the 'DESTDIR' trick to temporarily change the paths at install time:

```
./configure --prefix=/usr/local
make
make DESTDIR=/w install
```

Note that 'DESTDIR' operates as a prefix only. Sometimes this isn't enough. In this situation you can explicitly override each directory variable:

```
./configure --prefix=/usr/local
make
make prefix=/w/usr/local datadir=/w/usr/share install
```

Here is a full example<sup>3</sup> showing how you can unpack, configure, and build a typical GNU program on multiple machines at the same time:

```
sunos$ tar zxf foo-0.1.tar.gz
sunos$ mkdir sunos linux
```

In one window:

```
sunos$ cd sunos
sunos$ ../foo-0.1/configure --prefix=/usr/local \
> --exec-prefix=/usr/local/sunos
```

<sup>2</sup> The most common way being to simply set `prefix`.

<sup>3</sup> This example assumes the use of GNU tar when extracting; this is standard on Linux but does not come with Solaris.

```
sunos$ make
sunos$ make install
```

And in another window:

```
sunos$ rsh linux
linux$ cd ~/linux
linux$ ../foo-0.1/configure --prefix=/usr/local \
> --exec-prefix=/usr/local/linux
linux$ make
linux$ make install-exec
```

In this example we install everything on the ‘sunos’ machine, but we only install the platform-dependent files on the ‘linux’ machine. We use a different `exec-prefix`, so for example GNU/Linux executables will end up in ‘/usr/local/linux/bin/’.

### 14.3 Install hooks

As with `dist`, the `install` process allows for generic targets which can be used when the existing `install` functionality is not enough. There are two types of targets which can be used: local rules and hooks.

A local rule is named either `install-exec-local` or `install-data-local`, and is run during the course of the normal `install` procedure. This rule can be used to install things in ways that Automake usually does not support.

For instance, in `libgcj` we generate a number of header files, one per Java class. We want to install them in ‘`pkgincludedir`’, but we want to preserve the hierarchical structure of the headers (e.g., we want ‘`java/lang/String.h`’ to be installed as ‘`$(pkgincludedir)/java/lang/String.h`’, not ‘`$(pkgincludedir)/String.h`’), and Automake does not currently support this. So we resort to a local rule, which is a bit more complicated than you might expect:

```
install-data-local:
    @for f in $(nat_headers) $(extra_headers); do \
    ## Compute the install directory at runtime.
        d="echo $$f | sed -e s,/[^/]*$$,,'"; \
    ## Make the install directory.
        $(mkinstalldirs) $(DESTDIR)$(includedir)/$$d; \
    ## Find the header file -- in our case it might be in srcdir or
    ## it might be in the build directory. "p" is the variable that
    ## names the actual file we will install.
        if test -f $(srcdir)/$$f; then p=$(srcdir)/$$f; else p=$$f; fi; \
    ## Actually install the file.
        $(INSTALL_DATA) $$p $(DESTDIR)$(includedir)/$$f; \
    done
```

A hook is guaranteed to run after the `install` of objects in this directory has completed. This can be used to modify files after they have been installed. There are two install hooks, named `install-data-hook` and `install-exec-hook`.

For instance, suppose you have written a program which must be `setuid root`. You can accomplish this by changing the permissions after the program has been installed:

```
bin_PROGRAMS = su
su_SOURCES = su.c

install-exec-hook:
    chown root $(bindir)/su
    chmod u+s $(bindir)/su
```

Unlike an install hook, and install rule is not guaranteed to be after all other install rules are run. This lets it be run in parallel with other install rules when a parallel `make` is used. Ordinarily this is not very important, and in practice you almost always see local hooks and not local rules.

The biggest caveat to using a local rule or an install hook is to make sure that it will work when the source and build directories are not the same—many people forget to do this. This means being sure to look in `$(srcdir)` when the file is a source file.

It is also very important to make sure that you do not use a local rule when install order is important – in this case, your `Makefile` will succeed on some machines and fail on others.

## 14.4 Uninstall

As if things aren't confusing enough, there is still one more major installation-related feature which we haven't mentioned: `uninstall`. Automake adds an `uninstall` target to your `Makefile` which does the reverse of `install`: it deletes the newly installed package.

Unlike `install`, there is no `uninstall-data` or `uninstall-exec`; while possible in theory we don't think this would be useful enough to actually use. Like `install`, you can write `uninstall-local` or `uninstall-hook` rules.

In our experience, `uninstall` is not a very useful feature. Automake implements it because it is mandated by the GNU Standards, but it doesn't work reliably across packages. Maintainers who write install hooks typically neglect to write uninstall hooks. Also, since it can't reliably uninstall a *previously* installed version of a package, it isn't useful for what most people would want to use it for anyway. We recommend using a real packaging system, several of which are freely available. In particular, GNU Stow, RPM, and the Debian packaging system seem like good choices.



## 15 Writing Portable C with GNU Autotools

GNU Autotools permits you to write highly portable programs. However, using GNU Autotools is not by itself enough to make your programs portable. You must also write them portably.

In this chapter we will give an introduction to writing portable programs in C. We will start with some notes on portable use of the C language itself. We will then discuss cross-Unix portability. We will finish with some notes on portability between Unix and Windows.

Portability is a big topic, and we can not cover everything in this chapter. The basic rule of portable code is to remember that every system is in some ways unique. Do not assume that every other system is like yours. It is very helpful to be familiar with relevant standards, such as the ISO C standard and the POSIX.1 standard. Finally, there is no substitute for experience; if you have the opportunity to build and test your program on different systems, do so.

### 15.1 C Language Portability

The C language makes it easy to write non-portable code. In this section we discuss these portability issues, and how to avoid them.

We concentrate on differences that can arise on systems in common use today. For example, all common systems today define `char` to be 8 bits, and define a pointer to hold the address of an 8-bit byte. We do not discuss the more exotic possibilities found on historical machines or on certain supercomputers. If your program needs to run in unusual settings, make sure you understand the characteristics of those systems; the system documentation should include a C portability guide describing the problems you are likely to encounter.

#### 15.1.1 ISO C

The ISO C standard first appeared in 1989 (the standard is often called ANSI C). It added several new features to the C language, most notably function prototypes. This led to many years of portability issues when deciding whether to use ISO C features.

We think that programs written today can assume the presence of an ISO C compiler. Therefore, we will not discuss issues related to the differences between ISO C compilers and older compilers—often called K&R compilers, from the first book on C by Kernighan and Ritchie. You may see these differences handled in older programs.

There is a newer C standard called ‘C9X’. Because compilers that support it are not widely available as of this writing, this discussion does not cover it.

#### 15.1.2 C Data Type Sizes

The C language defines data types in terms of a minimum size, rather than an exact size. As of this writing, this mainly matters for the types `int` and `long`. A variable of type `int` must be at least 16 bits, and is often 32 bits. A variable of type `long` must be at least 32 bits, and is sometimes 64 bits.

The range of a 16 bit number is -32768 to 32767 for a signed number, or 0 to 65535 for an unsigned number. If a variable may hold numbers larger than 16 bits, use `long` rather than `int`. Never assume that `int` or `long` have a specific size, or that they will overflow at a particular point. When appropriate, use variables of system defined types rather than `int` or `long`:

`size_t`      Use this to hold the size of an object, as returned by `sizeof`.

`ptrdiff_t`      Use this to hold the difference between two pointers into the same array.

`time_t`      Use this to hold a time value as returned by the `time` function.

`off_t`      On a Unix system, use this to hold a file position as returned by `lseek`.

`ssize_t`      Use this to hold the result of the Unix `read` or `write` functions.

Some books on C recommend using typedefs to specify types of particular sizes, and then adjusting those typedefs on specific systems. GNU Autotools supports this using the ‘`AC_CHECK_SIZEOF`’ macro. However, while we agree with using typedefs for clarity, we do not recommend using them purely for portability. It is safest to rely only on the minimum size assumptions made by the C language, rather than to assume that a type of a specific size will always be available. Also, most C compilers will define `int` to be the most efficient type for the system, so it is normally best to simply use `int` when possible.

### 15.1.3 C Endianness

When a number longer than a single byte is stored in memory, it must be stored in some particular format. Modern systems do this by storing the number byte by byte such that the bytes can simply be concatenated into the final number. However, the order of storage varies: some systems store the least significant byte at the lowest address in memory, while some store the most significant byte there. These are referred to as *little-endian* and *big-endian* systems, respectively.<sup>1</sup>

This difference means that portable code may not make any assumptions about the order of storage of a number. For example, code like this will act differently on different systems:

```
/* Example of non-portable code; don't do this */
int i = 4;
char c = *(char *) i;
```

Although that was a contrived example, real problems arise when writing numeric data in a file or across a network connection. If the file or network connection may be read on a different type of system, numeric data must be written in a format which can be unambiguously recovered. It is not portable to simply do something like

```
/* Example of non-portable code; don't do this */
write (fd, &i, sizeof i);
```

This example is non-portable both because of endianness and because it assumes that the size of the type of `i` are the same on both systems.

Instead, do something like this:

---

<sup>1</sup> These names come from *Gulliver's Travels*.



```

int j;
char buf[4];
for (j = 0; j < 4; ++j)
    buf[j] = (i >> (j * 8)) & 0xff;
write (fd, buf, 4); /* In real code, check the return value */

```

This unambiguously writes out a little endian 4 byte value. The code will work on any system, and the result can be read unambiguously on any system.

Another approach to handling endianness is to use the `htons` and `ntohs` functions available on most systems. These functions convert between *network endianness* and host endianness. Network endianness is big-endian; it has that name because the standard TCP/IP network protocols use big-endian ordering.

These functions come in two sizes: `htonl` and `ntohl` operate on 4-byte quantities, and `htons` and `ntohs` operate on 2-byte quantities. The `hton` functions convert host endianness to network endianness. The `ntoh` functions convert network endianness to host endianness. On big-endian systems, these functions simply return their arguments; on little-endian systems, they return their arguments after swapping the bytes.

Although these functions are used in a lot of existing code, they can be difficult to use in highly portable code, because they require knowing the exact size of your data types. If you know that the type `int` is exactly 4 bytes long, then it is possible to write code like the following:

```

int j;
j = htonl (i);
write (fd, &j, 4);

```

However, if `int` is not exactly 4 bytes long, this example will not work correctly on all systems.

### 15.1.4 C Structure Layout

C compilers on different systems lay out structures differently. In some cases there can even be layout differences between different C compilers on the same system. Compilers add gaps between fields, and these gaps have different sizes and are at different locations. You can normally assume that there are no gaps between fields of type `char` or array of `char`. However, you can not make any assumptions about gaps between fields of any larger type. You also can not make any assumptions about the layout of bitfield types.

These structure layout issues mean that it is difficult to portably use a C struct to define the format of data which may be read on another type of system, such as data in a file or sent over a network connection. Portable code must read and write such data field by field, rather than trying to read an entire struct at once.

Here is an example of non-portable code when reading data which may have been written to a file or a network connection on another type of system. Don't do this.

```

/* Example of non-portable code; don't do this */
struct {
    short i;
    int j;
} s;
read (fd, &s, sizeof s);

```

Instead, do something like this (the struct `s` is assumed to be the same as above):

```
unsigned char buf[6];
read (fd, buf, sizeof buf); /* Should check return value */
s.i = buf[0] | (buf[1] << 8);
s.j = buf[2] | (buf[3] << 8) | (buf[4] << 16) | (buf[5] << 24);
```

Naturally the code to write out the structure should be similar.

### 15.1.5 C Floating Point

Most modern systems handle floating point following the IEEE-695 standard. However, there are still portability issues.

Most processors use 64 bits of precision when computing floating point values. However, the widely used Intel x86 series of processors compute temporary values using 80 bits of precision, as do most instances of the Motorola 68k series. Some other processors, such as the PowerPC, provide fused multiply-add instructions which perform a multiplication and an addition using high precision for the intermediate value. Optimizing compilers will generate such instructions based on sequences of C operations.

For almost all programs, these differences do not matter. However, for programs which do intensive floating point operations, the differences can be significant. It is possible to write floating point loops which terminate on one sort of processor but not on another.

Unfortunately, there is no rule of thumb that can be used to avoid these problems. Most compilers provide an option to disable the use of extended precision (for GNU `cc`, the option is `-ffloat-store`). However, on the one hand, this merely shifts the portability problem elsewhere, and, on the other, the extended precision is often good rather than bad. Although these portability problems can not be easily avoided, you should at least be aware of them if you write programs which require very precise floating point operations.

The IEEE-695 standard specifies certain flags which the floating point processor should make available (e.g., overflow, underflow, inexact), and specifies that there should be some control over the floating point rounding mode. Most processors make these flags and controls available; however, there is no portable way to access them. A portable program should not assume that it will have this degree of control over floating point operations.

### 15.1.6 GNU `cc` Extensions

The GNU `cc` compiler has several useful extensions, which are documented in the GNU `cc` manual. A program which must be portable to other C compilers must naturally avoid these extensions; the `-pedantic` option may be used to warn about any accidental use of an extension.

However, the GNU `cc` compiler is itself highly portable, and it runs on all modern Unix platforms as well as on Windows. Depending upon your portability requirements, you may be able to simply assume that GNU `cc` is available, in which case your program may use extensions when they are useful. Note that some extensions are inherently non-portable, such as inline assembler code, or using attributes to specify a particular section for a function or a global variable.

## 15.2 Cross-Unix Portability

In the previous section, we discussed issues related to the C language. Here we will discuss the portability of C programs across different Unix implementations. All modern Unix systems conform to the POSIX.1 (1990 edition) and POSIX.2 (1992 edition) standards. They also all support the sockets interface for networking code. However, there are still significant differences between systems which can affect portability.

We will not discuss portability to older Unix systems which do not conform to the POSIX standards. If you need this sort of portability, you can often find some valuable hints in the set of macros defined by `autoconf`, and in the `'configure.in'` files of older programs which use `autoconf`.

### 15.2.1 Cross-Unix Function Calls

Functions not mentioned in POSIX.1 may not be available on all systems. If you want to use one of these functions, you should normally check for its presence by using `'AC_CHECK_FUNCS'` in your `'configure.in'` script, and adapt to its absence if possible. Here is a list of some popular functions which are available on many, but not all, modern Unix systems:

<code>alloca</code>	There are several portability issues with <code>alloca</code> . See the description of <code>AC_FUNC_ALLOCA</code> in the <code>autoconf</code> manual. Although this function can be very convenient, it is normally best to avoid it in highly portable code.
<code>dlopen</code>	GNU libtool provides a portable alternate interface to <code>dlopen</code> . See <a href="#">Chapter 17 [Dynamic Loading]</a> , page 177.
<code>getline</code>	In some cases <code>fgets</code> may be used as a fallback. In others, you will need to provide your own version of this function.
<code>getpagesize</code>	On some systems, the page size is available as the macro <code>PAGE_SIZE</code> in the header file <code>'sys/param.h'</code> . On others, the page size is available via the <code>sysconf</code> function. If none of those work, you must generally simply guess a value such as 4096.
<code>gettimeofday</code>	When this is not available, fall back to a less precise function such as <code>time</code> or <code>ftime</code> (which itself is not available on all systems).
<code>mmap</code>	In some cases you can use either <code>mmap</code> or ordinary file I/O. In others, a program which uses <code>mmap</code> will simply not be portable to all Unix systems. Note that <code>mmap</code> is an optional part of the 1996 version of POSIX.1, so it is likely to be added to all Unix systems over time.
<code>ptrace</code>	Unix systems without <code>ptrace</code> generally provide some other mechanism for debugging subprocesses, such as <code>'/proc'</code> . However, there is no widely portable method for controlling subprocesses, as evidenced by the source code to the GNU debugger, <code>gdb</code> .
<code>setuid</code>	Different Unix systems handle this differently. On some systems, any program can switch between the effective user ID of the executable and the real user ID.

On others, switching to the real user ID is final; some of those systems provide the `setreuid` function instead to switch the effective and real user ID. The effect when a program run by the superuser calls `setuid` varies among systems.

**snprintf** If this is not available, then in some cases it will be reasonable to simply use `sprintf`, and in others you will need to write a little routine to estimate the required length and allocate an appropriate buffer before calling `sprintf`.

`strcasecmp`

`strdup`

`strncasecmp`

You can normally provide your own version of these simple functions.

**valloc** When this is not available, just use `malloc` instead.

**vfork** When this is not available, just use `fork` instead.

### 15.2.2 Cross-Unix System Interfaces

There are several Unix system interfaces which have associated portability issues. We do not have the space here to discuss all of these in detail across all Unix systems. However, we mention them here to indicate issues where you may need to consider portability.

`'curses'`

`'termcap'`

`'terminfo'`

Many Unix systems provide the `'curses'` interface for simple graphical terminal access, but the name of the library varies. Typical names are `'-lcurses'` or `'-lncurses'`. Some Unix systems do not provide `'curses'`, but do provide the `'-ltermcap'` or `'-lterminfo'` library. The latter libraries only provide an interface to the `'termcap'` file or `'terminfo'` files. These files contain information about specific terminals, the difference being mainly the manner in which they are stored.

`'proc file system'`

The `'/proc'` file system is not available on all Unix systems, and when it is available the actual set of files and their format varies.

`'pseudo terminals'`

All Unix systems provide pseudo terminals, but the interface to obtain them varies widely. We recommend examining the configuration of an existing program which uses them, such as GNU emacs or Expect.

`'shared libraries'`

Shared libraries differ across Unix systems. The GNU libtool program was written to provide an interface to hide the differences. See [Chapter 10 \[Introducing GNU Libtool\]](#), page 81.

`'termios'`

`'termio'`

`'tty'`

The `'termios'` interface to terminals is standard on modern Unix systems. Avoid the older, non-portable, `'termio'` and `'tty'` interfaces (these interfaces are defined in `'termio.h'` and `'sgtty.h'`, respectively).

**‘threads’** Many, but not all, Unix systems support multiple threads in a single process, but the interfaces differ. One thread interface, `pthread`, was standardized in the 1996 edition of POSIX.1, so Unix systems are likely to converge on that interface over time.

**‘utmp’**

**‘wtmp’** Most Unix systems maintain the `‘utmp’` and `‘wtmp’` files to record information about which users are logged onto the system. However, the format of the information in the files varies across Unix systems, as does the exact location of the files and the functions which some systems provide to access the information. Programs which merely need to obtain login information will be more portable if they invoke a program such as `w`. Programs which need to update the login information must be prepared to handle a range of portability issues.

**‘X Window System’**

Version 11 of the X Window System is widely available across Unix systems. The actual release number varies somewhat, as does the set of available programs and window managers. Extensions such as OpenGL are not available on all systems.

## 15.3 Unix/Windows Portability

Unix and Windows are very different operating systems, with very different APIs and functionality. However, it is possible to write programs which run on both Unix and Windows, with significant extra work and some sacrifice in functionality. For more information on how GNU Autotools can help you write programs which run on both Unix and Windows, see [Chapter 25 \[Integration with Cygnus Cygwin\]](#), page 267.

### 15.3.1 Unix/Windows Emulation

The simplest way to write a program which runs on both Unix and Windows is to use an emulation layer. This generally results in a program which runs, but does not really feel like other programs for the operating system in question.

For example, the Cygwin package, which is freely available from Cygnus Solutions<sup>2</sup>, provides a Unix API which works on Windows. This permits Unix programs to be compiled to run on Windows. It is even possible to run an X server in the Cygwin environment, so graphical programs will work as well, although they will not have the Windows look and feel. The Cygwin package is discussed in more detail in see [Chapter 25 \[Integration with Cygnus Cygwin\]](#), page 267.

There are also commercial packages available to compile Unix programs for Windows (e.g., Interix) and to compile Windows programs on Unix (e.g., Bristol Technology).

The main disadvantage with using an emulation layer is that the resulting programs have the wrong look and feel. They do not behave as users expect, so they are awkward to use. This is generally not acceptable for high quality programs.

---

<sup>2</sup> <http://sourceware.cygnus.com/cygwin/>

### 15.3.2 Unix/Windows Portable Scripting Language

Another approach to Unix/Windows portability is to develop the program using a portable scripting language. An example of such a scripting language is Tcl/Tk<sup>3</sup>. Programs written in Tcl/Tk will work on both Unix and Windows (and on the Apple Macintosh operating system as well, for that matter). Graphical programs will more or less follow the look and feel for the platform upon which they are run. Since Tcl/Tk was originally developed on Unix, graphical Tcl/Tk programs will typically not look quite right to experienced Windows users, but they will be usable and of reasonable quality. Other portable scripting languages are Perl, Python, and Guile.

One disadvantage of this approach is that scripting languages tend to be less efficient than straight C code, but it is often possible to recode important routines in C. Another disadvantage is the need to learn a new language, one which furthermore may not be well designed for large programming projects.

### 15.3.3 Unix/Windows User Interface Library

Some programs' main interaction with the operating system is drawing on the screen. It is often possible to write such programs using a cross platform user interface library.

A cross-platform user interface library is a library providing basic windowing functions which has been implemented separately for Unix and Windows. The program calls generic routines which are translated into the appropriate calls on each platform. These libraries generally provide a good look and feel on each platform, so this can be a reasonable approach for programs which do not require additional services from the system.

The main disadvantage is the least common denominator effect: the libraries often only provide functionality which is available on both Unix and Windows. Features specific to either Unix or Windows may be very useful for the program, but they may not be available via the library.

### 15.3.4 Unix/Windows Specific Code

When writing a program which should run on both Unix and Windows, it is possible to simply write different code for the two platforms. This requires a careful separation of the operating system interface, including the graphical user interface, from the rest of the program. An API must be designed to provide the system needs, and that API must be implemented separately on Unix and Windows. The API should be set at an appropriate level to avoid the least common denominator effect.

This approach can be useful for a program which has significant platform independent computation as well as significant user interface or other system needs. It generally produces better results than the other approaches discussed above. The disadvantage is that this approach requires much more work than the others discussed above.

---

<sup>3</sup> <http://www.scriptics.com/>

### 15.3.5 Unix/Windows Issues

Whatever approach is used to support the program on both Unix and Windows, there are certain issues which may affect the design of the program, or many specific areas of the program.

#### 15.3.5.1 Text and Binary Files

Windows supports two different types of files: text files and binary files. On Unix, there is no such distinction. On Windows, any program which uses files must know whether each file is text or binary, and open and use them accordingly.

In a text file on Windows, each line is terminated with a carriage return character followed by a line feed character. When the file is read by a C program in text mode, the C library converts each carriage return/line feed pair into a single line feed character. If the file is read in binary mode, the program will see both the carriage return and the line feed.

You may have seen this distinction when transferring files between Unix and Window systems via FTP. You need to set the FTP program into binary or text mode as appropriate for the file you want to transfer.

When transferring a binary file, the FTP program simply transfers the data unchanged. When transferring a text file, the FTP program must convert each carriage return/line feed pair into a single line feed.

When using the C standard library, a binary file is indicated by adding **b** after the **r**, **w**, or **a** in the call to **fopen**. When reading a text file, the program can not simply count characters and use that when computing arguments to **fseek**.

#### 15.3.5.2 File system Issues

There are several differences between the file systems used on Unix and Windows, mainly in the areas of what names can be used for files. The program **doschk**, which can be found in the gcc distribution, may be used on Unix to check for filenames which are not permitted on DOS or Windows.

#### 15.3.5.3 DOS Filename Restrictions

The older DOS FAT file systems have severe limitations on file names. These limitations no longer apply to Windows, but they do apply to DOS based systems such as DJGPP.

A file name may consist of no more than 8 characters, followed by an optional extension of no more than 3 characters. This is commonly referred to as an 8.3 file name. Filenames are case insensitive.

There are a couple of filenames which are treated specially. You can not name a file **'aux'** or **'prn'**. In some cases, you can not even use an extension, such as **'aux.c'**. These restrictions apply to DOS and also to at least some versions of Windows.

#### 15.3.5.4 Windows File Name Case

Windows normally folds case when referring to files, unlike Unix. That is, on Windows, the file names **'file'**, **'File'**, and **'FiLe'** all refer to the same file. You must be aware of



this when porting Unix programs to Windows, as the Unix programs may expect that using different case is reflected in the file system.

For example, the procedure used to build the program `perl` from source relies on distinguishing between the files `PERL` and `perl`. This fails on Windows.

As a matter of interest, the Windows file system stores files under the name with which they were created. The DOS shell displays the names in all upper case. The `Explorer` shell displays them with each word in the file name capitalized.

#### 15.3.5.5 Whitespace in File Names

Both Unix and Windows file systems permit whitespace in file names. However, Unix users rarely take advantage of this, while Windows users often do. For example, many Windows systems use a directory named ‘`Program Files`’, whose name has an embedded space. This is a clash of conventions.

Many programs developed on Unix unintentionally assume that there will be no spaces in file and directory names, and behave mysteriously if any are encountered. On Unix these bugs will almost never be seen. On Windows, they will pop up immediately.

When writing a program which must run on Windows, consider these issues. Don’t forget to test it on directories and files with embedded spaces.

#### 15.3.5.6 Windows Separators and Drive Letters

On Unix, directories in a file name are separated by a forward slash (`/`). On Windows, directories are separated by a backward slash (`\`). For example, the Unix file ‘`dir/file`’ on Windows would be ‘`dir\file`’.<sup>4</sup>

On Unix, a list of directories is normally separated by a colon (`:`). On Windows, a list of directories is normally separated by a semicolon (`;`). For example, a simple Unix search path might look like this: ‘`/bin:/usr/bin`’. The same search path on Windows would probably look like this: ‘`c:\bin;c:\usr\bin`’.

On Unix, the file system is a single tree rooted at the directory simply named `/`. On Windows, there are multiple file system trees. Absolute file names often start with a drive letter followed by a colon. Windows maintains a default drive, and a default directory on each drive, which can make it difficult for a program to convert a relative file name into the absolute file name intended by the user. Windows permits referring to files on other systems by using a file name which starts with two slashes followed by a system name.

#### 15.3.5.7 Miscellaneous Issues

Windows shared libraries (DLLs) are different from typical Unix shared libraries. They require special declarations for global variables declared in a shared library. Programs which use shared libraries must generally use special macros in their header files to define these appropriately. GNU libtool can help with some shared library issues, but not all.

---

<sup>4</sup> Windows does permit a program to use a forward slash to separate directories when calling routines such as ‘`fopen`’. However, Windows users do not expect to type forward slashes when they enter file names, and they do not expect to see forward slashes when a file name is printed.



There are some Unix system features which are not supported under Windows: pseudo terminals, effective user ID, file modes with user/group/other permission, named FIFOs, an executable overriding functions called by shared libraries, `select` on anything other than sockets.

There are some Windows system features which are not supported under Unix: the Windows event loop, many graphical capabilities, some aspects of the rich set of interthread communication mechanisms, the `WSAAsyncSelect` function. You should keep these issues in mind when designing and writing a program which should run on both Unix and Windows.



## 16 Writing Portable C++ with GNU Autotools

My first task in industry was to port a large C++ application from one Unix platform to another. My colleagues immediately offered their sympathies and I remember my initial reaction—‘what’s the big deal?’. After all, this application used the C++ standard library, a modest subset of common Unix system calls and C++ was approaching ISO standardization. Little did I know what lay ahead—endless hurdles imposed by differences to C++ implementations in use on those platforms.

Being essentially a superset of the C programming language, C++ suffers from all of the machine-level portability issues described in [Chapter 15 \[Writing Portable C\]](#), [page 149](#). In addition to this, variability in the language and standard libraries present additional trouble when writing portable C++ programs.

There have been comprehensive guides written on C++ portability (see [Section 16.5 \[Further Reading\]](#), [page 174](#)). This chapter will attempt to draw attention to the less portable areas of the C++ language and describe how the GNU Autotools can help you overcome these (see [Section 16.4 \[How GNU Autotools Can Help\]](#), [page 173](#)). In many instances, the best approach to multi-platform C++ portability is to simply re-express your programs using more widely supported language constructs. Fortunately, this book has been written at a time when the C++ language standard has been ratified and C++ implementations are rapidly conforming. Gladly, as time goes on the necessity for this chapter will diminish.

### 16.1 Brief History of C++

C++ was developed in 1983 by Bjarne Stroustrup at AT&T. Stroustrup was seeking a new object-oriented language with which to write simulations. C++ has now become a mainstream systems programming language and is increasingly being used to implement free software packages. C++ underwent a lengthy standardization process and was ratified as an ISO standard in 1998.

The first specification of C++ was available in a book titled ‘The Annotated C++ Reference Manual’ by Stroustrup and Ellis, also known as the ‘ARM’. Since this initial specification, C++ has developed in some areas. These developments will be discussed in [Section 16.2 \[Changeable C++\]](#), [page 162](#).

The first C++ compiler, known as *cfront*, was produced by Stroustrup at AT&T. Because of its strong ties to C and because C is such a general purpose systems language, *cfront* consisted of a translator from C++ to C. After translation, an existing C compiler was used to compile the intermediate C code down to machine code for almost any machine you care to mention. C++ permits overloaded functions—that is, functions with the same name but different argument lists, so *cfront* implemented a *name mangling* algorithm (see [Section 16.3.2 \[Name Mangling\]](#), [page 171](#)) to give each function a unique name in the linker’s symbol table.

In 1989, the first true C++ compiler, G++, was written by Michael Tiemann of Cygnus Support. G++ mostly consisted of a new front-end to the GCC portable compiler, so G++ was able to produce code for most of the targets that GCC already supported.

In the years following, a number of new C++ compilers were produced. Unfortunately many were unable to keep pace with the development of the language being undertaken by

the standards committee. This divergence of implementations is the fundamental cause of non-portable C++ programs.

## 16.2 Changeable C++

The C++ standard encompasses the language and the interface to the standard library, including the Standard Template Library (see [Section 16.2.13 \[Standard Template Library\]](#), [page 170](#)). The language has evolved somewhat since the ARM was published; mostly driven by the experience of early C++ users.

In this section, the newer features of C++ will be briefly explained. Alternatives to these features, where available, will be presented when compiler support is lacking. The alternatives may be used if you need to make your code work with older C++ compilers or to avoid these features until the compilers you are concerned with are mature. If you are releasing a free software package to the wider community, you may need to specify a minimum level of standards conformance for the end-user's C++ compiler, or use the unappealing alternative of using lowest-common denominator C++ features.

In covering these, we'll address the following language features:

- Built-in `bool` type
- Exceptions
- Casts
- Variable scoping in `for` loops
- Namespaces
- The `explicit` keyword
- The `mutable` keyword
- The `typename` keyword
- Runtime Type Identification (RTTI)
- Templates
- Default template arguments
- Standard library headers
- Standard Template Library (STL)

### 16.2.1 Built-in `bool` type

C++ introduced a built-in boolean data type called `bool`. The presence of this new type makes it unnecessary to use an `int` with the values 0 and 1 and improves type safety. The two possible values of a `bool` are `true` and `false`—these are reserved words. The compiler knows how to coerce a `bool` into an `int` and vice-versa.

If your compiler does not have the `bool` type and `false` and `true` keywords, an alternative is to produce such a type using a `typedef` of an enumeration representing the two possible values:

```
enum boolvals { false, true };
typedef enum boolvals bool;
```

What makes this simple alternative attractive is that it prevents having to adjust the prolific amount of code that might use `bool` objects once your compiler supports the built-in type.

### 16.2.2 Exceptions

Exception handling is a language feature present in other modern programming languages. Ada and Java both have exception handling mechanisms. In essence, exception handling is a means of propagating a classified error by unwinding the procedure call stack until the error is caught by a higher procedure in the procedure call chain. A procedure indicates its willingness to handle a kind of error by *catching* it:

```
void foo ();

void
func ()
{
    try {
        foo ();
    }
    catch (...) {
        cerr << "foo failed!" << endl;
    }
}
```

Conversely, a procedure can throw an exception when something goes wrong:

```
typedef int io_error;

void
init ()
{
    int fd;
    fd = open ("/etc/passwd", O_RDONLY);
    if (fd < 0) {
        throw io_error(errno);
    }
}
```

C++ compilers tend to implement exception handling in full, or not at all. If any C++ compiler you may be concerned with does not implement exception handling, you may wish to take the lowest common denominator approach and eliminate such code from your project.

### 16.2.3 Casts

C++ introduced a collection of *named* casting operators to replace the conventional C-style cast of the form `(type) expr`. The new casting operators are `static_cast`, `reinterpret_cast`, `dynamic_cast` and `const_cast`. They are reserved words.

These refined casting operators are vastly preferred over conventional C casts for C++ programming. In fact, even Stroustrup recommends that the older style of C casts be banished from programming projects where at all possible *The C++ Programming Language, 3rd edition*. Reasons for preferring the new named casting operators include:

- They provide the programmer with a mechanism for more explicitly specifying the kind of type conversion. This assists the compiler in identifying incorrect conversions.

- They are easier to locate in source code, due to their unique syntax: `X_cast<type>(expr)`.

If your compiler does not support the new casting operators, you may have to continue to use C-style casts—and carefully! I have seen one project agree to use macros such as the one shown below to encourage those involved in the project to adopt the new operators. While the syntax does not match that of the genuine operators, these macros make it easy to later locate and alter the casts where they appear in source code.

```
#define static_cast(T,e) (T) e
```

### 16.2.4 Variable Scoping in For Loops

C++ has always permitted the declaration of a control variable in the initializer section of for loops:

```
for (int i = 0; i < 100; i++)
{
    ...
}
```

The original language specification allowed the control variable to remain live until the end of the scope of the loop itself:

```
for (int i = 0; i < j; i++)
{
    if (some condition)
        break;
}

if (i < j)
    // loop terminated early
```

In a later specification of the language, the control variable's scope only exists within the body of the for loop. The simple resolution to this incompatible change is to not use the older style. If a control variable needs to be used outside of the loop body, then the variable should be defined before the loop:

```
int i;

for (i = 0; i < j; i++)
{
    if (some condition)
        break;
}

if (i < j)
    // loop terminated early
```

### 16.2.5 Namespaces

C++ namespaces are a facility for expressing a relationship between a set of related declarations such as a set of constants. Namespaces also assist in constraining *names* so that they will not collide with other identical names in a program. Namespaces were

introduced to the language in 1993 and some early compilers were known to have incorrectly implemented namespaces. Here's a small example of namespace usage:

```
namespace Animals {
    class Bird {
    public:
        fly (); {} // fly, my fine feathered friend!
    };
};

// Instantiate a bird.
Animals::Bird b;
```

For compilers which do not correctly support namespaces it is possible to achieve a similar effect by placing related declarations into an enveloping structure. Note that this utilises the fact that C++ structure members have public protection by default:

```
struct Animals {
    class Bird {
    public:
        fly (); {} // fly, my find feathered friend!
    };
protected
    // Prohibit construction.
    Animals ();
};

// Instantiate a bird.
Animals::Bird b;
```

### 16.2.6 The explicit Keyword

C++ adopted a new **explicit** keyword to the language. This keyword is a qualifier used when declaring constructors. When a constructor is declared as **explicit**, the compiler will never call that constructor implicitly as part of a type conversion. This allows the compiler to perform stricter type checking and to prevent simple programming errors. If your compiler does not support the **explicit** keyword, you should avoid it and do without the benefits that it provides.

### 16.2.7 The mutable Keyword

C++ classes can be designed so that they behave correctly when **const** objects of those types are declared. Methods which do not alter internal object state can be qualified as **const**:

```
class String
{
public:
    String (const char* s);
    ~String ();

    size_t Length () const { return strlen (buffer); }
```

```
private:
    char* buffer;
};
```

This simple, though incomplete, class provides a `Length` method which guarantees, by virtue of its `const` qualifier, to never modify the object state. Thus, `const` objects of this class can be instantiated and the compiler will permit callers to use such objects' `Length` method.

The `mutable` keyword enables classes to be implemented where the concept of constant objects is sensible, but details of the implementation make it difficult to declare essential methods as `const`. A common application of the `mutable` keyword is to implement classes that perform caching of internal object data. A method may not modify the logical state of the object, but it may need to update a cache—an implementation detail. The data members used to implement the cache storage need to be declared as `mutable` in order for `const` methods to alter them.

Let's alter our rather farfetched `String` class so that it implements a primitive cache that avoids needing to call the `strlen` library function on each invocation of `Length`():

```
class String
{
public:
    String (const char* s) :length(-1) { /* copy string, etc. */ }
    ~String ();

    size_t Length () const
    {
        if (length < 0)
            length = strlen(buffer);
        return length;
    }

private:
    char* buffer;
    mutable size_t length;
}
```

When the `mutable` keyword is not available, your alternatives are to avoid implementing classes that need to alter internal data, like our caching string class, or to use the `const_cast` casting operator (see [Section 16.2.3 \[Casts\]](#), page 163) to cast away the 'constness' of the object.

### 16.2.8 The `typename` Keyword

The `typename` keyword was added to C++ after the initial specification and is not recognized by all compilers. It is a hint to the compiler that a name following the keyword is the name of a type. In the usual case, the compiler has sufficient context to know that a symbol is a defined type, as it must have been encountered earlier in the compilation:



```

class Foo
{
public:
    typedef int map_t;
};

void
func ()
{
    Foo::map_t m;
}

```

Here, `map_t` is a type defined in class `Foo`. However, if `func` happened to be a function template, the class which contains the `map_t` type may be a template parameter. In this case, the compiler simply needs to be guided by qualifying `T::map_t` as a *type name*:

```

class Foo
{
public:
    typedef int map_t;
};

template <typename T>
void func ()
{
    typename T::map_t t;
}

```

### 16.2.9 Runtime Type Identification (RTTI)

Run-time Type Identification, or RTTI, is a mechanism for interrogating the type of an object at runtime. Such a mechanism is useful for avoiding the dreaded *switch-on-type* technique used before RTTI was incorporated into the language. Until recently, some C++ compilers did not support RTTI, so it is necessary to assume that it may not be widely available.

Switch-on-type involves giving all classes a method that returns a special type token that an object can use to discover its own type. For example:

```

class Shape
{
public:
    enum types { TYPE_CIRCLE, TYPE_SQUARE };
    virtual enum types type () = 0;
};

class Circle: public Shape
{
public:
    enum types type () { return TYPE_CIRCLE; }
};

```

```

class Square: public Shape
{
public:
    enum types type () { return TYPE_SQUARE; }
};

```

Although switch-on-type is not elegant, RTTI isn't particularly object-oriented either. Given the limited number of times you ought to be using RTTI, the switch-on-type technique may be reasonable.

### 16.2.10 Templates

Templates—known in other languages as *generic types*—permit you to write C++ classes which represent parameterized data types. A common application for *class templates* is container classes. That is, classes which implement data structures that can contain data of any type. For instance, a well-implemented binary tree is not interested in the type of data in its nodes. Templates have undergone a number of changes since their initial inclusion in the ARM. They are a particularly troublesome C++ language element in that it is difficult to implement templates well in a C++ compiler.

Here is a fictitious and overly simplistic C++ class template that implements a fixed-sized stack. It provides a pair of methods for setting (and getting) the element at the bottom of the stack. It uses the modern C++ template syntax, including the new `typename` keyword (see [Section 16.2.8 \[The typename Keyword\]](#), page 166).

```

template <typename T> class Stack
{
public:
    T first () { return stack[9]; }
    void set_first (T t) { stack[9] = t; }

private:
    T stack[10];
};

```

C++ permits this class to be instantiated for any type you like, using calling code that looks something like this:

```

int
main ()
{
    Stack<int> s;
    s.set_first (7);
    cout << s.first () << endl;
    return 0;
}

```

An old trick for fashioning class templates is to use the C preprocessor. Here is our limited `Stack` class, rewritten to avoid C++ templates:

```

#define Stack(T) \
    class Stack_##T##__LINE__ \
    { \
    public: \
        T first () { return stack[0]; } \
        void set_first (T t) { stack[0] = t; } \
    \
    private: \
        T stack[10]; \
    }

```

There is a couple of subtleties being used here that should be highlighted. This generic class declaration uses the C preprocessor operator ‘##’ to generate a type name which is unique amongst stacks of any type. The `__LINE__` macro is defined by the preprocessor and is used here to maintain unique names when the template is instantiated multiple times. The trailing semicolon that must follow a class declaration has been omitted from the macro.

```

int
main ()
{
    Stack (int) s;
    s.set_first (7);
    cout << s.first () << endl;
    return 0;
}

```

The syntax for instantiating a `Stack` is slightly different to modern C++, but it does work relatively well, since the C++ compiler still applies type checking after the preprocessor has expanded the macro. The main problem is that unless you go to great lengths, the generated type name (such as `Stack__int`) could collide with other instances of the same type in the program.

### 16.2.11 Default template arguments

A later refinement to C++ templates was the concept of *default template arguments*. Templates allow C++ types to be *parameterized* and as such, the parameter is in essence a variable that the programmer must specify when instantiating the template. This refinement allows defaults to be specified for the template parameters.

This feature is used extensively throughout the Standard Template Library (see [Section 16.2.13 \[Standard Template Library\], page 170](#)) to relieve the programmer from having to specify a comparison function for sorted container classes. In most circumstances, the default less-than operator for the type in question is sufficient.

If your compiler does not support default template arguments, you may have to suffer without them and require that users of your class and function templates provide the default parameters themselves. Depending on how inconvenient this is, you might begrudgingly seek some assistance from the C preprocessor and define some preprocessor macros.

### 16.2.12 Standard library headers

Newer C++ implementations provide a new set of standard library header files. These are distinguished from older incompatible header files by their filenames—the new headers

omit the conventional `‘.h’` extension. Classes and other declarations in the new headers are placed in the `std` namespace. Detecting the kind of header files present on any given system is an ideal application of Autoconf. For instance, the header `‘<vector>’` declares the class `std::vector<T>`. However, if it is not available, `‘<vector.h>’` declares the class `vector<T>` in the global namespace.

### 16.2.13 Standard Template Library

The Standard Template Library (STL) is a library of containers, iterators and algorithms. I tend to think of the STL in terms of the container classes it provides, with algorithms and iterators necessary to make these containers useful. By segregating these roles, the STL becomes a powerful library—containers can store any kind of data and algorithms can use iterators to traverse the containers.

There are about half a dozen STL implementations. Since the STL relies so heavily on templates, these implementations tend to inline all of their method definitions. Thus, there are no precompiled STL libraries, and as an added bonus, you’re guaranteed to get the source code to your STL implementation. Hewlett-Packard and SGI produce freely redistributable STL implementations.

It is widely known that the STL can be implemented with complex C++ constructs and is a certain workout for any C++ compiler. The best policy for choosing an STL is to use a modern compiler such as GCC 2.95 or to use the STL that your vendor may have provided as part of their compiler.

Unfortunately, using the STL is pretty much an ‘all or nothing’ proposition. If it is not available on a particular system, there are no viable alternatives. There is a macro in the Autoconf macro archive (see [Section 23.5.1 \[Autoconf macro archive\]](#), page 258) that can test for a working STL.

## 16.3 Compiler Quirks

C++ compilers are complex pieces of software. Sadly, sometimes the details of a compiler’s implementations leak out and bother the application programmer. The two aspects of C++ compiler implementation that have caused grief in the past are efficient template instantiation and name mangling. Both of these aspects will be explained.

### 16.3.1 Template Instantiation

The problem with template instantiation exists because of a number of complex constraints:

- The compiler should only generate an instance of a template once, to speed the compilation process.
- The linker needs to be smart about where to locate the object code for instantiations produced by the compiler.

This problem is exacerbated by separate compilation—that is, the method bodies for `List<T>` may be located in a header file or in a separate compilation unit. These files may even be in a different directory than the current directory!

Life is easy for the compiler when the template definition appears in the same compilation unit as the site of the instantiation—everything that is needed is known:

```
template <class T> class List
{
private:
    T* head;
    T* current;
};

List<int> li;
```

This becomes significantly more difficult when the site of a template instantiation and the template definition is split between two different compilation units. In *Linkers and Loaders*, Levine describes in detail how the compiler driver deals with this by iteratively attempting to link a final executable and noting, from ‘undefined symbol’ errors produced by the linker, which template instantiations must be performed to successfully link the program.

In large projects where templates may be instantiated in multiple locations, the compiler may generate instantiations multiple times for the same type. Not only does this slow down compilation, but it can result in some difficult problems for linkers which refuse to link object files containing duplicate symbols. Suppose there is the following directory layout:

```
src
|
'--- core
|   '--- core.cxx
'--- modules
|   '--- http.cxx
'--- lib
|   '--- stack.h
```

If the compiler generates ‘core.o’ in the ‘core’ directory and ‘libhttp.a’ in the ‘http’ directory, the final link may fail because ‘libhttp.a’ and the final executable may contain duplicate symbols—those symbols generated as a result of both ‘http.cxx’ and ‘core.cxx’ instantiating, say, a `Stack<int>`. Linkers, such as that provided with AIX will allow duplicate symbols during a link, but many will not.

Some compilers have solved this problem by maintaining a template repository of template instantiations. Usually, the entire template definition is expanded with the specified type parameters and compiled into the repository, leaving the linker to collect the required object files at link time.

The main concerns about non-portability with repositories center around getting your compiler to do the right thing about maintaining a single repository across your entire project. This often requires a vendor-specific command line option to the compiler, which can detract from portability. It is conceivable that Libtool could come to the rescue here in the future.

### 16.3.2 Name Mangling

Early C++ compilers mangled the names of C++ symbols so that existing linkers could be used without modification. The cfront C++ translator also mangled names so that

information from the original C++ program would not be lost in the translation to C. Today, name mangling remains important for enabling overloaded function names and link-time type checking. Here is an example C++ source file which illustrates name mangling in action:

```
class Foo
{
public:
    Foo ();

    void go ();
    void go (int where);

private:
    int pos;
};

Foo::Foo ()
{
    pos = 0;
}

void
Foo::go ()
{
    go (0);
}

void
Foo::go (int where)
{
    pos = where;
}

int
main ()
{
    Foo f;
    f.go (10);
}

$ g++ -Wall example.cxx -o example.o

$ nm --defined-only example.o
00000000 T __3Foo
00000000 ? __FRAME_BEGIN__
00000000 t gcc2_compiled.
0000000c T go__3Foo
0000002c T go__3Fooi
00000038 T main
```

Even though `Foo` contains two methods with the same name, their argument lists (one taking an `int`, one taking no arguments) help to differentiate them once their names are mangled. The `'go__3Fooi'` is the version which takes an `int` argument. The `'__3Foo'`

symbol is the constructor for `Foo`. The GNU binutils package includes a utility called `c++filt` that can demangle names. Other proprietary tools sometimes include a similar utility, although with a bit of imagination, you can often demangle names in your head.

```
$ nm --defined-only example.o | c++filt
00000000 T Foo::Foo(void)
00000000 ? __FRAME_BEGIN__
00000000 t gcc2_compiled.
0000000c T Foo::go(void)
0000002c T Foo::go(int)
00000038 T main
```

Name mangling algorithms differ between C++ implementations so that object files assembled by one tool chain may not be linked by another if there are legitimate reasons to prohibit linking. This is a deliberate move, as other aspects of the object file may make them incompatible—such as the calling convention used for making function calls.

This implies that C++ libraries and packages cannot be practically distributed in binary form. Of course, you were intending to distribute the source code to your package anyway, weren't you?

## 16.4 How GNU Autotools Can Help

Each of the GNU Autotools contribute to C++ portability. Now that you are familiar with the issues, the following subsections will outline precisely how each tool contributes to achieving C++ portability.

### 16.4.1 Testing C++ Implementations with Autoconf

Of the GNU Autotools, perhaps the most valuable contribution to the portability of your C++ programs will come from Autoconf. All of the portability issues raised in [Section 16.2 \[Changeable C++\]](#), [page 162](#) can be detected using Autoconf macros.

Luc Maisonobe has written a large suite of macros for this purpose and they can be found in the Autoconf macro archive (see [Section 23.5.1 \[Autoconf macro archive\]](#), [page 258](#)). If any of these macros become important enough, they may become incorporated into the core Autoconf release. These macros perform their tests by compiling small fragments of C++ code to ensure that the compiler accepts them. As a side effect, these macros typically use `AC_DEFINE` to define preprocessor macros of the form `HAVE_feature`, which may then be exploited through conditional compilation.

### 16.4.2 Automake C++ support

Automake provides support for compiling C++ programs. In fact, it makes it practically trivial: files listed in a `SOURCES` primary may include `.c++`, `.cc`, `.cpp`, `.cxx` or `.C` extensions and Automake will know to use the C++ compiler to build them.

For a project containing C++ source code, it is necessary to invoke the `AC_PROG_CXX` macro in `configure.in` so that Automake knows how to run the most suitable compiler. Fortunately, when little details like this happen to escape you, `automake` will produce a warning:

```
$ automake
automake: Makefile.am: C++ source seen but CXX not defined in
automake: Makefile.am: 'configure.in'
```

### 16.4.3 Libtool C++ support

At the moment, Libtool is the weak link in the chain when it comes to working with C++. It is very easy to naively build a shared library from C++ source using `libtool`:

```
$ libtool -mode=link g++ -o libfoo.la -rpath /usr/local/lib foo.c++
```

This works admirably for trivial examples, but with real code, there are several things that can go wrong:

- On many architectures, for a variety of reasons, `libtool` needs to perform object linking using `ld`. Unfortunately, the C++ compiler often links in standard libraries at this stage, and using `ld` causes them to be dropped.

This can be worked around (at the expense of portability) by explicitly adding these missing libraries to the link line in your `'Makefile'`. You could even write an Autoconf macro to probe the host machine to discover likely candidates.

- The C++ compiler likes to instantiate static constructors in the library objects, which C++ programmers often rely on. Linking with `ld` will cause this to fail.

The only reliable way to work around this currently is to not write C++ that relies on static constructors in libraries. You might be lucky enough to be able to link with `LD=$CXX` in your environment with some projects, but it would be prone to stop working as your project develops.

- Libtool's inter-library dependency analysis can fail when it can't find the special run-time library dependencies added to a shared library by the C++ compiler at link time.

The best way around this problem is to explicitly add these dependencies to `libtool`'s link line:

```
$ libtool -mode=link g++ -o libfoo.la -rpath /usr/local/lib foo.cxx \
-lstdc++ -lg++
```

Now that C++ compilers on Unix are beginning to see widespread acceptance and are converging on the ISO standard, it is becoming unacceptable for Libtool to impose such limits. There is work afoot to provide generalized multi-language and multi-compiler support into Libtool—currently slated to arrive in Libtool 1.5. Much of the work for supporting C++ is already finished at the time of writing, pending beta testing and packaging<sup>1</sup>.

## 16.5 Further Reading

A number of books have been published which are devoted to the topic of C++ portability. Unfortunately, the problem with printed publications that discuss the state of C++ is that they date quickly. These publications may also fail to cover inadequacies of your particular compiler, since portability know-how is something that can only be acquired by collective experience.

---

<sup>1</sup> Visit the Libtool home page at <http://www.gnu.org/software/libtool> for breaking news.



Instead, online guides such as the Mozilla C++ Portability Guide<sup>2</sup> tend to be a more useful resource. An online guide such as this can accumulate the knowledge of a wider developer community and can be readily updated as new facts are discovered. Interestingly, the Mozilla guide is aggressive in its recommendations for achieving true C++ portability: item 3, for instance, states ‘Don’t use exceptions’. While you may not choose to follow each recommendation, there is certainly a lot of useful experience captured in this document.

---

<sup>2</sup> <http://www.mozilla.org/hacking/portable-cpp.html>



## 17 Dynamic Loading

An increasingly popular way of adding functionality to a project is to give a program the ability to dynamically load plugins, or modules. By doing this your users can extend your project in new ways, which even you perhaps hadn't envisioned. *Dynamic Loading*, then, is the process of loading compiled objects into a running program and executing some or all of the code from the loaded objects in the same context as the main executable.

This chapter begins with a discussion of the mechanics of dynamic modules and how they are used, and ends with example code for very simple module loading on GNU/Linux, along with the example code for a complementary dynamically loadable module. Once you have read this chapter and understand the principles of dynamic loading, the next chapter will explain how to use GNU Autotools to write portable dynamic module loading code and address some of the shortcomings of native dynamic loading APIs.

### 17.1 Dynamic Modules

In order to dynamically load some code into your executable, that code must be compiled in some special but architecture dependent fashion. Depending on the compiler you use and the platform you are compiling for, there are different conventions you must observe in the code for the module, and for the particular combination of compiler options you need to select if the resulting objects are to be suitable for use in a dynamic module. For the rest of this chapter I will concentrate on the conventions used when compiling dynamic modules with GCC on GNU/Linux, which although peculiar to this particular combination of compiler and host architecture, are typical of the sorts of conventions you would need to observe on other architectures or with a different compiler.

With GCC on GNU/Linux, you must compile each of the source files with `'-fPIC'`<sup>1</sup>, the resulting objects must be linked into a loadable module with gcc's `'-shared'` option:

```
$ gcc -fPIC -c foo.c
$ gcc -fPIC -c bar.c
$ gcc -shared -o baz.so foo.o bar.o
```

This is pretty similar to how you might go about linking a shared library, except that the `'baz.so'` module will never be linked with a `'-lbaz'` option, so the `'lib'` prefix isn't necessary. In fact, it would probably be confusing if you used the prefix. Similarly, there is no constraint to use any particular filename suffix, but it is sensible to use the target's native shared library suffix (GNU/Linux uses `'.so'`) to make it obvious that the compiled file is some sort of shared object, and not a normal executable.

Apart from that, the only difference between a shared library built for linking at compile-time and a dynamic module built for loading at run-time is that the module must provide known *entry points* for the main executable to call. That is, when writing code destined for a dynamic module, you must provide functions or variables with known names and semantics that the main executable can use to access the functionality of the module. This is different to the function and variable names in a regular library, which are already known when you write the client code, since the libraries are always written *before* the code that

---

<sup>1</sup> Not essential but will be slower without this option, see [Section 10.2.1 \[Position Independent Code\]](#), page 84.

uses them; a runtime module loading system must, by definition, be able to cope with modules that are written *after* the code that uses those modules.

## 17.2 Module Access Functions

In order to access the functionality of dynamic modules, different architectures provide various APIs to bring the code from the module into the address space of the loading program, and to access the symbols exported by that module.

GNU/Linux uses the dynamic module API introduced by Sun's Solaris operating system, and widely adopted (and adapted!) by the majority of modern Unices<sup>2</sup>. The interface consists of four functions. In practice, you really ought not to use these functions, since you would be locking your project into this single API, and the class of machines that supports it. This description is over-simplified to serve as a comparison with the fully portable `libltdl` API described in [Chapter 18 \[Using GNU libltdl\]](#), page 185. The minutiae are not discussed, because therein lie the implementation peculiarities that spoil the portability of this API. As they stand, these descriptions give a good overview of how the functions work at a high level, and are broadly applicable to the various implementations in use. If you are curious, the details of your machines particular dynamic loading API will be available in its system manual pages.

**void \* `dlopen` (const char \**filename*, int *flag*)** Function

This function brings the code from a named module into the address space of the running program that calls it, and returns a handle which is used by the other API functions. If *filename* is not an absolute path, GNU/Linux will search for it in directories named in the 'LD\_LIBRARY\_PATH' environment variable, and then in the standard library directories before giving up.

The flag argument is made by 'OR'ing together various flag bits defined in the system headers. On GNU/Linux, these flags are defined in '`dlfcn.h`':

'RTLD\_LAZY'

Resolve undefined symbols when they are first used.

'RTLD\_NOW'

If all symbols cannot be resolved when the module is loaded, `dlopen` will fail and return 'NULL'.

'RTLD\_GLOBAL'

All of the global symbols in the loaded module will be available to resolve undefined symbols in subsequently loaded modules.

**void \* `dlsym` (void \**handle*, char \**name*)** Function

Returns the address of the named symbol in the module which returned *handle* when it was `dlopened`. You must cast the returned address to a known type before using it.

---

<sup>2</sup> HP-UX being the most notable exception.

**int dlclose (void \*handle)** Function  
 When you are finished with a particular module, it can be removed from memory using this function.

**const char \* dlerror (void)** Function  
 If any of the other three API calls fails, this function returns a string which describes the last error that occurred.

In order to use these functions on GNU/Linux, you must `#include <dlfcn.h>` for the function prototypes, and link with `‘-ldl’` to provide the API implementation. Other Unices use `‘-ldld’` or provide the implementation of the API inside the standard C library.

### 17.3 Finding a Module

When you are writing a program that will load dynamic modules, a major stumbling block is writing the code to find the modules you wish to load. If you are worried about portability (which you must be, or you wouldn’t be reading this book!), you can’t rely on the default search algorithm of the vendor `dlopen` function, since it varies from implementation to implementation. You can’t even rely on the name of the module, since the module suffix will vary according to the conventions of the target host (though you could insist on a particular suffix for modules you are willing to load).

Unfortunately, this means that you will need to implement your own searching algorithm and always use an absolute pathname when you call `dlopen`. A widely adopted mechanism is to look for each module in directories listed in an environment variable specific to your application, allowing your users to inform the application of the location of any modules they have written. If a suitable module is not yet found, the application would then default to looking in a list of standard locations – say, in a subdirectory of the user’s home directory, and finally a subdirectory of the application installation tree. For application `‘foo’`, you might use `‘/usr/lib/foo/module.so’` – that is, `‘$(pkglibdir)/module.so’` if you are using Automake.

This algorithm can be further improved:

- If you try different module suffixes to the named module for every directory in the search path, which will avoid locking your code into a subset of machines that use the otherwise hardcoded module suffix. With this in place you could ask the module loader for module `‘foomodule’`, and if it was not found in the first search directory, the module loader could try `‘foomodule.so’`, `‘foomodule.sl’` and `‘foomodule.dll’` before moving on to the next directory.
- You might also provide command line options to your application which will preload modules before starting the program proper or to modify the module search path. For example, GNU M4, version 1.5, will have the following dynamic loading options:

```
$ m4 --help
Usage: m4 [OPTION]... [FILE]...
...
Dynamic loading features:
  -M, --module-directory=DIRECTORY  add DIRECTORY to the search path
  -m, --load-module=MODULE          load dynamic MODULE from M4MODPATH
```

...  
Report bugs to <bug-m4@gnu.org>.

## 17.4 A Simple GNU/Linux Module Loader

Something to be aware of, is that when your users write dynamic modules for your application, they are subject to the interface you design. It is very important to design a dynamic module interface that is clean and functional before other people start to write modules for your code. If you ever need to change the interface, your users will need to rewrite their modules. Of course you can carefully change the interface to retain backwards compatibility to save your users the trouble of rewriting their modules, but that is no substitute for designing a good interface from the outset. If you do get it wrong, and subsequently discover that the design you implemented is misconceived (this is the voice of experience speaking!), you will be left with a difficult choice: try to tweak the broken API so that it does work while retaining backwards compatibility, and the maintenance and performance penalty that brings? Or start again with a fresh design born of the experience gained last time, and rewrite all of the modules you have so far?

If there are other applications which have similar module requirements to you, it is worth writing a loader that uses the same interface and semantics. That way, you will (hopefully) be building from a known good API design, and you will have access to all the modules for that other application too, and vice versa.

For the sake of clarity, I have sidestepped any issues of API design for the following example, by choosing this minimal interface:

<b>int run (const char *argument)</b>	Function
When the module is successfully loaded a function with the following prototype is called with the argument given on the command line. If this entry point is found and called, but returns '-1', an error message is displayed by the calling program.	

Here's a simplistic but complete dynamic module loading application you can build for this interface with the GNU/Linux dynamic loading API:

```
#include <stdio.h>
#include <stdlib.h>
#ifdef EXIT_FAILURE
# define EXIT_FAILURE      1
# define EXIT_SUCCESS      0
#endif

#include <limits.h>
#ifdef PATH_MAX
# define PATH_MAX 255
#endif

#include <dlfcn.h>
/* This is missing from very old Linux libc. */
#ifdef RTLD_NOW
# define RTLD_NOW 2
```

```

#endif

typedef int entrypoint (const char *argument);

/* Save and return a copy of the dlerror() error message,
   since the next API call may overwrite the original. */
static char *dlerrordup (char *errmsg);

int
main (int argc, const char *argv[])
{
    const char modulepath[1+ PATH_MAX];
    const char *errmsg = NULL;
    void *module = NULL;
    entrypoint *run = NULL;
    int errors = 0;

    if (argc != 3)
    {
        fprintf (stderr, "USAGE: main MODULENAME ARGUMENT\n");
        exit (EXIT_FAILURE);
    }

    /* Set the module search path. */
    getcwd (modulepath, PATH_MAX);
    strcat (modulepath, "/");
    strcat (modulepath, argv[1]);

    /* Load the module. */
    module = dlopen (modulepath, RTLD_NOW);
    if (!module)
    {
        strcat (modulepath, ".so");
        module = dlopen (modulepath, RTLD_NOW);
    }
    if (!module)
        errors = 1;

    /* Find the entry point. */
    if (!errors)
    {
        run = dlsym (module, "run");
        /* In principle, run might legitimately be NULL, so
           I don't use run == NULL as an error indicator. */
        errmsg = dlerrordup (errmsg);

        if (errmsg != NULL)
            errors = dlclose (module);
    }
}

```

```

/* Call the entry point function. */
if (!errors)
{
    int result = (*run) (argv[2]);
    if (result < 0)
        errormsg = strdup ("module entry point execution failed");
    else
        printf ("\t=> %d\n", result);
}

/* Unload the module, now that we are done with it. */
if (!errors)
    errors = dlclose (module);

if (errors)
{
    /* Diagnose the encountered error. */
    errormsg = dlerrordup (errormsg);

    if (!errormsg)
    {
        fprintf (stderr, "%s: dlerror() failed.\n", argv[0]);
        return EXIT_FAILURE;
    }
}

if (errormsg)
{
    fprintf (stderr, "%s: %s.\n", argv[0], errormsg);
    free (errormsg);
    return EXIT_FAILURE;
}

return EXIT_SUCCESS;
}

/* Be careful to save a copy of the error message,
   since the next API call may overwrite the original. */
static char *
dlerrordup (char *errormsg)
{
    char *error = (char *) dlerror ();
    if (error && !errormsg)
        errormsg = strdup (error);
    return errormsg;
}

```

You would compile this on a GNU/Linux machine like so:



```
$ gcc -o simple-loader simple-loader.c -ldl
```

However, despite making reasonable effort with this loader, and ignoring features which could easily be added, it still has some seemingly insoluble problems:

1. It will fail if the user's platform doesn't have the `dlopen` API. This also includes platforms which have no shared libraries.
2. It relies on the implementation to provide a working self-opening mechanism. '`dlopen (NULL, RTLD_NOW)`' is very often unimplemented, or buggy, and without that, it is impossible to access the symbols of the main program through the '`dlsym`' mechanism.
3. It is quite difficult to figure out at compile time whether the target host needs '`libdl.so`' to be linked.

I will use GNU Autotools to tackle these problems in the next chapter.

## 17.5 A Simple GNU/Linux Dynamic Module

As an appetiser for working with dynamic loadable modules, here is a minimal module written for the interface used by the loader in the previous section:

```
#include <stdio.h>

int
run (const char *argument)
{
    printf ("Hello, %s!\n", argument);
    return 0;
}
```

Again, to compile on a GNU/Linux machine:

```
$ gcc -fPIC -c simple-module.c
$ gcc -shared -o simple-module.so
```

Having compiled both loader and module, a test run looks like this:

```
$ ./simple-loader simple-module World
Hello, World!
=> 0
```

If you have a GNU/Linux system, you should experiment with the simple examples from this chapter to get a feel for the relationship between a dynamic module loader and its modules – tweak the interface a little; try writing another simple module. If you have a machine with a different dynamic loading API, try porting these examples to that machine to get a feel for the kinds of problems you would encounter if you wanted a module system that would work with both APIs.

The next chapter will do just that, and develop these examples into a fully portable module loading system with the aid of GNU Autotools. In [Section 20.1 \[A Module Loading Subsystem\]](#), [page 209](#), I will add a more realistic module loader into the Sic project last discussed in [Chapter 12 \[A Large GNU Autotools Project\]](#), [page 123](#).



## 18 Using GNU libltdl

Now that you are conversant with the mechanics and advantages of using dynamic run time modules in your projects, you can probably already imagine a hundred and one uses for a plugin architecture. As I described in the last chapter, there are several gratuitously different architecture dependent dynamic loading APIs, and yet several more shortcomings in many of those.

If you have Libtool installed on your machine, then you almost certainly have libltdl which has shipped as part of the standard Libtool distribution since release 1.3. In this chapter I will describe GNU *libltdl*, the **LibTool Dynamic Loading library**, and explain some of its features and how to make use of them.

### 18.1 Introducing libltdl

Probably the best known and supported Unix run time linking API is the ‘dlopen’ interface, used by Solaris and GNU/Linux amongst others, and discussed earlier in [Chapter 17 \[Dynamic Loading\]](#), [page 177](#). libltdl is based on the ‘dlopen’ API, with a few small differences and several enhancements.

The following libltdl API functions are declared in ‘ltdl.h’:

- |  |          |
|--|----------|
| <b>lt_dlhandle</b> <b>lt_dlopen</b> (const char * <i>filename</i> )  | Function |
| This function brings the code from a named module into the address space of the running program that calls it, and returns a handle which is used by the other API functions. If <i>filename</i> is not an absolute path, libltdl will search for it in directories named in the ‘LTDL_LIBRARY_PATH’ environment variable, and then in the standard library directories before giving up. It is safe to call this function many times, libltdl will keep track of the number of calls made, but will require the same number of calls to ‘lt_dlclose’ to actually unload the module. |          |
| <b>lt_ptr_t</b> <b>lt_dlsym</b> (lt_dlhandle <i>handle</i> , const char * <i>name</i> )  | Function |
| Returns the address of the named symbol in the module which returned <i>handle</i> when it was lt_dlopened. You must cast the returned address to a known type before using it.  |          |
| <b>int</b> <b>lt_dlclose</b> (lt_dlhandle <i>handle</i> )  | Function |
| When you are finished with a particular module, it can be removed from memory using this function.   |          |
| <b>const char *</b> <b>lt_dLError</b> (void)   | Function |
| If any of the libltdl API calls fail, this function returns a string which describes the last error that occurred.   |          |

In order to use these functions, you must `#include <ltdl.h>` for the function prototypes, and link with ‘-lltdl’ to provide the API implementation. Assuming you link your application with libtool, and that you call the necessary macros from your ‘configure.in’

(see [Section 18.2 \[Using libltdl\]](#), page 187), then any host specific dependent libraries (for example, ‘libdl’ on GNU/Linux) will automatically be added to the final link line by libtool.

You don’t limit yourself to using only Libtool compiled modules when you use libltdl. By writing the module loader carefully, it will be able to load native modules too—although you will not be able to preload non-Libtool modules (see [Section 18.4 \[dlpreopen Loading\]](#), page 198. The loader in [Section 18.2.3 \[libltdl Module Loader\]](#), page 190 is written in this way. It is useful to be able to load modules flexibly like this, because you don’t tie your users into using Libtool for any modules they write.

Compare the descriptions of the functions above with the API described in [Section 17.2 \[Module Access Functions\]](#), page 178. You will notice that they are very similar.

Back-linking is the process of resolving any remaining symbols by referencing back into the application that loads the library at runtime – a mechanism implemented on almost all modern Unices.

For instance, your main application may provide some utility function, ‘my\_function’, which you want a module to have access to. There are two ways to do that:

- You could use Libtool to link your application, using the ‘-export-dynamic’ option to ensure that the global application symbols are available to modules. When libltdl loads a module into an application compiled like this, it will *back-link* symbols from the application to resolve any otherwise undefined symbols in a module. When the module is ‘ltdlopen’ed, libltdl will arrange for calls to ‘my\_function’ in the module, to execute the ‘my\_function’ implementation in the application. If you have need of this functionality, relying on back-linking is the simplest way to achieve it. Unfortunately, this simplicity is at the expense of portability: some platforms have no support for back-linking at all, and others will not allow a module to be created with unresolved symbols. Never-the-less, libltdl allows you to do this if you want to.
- You could split the code that implements the symbols you need to share with modules into a separate library. This library would then be used to resolve the symbols you wish to share, by linking it into modules and application alike. The definition of ‘my\_function’ would be compiled separately into a library, ‘libmy\_function.la’. References to ‘my\_function’ from the application would be resolved by linking it with ‘libmy\_function.la’, and the library would be installed so that modules which need to call ‘my\_function’ would be able to resolve the symbol by linking with ‘-lmy\_function’.

This method requires support for neither back-linking nor unresolved link time symbols from the host platform. The disadvantage is that when you realise you need this functionality, it may be quite complicated to extract the shared functionality from the application to be compiled in a stand alone library.

On those platforms which support *back-linking*, libltdl can be configured to resolve external symbol references in a dynamic module with any global symbols already present in the main application. This has two implications for the libltdl API:

- There is no need to pass ‘RTLD\_GLOBAL’ (or equivalent) to `lt_dlopen` as might be necessary with the native module loading API.

- You should be aware that your application will not work on some platforms—most notably, Windows and AIX—if you rely on a back-linking.

Similarly, there is no need to specify whether the module should be integrated into the application core before `lt_dlopen` returns, or else when the symbols it provides are first referenced. libltdl will use *lazy loading* if it is supported, since this is a slight performance enhancement, or else fall back to loading everything immediately. Between this feature and the support of back-linking, there is no need to pass flags into `lt_dlopen` as there is with most native `dlopen` APIs.

There are a couple of other important API functions which you will need when using libltdl:

**int lt\_dlinit (void)** Function

You must call this function to initialise libltdl before calling any of the other libltdl API functions. It is safe to call this function many times, libltdl will keep track of the number of calls made, but will require the same number of calls to `lt_dlexit` to actually recycle the library resources. If you don't call `lt_dlinit` before any other API call, the other calls, including `lt_dLError`, will return their respective failure codes (`NULL` or `'1'`, as appropriate).

**int lt\_dlexit (void)** Function

When you are done with libltdl and all dynamic modules have been unloaded you can call this function to finalise the library, and recycle its resources. If you forget to unload any modules, the call to `lt_dlexit` will `lt_dlclose` them for you.

Another useful departure that the libltdl API makes from a vanilla `dlopen` implementation is that it also will work correctly with old K&R C compilers, by virtue of not relying on `'void *'` pointers. libltdl uses `lt_dlhandles` to pass references to loaded modules, and this also improves ANSI C compiler's type checking compared to the untyped addresses typically used by native `dlopen` APIs.

## 18.2 Using libltdl

Various aspects of libltdl are addressed in the following subsections, starting with a step by step guide to adding libltdl to your own GNU Autotools projects (see [Section 18.2.1 \[libltdl Configury\]](#), page 188) and an explanation of how to initialise libltdl's memory management (see [Section 18.2.2 \[libltdl Memory Management\]](#), page 190). After this comes a simple libltdl module loader which you can use as the basis for a module loader in your own projects (see [Section 18.2.3 \[libltdl Module Loader\]](#), page 190), including an explanation of how libltdl finds and links any native dynamic module library necessary for the host platform. The next subsection (see [Section 18.2.4 \[libltdl Dependent Libraries\]](#), page 194) deals with the similar problem of dynamic modules which depend on other libraries – take care not to confuse the problems discussed in the previous two subsections. Following that, the source code for and use of a simple dynamic module for use with this section's module loader is detailed (see [Section 18.2.5 \[libltdl Dynamic Module\]](#), page 195).

## 18.2.1 Configury

Because libltdl supports so many different platforms<sup>1</sup> it needs to be configured for the host platform before it can be used.

The path of least resistance to successfully integrating libltdl into your own project, dictates that the project use Libtool for linking its module loader with libltdl. This is certainly the method I use and recommend, and is the method discussed in this chapter. However, I have seen projects which did not use Libtool (specifically because Libtool's poor C++ support made it difficult to adopt), but which wanted the advantages of libltdl. It is possible to use libltdl entirely without Libtool, provided you take care to use the configuration macros described here, and use the results of those running these macros to determine how to link your application with libltdl.

The easiest way to add libltdl support to your own projects is with the following simple steps:

1. You must add the libltdl sources to your project distribution. If you are not already using Libtool in some capacity for your project, you should add 'AC\_PROG\_LIBTOOL'<sup>2</sup> to your 'configure.in'. That done, move to the top level directory of the project, and execute:

```
$ libtoolize --ltdl
$ ls -F
aclocal.m4      configure.in    libltdl/
$ ls libltdl/
COPYING.LIB  README          aclocal.m4      configure.in    stamp-h.in
Makefile.am  acconfig.h      config.h.in     ltdl.c
Makefile.in  acinclude.m4    configure       ltdl.h
```

2. libltdl has its own configuration to run in addition to the configuration for your project, so you must be careful to call the subdirectory configuration from your top level 'configure.in':

```
AC_CONFIG_SUBDIRS(libltdl)
```

And you must ensure that Automake knows that it must descend into the libltdl source directory at make time, by adding the name of that subdirectory to the 'SUBDIRS' macro in your top level 'Makefile.am':

```
SUBDIRS = libltdl src
```

3. You must also arrange for the code of libltdl to be linked into your application. There are two ways to do this: as a regular Libtool library; or as a convenience library (see [Section 10.2.4 \[Creating Convenience Libraries with libtool\], page 87](#)). Either way there are catches to be aware of, which will be addressed in a future release. Until libltdl is present on the average user's machine, I recommend building a convenience library. You can do that in 'configure.in':

```
AC_LIBLTDL_CONVENIENCE
AC_PROG_LIBTOOL
```

<sup>1</sup> As I always like to say, 'from BeOS to Windows!'. And yes, I do think that it is a better catchphrase than 'from AIX to Xenix'!

<sup>2</sup> Use 'AM\_PROG\_LIBTOOL' if you have automake version 1.4 or older or a version of libtool earlier than 1.4.

The main thing to be aware of when you follow these steps, is that you can only have one copy of the code from libltdl in any application. Once you link the objects into a library, that library will not work with any other library which has also linked with libltdl, or any application which has its own copy of the objects. If you were to try, the libltdl symbol names would clash.

The alternative is to substitute ‘AC\_LIBLTDL\_CONVENIENCE’ with ‘AC\_LIBLTDL\_INSTALLABLE’. Unfortunately there are currently many potential problems with this approach. This macro will try to find an already installed libltdl and use that, or else the embedded libltdl will be built as a standard shared library, which must be installed along with any libraries or applications that use it. There is no testing for version compatibility, so it is possible that two or more applications that use this method will overwrite one another’s copies of the installed libraries and headers. Also, the code which searches for the already installed version of libltdl tends not to find the library on many hosts, due to the native libraries it depends on being difficult to predict.

Both of the ‘AC\_LIBLTDL\_...’ macros set the values of ‘INCLTDL’ and ‘LIBLTDL’ so that they can be used to add the correct include and library flags to the compiler in your Makefiles. They are not substituted by default. If you need to use them you must also add the following macros to your ‘configure.in’:

```
AC_SUBST(INCLTDL)
AC_SUBST(LIBLTDL)
```

4. Many of the libltdl supported hosts require that a separate shared library be linked into any application that uses dynamic runtime loading. libltdl is wrapped around this native implementation on these hosts, so it is important to link that library too. Adding support for module loading through the wrapped native implementation is independent of Libtool’s determination of how shared objects are compiled. On GNU/Linux, you would need to link your program with libltdl and ‘libdl’, for example.

Libtool installs a macro, ‘AC\_LIBTOOL\_DLOPEN’, which adds tests to your ‘configure’ that will search for this native library. Whenever you use libltdl you should add this macro to your ‘configure.in’ before ‘AC\_PROG\_LIBTOOL’:

```
AC_LIBTOOL_DLOPEN
AC_LIBLTDL_CONVENIENCE
AC_PROG_LIBTOOL
...
AC_SUBST(INCLTDL)
AC_SUBST(LIBLTDL)
```

‘AC\_LIBTOOL\_DLOPEN’ takes care to substitute a suitable value of ‘LIBADD\_DL’ into your ‘Makefile.am’, so that your code will compile correctly wherever the implementation library is discovered:

```
INCLUDES      += @INCLTDL@

bin_PROGRAMS  = your_app
your_app_SOURCES = main.c support.c
your_app_LDADD  = @LIBLTDL@ @LIBADD_DL@
```

Libtool 1.4 has much improved inter-library dependency tracking code which no longer requires ‘@LIBADD\_DL@’ be explicitly referenced in your ‘Makefile.am’. When you install

libltdl, Libtool 1.4 (or better) will make a note of any native library that libltdl depends on – linking it automatically, provided that you link ‘libltdl.la’ with libtool. You might want to omit the ‘@LIBADD\_DL@’ from your ‘Makefile.am’ in this case, if seeing the native library twice (once as a dependee of libltdl, and again as an expansion of ‘@LIBADD\_DL@’) on the link line bothers you.

Beyond this basic configury setup, you will also want to write some code to form a module loading subsystem for your project, and of course some modules! That process is described in [Section 18.2.3 \[libltdl Module Loader\]](#), page 190 and [Section 18.2.5 \[libltdl Dynamic Module\]](#), page 195 respectively.

## 18.2.2 Memory Management

Internally, libltdl maintains a list of loaded modules and symbols on the heap. If you find that you want to use it with a project that has an unusual memory management API, or if you simply want to use a debugging ‘malloc’, libltdl provides hook functions for you to set the memory routines it should call.

The way to use these hooks is to point them at the memory allocation routines you want libltdl to use before calling any of its API functions:

```
lt_dlmalloc = (lt_ptr_t (*) PARAMS((size_t))) mymalloc;
lt_dlfree   = (void (*) PARAMS((lt_ptr_t))) myfree;
```

Notice that the function names need to be cast to the correct type before assigning them to the hook symbols. You need to do this because the prototypes of the functions you want libltdl to use will vary slightly from libltdl's own function pointer types— libltdl uses `lt_ptr_t` for compatibility with K&R compilers, for example.

## 18.2.3 Module Loader

This section contains a fairly minimal libltdl based dynamic module loader that you can use as a base for your own code. It implements the same API as the simple module loader in [Section 17.4 \[A Simple GNU/Linux Module Loader\]](#), page 180, and because of the way libltdl is written is able to load modules written for that loader, too. The only part of this code which is arguably more complex than the equivalent from the previous example loader, is that `lt_dlinit` and `lt_dlexit` must be called in the appropriate places. In contrast, The module search path initialisation is much simplified thanks to another relative improvement in the libltdl API:

**int lt\_dlsetsearchpath (const char \*path)** Function  
 This function takes a colon separated list of directories, which will be the first directories libltdl will search when trying to locate a dynamic module.

Another new API function is used to actually load the module:

**lt\_dlhandle lt\_dlopenext (const char \*filename)** Function  
 This function is used in precisely the same way as `lt_dlopen`. However, if the search for the named module by exact match against *filename* fails, it will try again with a ‘.la’ extension, and then the native shared library extension (‘.sl’ on HP-UX, for example).



The advantage of using `lt_dlopenext` to load dynamic modules is that it will work equally well when loading modules not compiled with Libtool. Also, by passing the module name parameter with no extension, this function allows module coders to manage without Libtool.

```
#include <stdio.h>
#include <stdlib.h>
#ifndef EXIT_FAILURE
# define EXIT_FAILURE      1
# define EXIT_SUCCESS      0
#endif

#include <limits.h>
#ifndef PATH_MAX
# define PATH_MAX 255
#endif

#include <string.h>
#include <ltdl.h>

#ifndef MODULE_PATH_ENV
# define MODULE_PATH_ENV    "MODULE_PATH"
#endif

typedef int entrypoint (const char *argument);

/* Save and return a copy of the dlerror() error message,
   since the next API call may overwrite the original. */
static char *dlerrordup (char *errmsg);

int
main (int argc, const char *argv[])
{
    char *errmsg = NULL;
    lt_dlhandle module = NULL;
    entrypoint *run = NULL;
    int errors = 0;

    if (argc != 3)
    {
        fprintf (stderr, "USAGE: main MODULENAME ARGUMENT\n");
        exit (EXIT_FAILURE);
    }

    /* Initialise libltdl. */
    errors = lt_dlinit ();

    /* Set the module search path. */
    if (!errors)
    {
```

```

    const char *path = getenv (MODULE_PATH_ENV);

    if (path != NULL)
        errors = lt_dlsetsearchpath (path);
}

/* Load the module. */
if (!errors)
    module = lt_dlopenext (argv[1]);

/* Find the entry point. */
if (module)
{
    run = (entrypoint *) lt_dlsym (module, "run");

    /* In principle, run might legitimately be NULL, so
       I don't use run == NULL as an error indicator
       in general. */
    errormsg = dlerror (errormsg);
    if (errormsg != NULL)
    {
        errors = lt_dlclose (module);
        module = NULL;
    }
}
else
    errors = 1;

/* Call the entry point function. */
if (!errors)
{
    int result = (*run) (argv[2]);
    if (result < 0)
        errormsg = strdup ("module entry point execution failed");
    else
        printf ("\t=> %d\n", result);
}

/* Unload the module, now that we are done with it. */
if (!errors)
    errors = lt_dlclose (module);

if (errors)
{
    /* Diagnose the encountered error. */
    errormsg = dlerror (errormsg);

    if (!errormsg)
    {

```

```

        fprintf (stderr, "%s: dlerror() failed.\n", argv[0]);
        return EXIT_FAILURE;
    }
}

/* Finished with ltdl now. */
if (!errors)
    if (lt_dlexit () != 0)
        errormsg = dlerrordup (errormsg);

if (errormsg)
{
    fprintf (stderr, "%s: %s.\n", argv[0], errormsg);
    free (errormsg);
    exit (EXIT_FAILURE);
}

return EXIT_SUCCESS;
}

/* Be careful to save a copy of the error message,
   since the next API call may overwrite the original. */
static char *
dlerrordup (char *errormsg)
{
    char *error = (char *) lt_dlerror ();
    if (error && !errormsg)
        errormsg = strdup (error);
    return errormsg;
}

```

This file must be compiled with `libtool`, so that the dependent libraries (`'libdl.so'` on my GNU/Linux machine) are handled correctly, and so that the `dlpreopen` support is compiled in correctly (see [Section 18.4 \[dlpreopen Loading\]](#), page 198):

```

$ libtool --mode=link gcc -g -o ltdl-loader -dlopen self \
-rpath /tmp/lib ltdl-loader.c -lltdl
gcc -g -o ltdl-loader -Wl,--rpath,/tmp/lib ltdl-loader.c -lltdl -ldl

```

By using *both* of `lt_dlopenext` and `lt_dlsetsearchpath`, this module loader will make a valiant attempt at loading anything you pass to it – including the module I wrote for the simple GNU/Linux module loader earlier (see [Section 17.5 \[A Simple GNU/Linux Dynamic Module\]](#), page 183). Here, you can see the new `ltdl-loader` loading and using the `'simple-module'` module from [Section 17.5 \[A Simple GNU/Linux Dynamic Module\]](#), page 183:

```

$ ltdl-loader simple-module World
Hello, World!
=> 0

```

### 18.2.4 Dependent Libraries

On modern Unices<sup>3</sup>, the shared library architecture is smart enough to encode all of the other libraries that a dynamic module depends on as part of the format of the file which is that module. On these architectures, when you `lt_dlopen` a module, if any shared libraries it depends on are not already loaded into the main application, the system runtime loader will ensure that they too are loaded so that all of the module's symbols are satisfied.

Less well endowed systems<sup>4</sup>, cannot do this by themselves. Since Libtool release 1.4, `libltdl` uses the record of inter-library dependencies in the libtool pseudo-library (see [Chapter 10 \[Introducing GNU Libtool\], page 81](#)) to manually load dependent libraries as part of the `lt_dlopen` call.

An example of the sort of difficulties that can arise from trying to load a module that has a complex library dependency chain is typified by a problem I encountered with GNU Guile a few years ago: Earlier releases of the libXt Athena widget wrapper library for GNU Guile failed to load on my a.out based GNU/Linux system. When I tried to load the module into a running Guile interpreter, it couldn't resolve any of the symbols that referred to libXt. I soon discovered that the libraries that the module depended upon were not loaded by virtue of loading the module itself. I needed to build the interpreter itself with libXt and rely on back-linking to resolve the 'Xt' references when I loaded the module. This pretty much defeated the whole point of having the wrapper library as a module. Had Libtool been around in those days, it would have been able to load libXt as part of the process of loading the module.

If you program with the X window system, you will know that the list of libraries you need to link into your applications soon grows to be very large. Worse, if you want to load an X extension module into a non-X aware application, you will encounter the problems I found with Guile, unless you link your module with `libtool` and dynamically load it with `libltdl`. At the moment, the various X Window libraries are not built with libtool, so you must be sure to list all of the dependencies when you link a module. By doing this, Libtool can use the list to check that all of the libraries required by a module are loaded correctly as part of the call to `lt_dlopen`, like this:

```
$ libtool --mode=link gcc -o module.so -module -avoid-version \
source.c -L/usr/X11R6/lib -lXt -lX11
...
$ file .libs/module.so
.libs/module.so: ELF 32-bit LSB shared object, Intel 80386,
version 1, not stripped
$ ldd .libs/module.so
        libX11.so.6 => /usr/X11R6/lib/libX11.so.6 (0x4012f00)
        libXt.so.6 => /usr/X11R6/lib/libXt.so.6 (0x4014500)
```

Or, if you are using Automake:

```
...
lib_LTLIBRARIES = module.la
module_la_SOURCES = source.c
module_la_LDFLAGS = -module -avoid-version -L$(X11LIBDIR)
```

<sup>3</sup> Architectures which use ELF and ECOFF binary format for example.

<sup>4</sup> Those which use a.out binary format, for example.

```
module_la_LIBADD = -lXt -lX11
...
```

It is especially important to be aware of this if you develop on a modern platform which correctly handles these dependencies natively (as in the example above), since the code may still work on your machine even if you don't correctly note all of the dependencies. It will only break if someone tries to use it on a machine that needs Libtool's help for it to work, thus reducing the portability of your project.

### 18.2.5 Dynamic Module

Writing a module for use with the libltdl based dynamic module loader is no more involved than before: It must provide the correct entry points, as expected by the simple API I designed – the 'run' entry point described in [Section 17.4 \[A Simple GNU/Linux Module Loader\]](#), [page 180](#). Here is such a module, 'ltdl-module.c':

```
#include <stdio.h>
#include <math.h>

#define run ltdl_module_LTX_run

int
run (const char *argument)
{
    char *end = NULL;
    long number;

    if (!argument || *argument == '\0')
    {
        fprintf (stderr, "error: invalid argument, \"%s\".\n",
                 argument ? argument : "(null)");
        return -1;
    }

    number = strtol (argument, &end, 0);
    if (end && *end != '\0')
    {
        fprintf (stderr, "warning: trailing garbage \"%s\".\n",
                 end);
    }

    printf ("Square root of %s is %f\n", argument, sqrt (number));

    return 0;
}
```

To take full advantage of the new module loader, the module itself **must** be compiled with Libtool. Otherwise dependent libraries will not have been stored when libltdl tries to load the module on an architecture that doesn't load them natively, or which doesn't have shared libraries at all (see [Section 18.4 \[dlpreopen Loading\]](#), [page 198](#)).

```
$ libtool --mode=compile gcc -c ltdl-module.c
rm -f .libs/ltdl-module.lo
gcc -c ltdl-module.c -fPIC -DPIC -o .libs/ltdl-module.lo
gcc -c ltdl-module.c -o ltdl-module.o >/dev/null 2>&1
mv -f .libs/ltdl-module.lo ltdl-module.lo
$ libtool --mode=link gcc -g -o ltdl-module.la -rpath 'pwd' \
-no-undefined -module -avoid-version ltdl-module.lo -lm
rm -fr .libs/ltdl-module.la .libs/ltdl-module.* .libs/ltdl-module.*
gcc -shared ltdl-module.lo -lm -lc -Wl,-soname \
-Wl,ltdl-module.so -o .libs/ltdl-module.so
ar cru .libs/ltdl-module.a ltdl-module.o
creating ltdl-module.la
(cd .libs && rm -f ltdl-module.la && ln -s ../ltdl-module.la \
ltdl-module.la)
```

You can see from the interaction below that ‘ltdl-loader’ does not load the math library, ‘libm’, and that the shared part of the Libtool module, ‘ltdl-module’, does have a reference to it. The pseudo-library also has a note of the ‘libm’ dependency so that libltdl will be able to load it even on architectures that can’t do it natively:

```
$ libtool --mode=execute ldd ltdl-loader
libltdl.so.0 => /usr/lib/libltdl.so.0 (0x4001a000)
libdl.so.2 => /lib/libdl.so.2 (0x4001f000)
libc.so.6 => /lib/libc.so.6 (0x40023000)
/lib/ld-linux.so.2 => /lib/ld-linux.so.2 (0x40000000)
$ ldd .libs/ltdl-module.so
libm.so.6 => /lib/libm.so.6 (0x40008000)
libc.so.6 => /lib/libc.so.6 (0x40025000)
/lib/ld-linux.so.2 => /lib/ld-linux.so.2 (0x80000000)
$ fgrep depend ltdl-module.la
# Libraries that this one depends upon.
dependency_libs=' -lm'
```

This module is now ready to load from ‘ltdl-loader’:

```
$ ltdl-loader ltdl-module 9
Square root of 9 is 3.000000
=> 0
```

## 18.3 Portable Library Design

When partitioning the functionality of your project into libraries, and particularly loadable modules, it is easy to inadvertently rely on modern shared library features such as *back-linking* or *dependent library loading*. If you do accidentally use any of these features, you probably won’t find out about it until someone first tries to use your project on an older or less featureful host.

I have already used the ‘-module’ and ‘-avoid-version’ libtool linking options when compiling the libltdl module in the last section, the others are useful to know also. All of these are used with the ‘link’ mode of libtool (‘libtool --mode=link’):

**‘-module’** This option tells `libtool` that the target is a dynamically loadable module (as opposed to a conventional shared library) and as such need not have the ‘`lib`’ prefix.

**‘-avoid-version’**

When linking a dynamic module, this option can be used instead of the ‘`-version-info`’ option, so that the module is not subject to the usual shared library version number suffixes.


**‘-no-undefined’**

This is an extremely important option when you are aiming for maximum portability. It declares that all of the symbols required by the target are resolved at link time. Some shared library architectures do not allow undefined symbols by default (Tru64 Unix), and others do not allow them at all (AIX). By using this switch, and ensuring that all symbols really are resolved at link time, your libraries will work on even these platforms. See [Section 11.2.1 \[Creating Libtool Libraries with Automake\]](#), page 108.

**‘-export-dynamic’**

Almost the opposite of ‘`-no-undefined`’, this option will compile the target so that the symbols it exports can be used to satisfy unresolved symbols in subsequently loaded modules. Not all shared library architectures support this feature, and many that do support it, do so by default regardless of whether this option is supplied. If you rely on this feature, then you should use this option, in the knowledge that your project will not work correctly on architectures that have no support for the feature. For maximum portability, you should neither rely on this feature nor use the ‘`-export-dynamic`’ option – but, on the occasions you do need the feature, this option is necessary to ensure that the linker is called correctly.

When you have the option to do so, I recommend that you design your project so that each of the libraries and modules is self contained, except for minimal number of dependent libraries, arranged in a directional graph shaped like a tree. That is, by relying on back-linking, or mutual or cyclic dependencies you reduce the portability of your project. In the diagrams below, an arrow indicates that the compilation object relies on symbols from the objects that it points to:



## 18.4 dlopen Loading

On machines which do not have any facility for shared libraries or dynamic modules, libltdl allows an application to `lt_dlopen` modules, provided that the modules are known at link time. This works by linking the code for the modules into the application in advance, and then looking up the addresses of the already loaded symbols when `lt_dlsym` is called. We call this mechanism *dlopen opening* – so named because the modules must be loaded at link time, not because the API to use modules loaded in this way is any different.

This feature is extremely useful for debugging, allowing you to make a fully statically linked application from the executable and module objects, without changing any source code to work around the module loading calls. As far as the code outside the libltdl API can tell, these modules really are being loaded dynamically. Driving a symbolic debugger across module boundaries is however much easier when blocks of code aren't moving in and out of memory during execution.

You may have wondered about the purpose of the following line in the dynamic module code in [Section 18.2.4 \[libltdl Dependent Libraries\]](#), page 194:

```
#define run ltdl_module_LTX_run
```

The reason for redefining the entry point symbol in this way is to prevent a symbol clash when two or more modules that provide identically named entry point functions are preloaded into an executable. It would be otherwise impossible to preload both `'simple-module.c'` and `'ltdl-module.c'`, for example, since each defines the symbol `'run'`. To allow us to write dynamic modules that are potentially preloaded, `lt_dlsym` will first try to lookup the address of a named symbol with a prefix consisting of the canonicalized name of the module being searched, followed by the characters `'_LTX_'`. The module name part of this prefix is canonicalized by replacing all non-alphanumeric characters with an underscore. If that fails, `lt_dlsym` resorts to the unadorned symbol name, which is how `'run'` was found in `'simple-module.la'` by `'ltdl-loader'` earlier.

Supporting this feature in your module loading code is a simple matter of initialising the address lookup table, and `'ltdl.h'` defines a convenient macro to do exactly that:

### LTDL\_SET\_PRELOADED\_SYMBOLS ()

Macro

Add this macro to the code of your module loading code, before the first call to a libltdl function, to ensure that the dlopen address lookup table is populated.

Now change the contents of `'ltdl-loader.c'`, and add a call to this macro, so that it looks like this:

```
/* Initialise preloaded symbol lookup table. */
LTDL_SET_PRELOADED_SYMBOLS();

/* Initialise libltdl. */
errors = lt_dlinit ();
```

Libtool will now be able to fall back to using preloaded static modules if you tell it to, or if the host platform doesn't support native dynamic loading.

If you use `'LTDL_SET_PRELOADED_SYMBOLS'` in your module loader, you **must** also specify something to preload to avoid compilation failure due to undefined `'lt_preloaded_symbols'`. You can name modules on the Libtool link command



line using one of ‘-dlopen’ or ‘-dlpreopen’. This includes support for accessing the symbols of the main executable opened with ‘lt\_dlopen(NULL)’—you can ask Libtool to fall back to preopening the main modules like this:

```
$ libtool gcc -g -o ltdl-loader -dlopen self -rpath /tmp/lib \
ltdl-loader.c -lltdl
rm -f .libs/ltdl-loader.nm .libs/ltdl-loader.nmS \
.libs/ltdl-loader.nmT
creating .libs/ltdl-loaderS.c
(cd .libs && gcc -c -fno-builtin -fno-rtti -fno-exceptions
"ltdl-loaderS.c")
rm -f .libs/ltdl-loaderS.c .libs/ltdl-loader.nm .libs/ltdl-loader.nmS
.libs/ltdl-loader.nmT
gcc -o ltdl-loader .libs/ltdl-loaderS.o ltdl-loader.c
-Wl,--export-dynamic /usr/lib/libltdl.so -ldl -Wl,--rpath -Wl,/tmp/lib
rm -f .libs/ltdl-loaderS.o
```

It doesn’t make sense to add preloaded module support to a project, when you have no modules to preopen, so the compilation failure in that case is actually a feature of sorts.

The ‘LTDL\_SET\_PRELOADED\_SYMBOLS’ macro does not interfere with the normal operation of the code when modules are dynamically loaded, provided you use the ‘-dlopen’ option on the link line. The advantage of referencing the macro by default is that you can recompile the application with or without preloaded module, and all without editing the sources.

If you have no modules to link in by default, you can force Libtool to populate the preload symbol table by using the ‘-dlopen force’ option. This is the option used to preload the symbols of the main executable so that you can subsequently call ‘lt\_dlopen(NULL)’.

Multiple modules can be preloaded, although at the time of writing only Libtool compiled modules can be used. If there is a demand, Libtool will be extended to include native library preloading in a future revision.

To illustrate, I have recompiled the ‘simple-module.c’ module with libtool:

```
$ libtool --mode=compile gcc -c simple-module.c
rm -f .libs/simple-module.lo
gcc -c simple-module.c -fPIC -DPIC -o .libs/simple-module.lo
gcc -c simple-module.c -o simple-module.o >/dev/null 2>&1
mv -f .libs/simple-module.lo simple-module.lo
$ libtool --mode=link gcc -g -o simple-module.la -rpath 'pwd'
-no-undefined -module -avoid-version simple-module.lo
rm -fr .libs/simple-module.la .libs/simple-module.*
.libs/simple-module.*
gcc -shared simple-module.lo -lc -Wl,-soname \
-Wl,simple-module.so -o .libs/simple-module.so
ar cru .libs/simple-module.a simple-module.o
creating simple-module.la
(cd .libs && rm -f simple-module.la && ln -s ../simple-module.la \
simple-module.la)
```

The names of the modules that may be subsequently lt\_dlopened are added to the application link line. I am using the ‘-static’ option to force a static only link, which must use

dlpreopened modules by definition. I am only specifying this because my host has native dynamic loading, and Libtool will use that unless I force a static only link, like this:

```
$ libtool --mode=link gcc -static -g -o ltdl-loader ltdl-loader.c \
-lltdl -dlopen ltdl-module.la -dlopen simple-module.la
rm -f .libs/ltdl-loader.nm .libs/ltdl-loader.nmS \
.libs/ltdl-loader.nmT
creating .libs/ltdl-loaderS.c
extracting global C symbols from ../libs/ltdl-module.a
extracting global C symbols from ../libs/simple-module.a
(cd .libs && gcc -c -fno-builtin -fno-rtti -fno-exceptions \
"ltdl-loaderS.c")
rm -f .libs/ltdl-loaderS.c .libs/ltdl-loader.nm \
.libs/ltdl-loader.nmS .libs/ltdl-loader.nmT
gcc -g -o ltdl-loader ltdl-loader.c .libs/ltdl-loaderS.o \
../libs/ltdl-module.a -lm ../libs/simple-module.a \
/usr/lib/libltdl.a -ldl
rm -f .libs/ltdl-loaderS.o
$ ./ltdl-loader ltdl-module 345
Square root of 345 is 18.574176
=> 0
$ ./ltdl-loader simple-module World
Hello, World!
=> 0
```

Note that the current release of Libtool requires that the pseudo-library be present for any libltdl loaded module, even preloaded ones. Once again, if there is sufficient demand, this may be fixed in a future release. Until then, if the pseudo-library was deleted or cannot be found, this will happen:

```
$ rm -f simple-module.la
$ ./ltdl-loader simple-module World
./ltdl-loader: file not found.
```

A side effect of using the ‘LTDL\_SET\_PRELOADED\_SYMBOLS’ macro is that if you subsequently link the application without Libtool, you will get an undefined symbol for the Libtool supplied ‘lt\_preloaded\_symbols’. If you need to link in this fashion, you will need to provide a stub that supplies the missing definition. Conversely, you must be careful not to link the stub file when you *do* link with Libtool, because it will clash with the Libtool generated table it is supposed to replace:

```
#include <ltdl.h>
const lt_dlsymlist lt_preloaded_symbols[] = { { 0, 0 } };
```

Of course, if you use this stub, and link the application without the benefits of Libtool, you will not be able to use any preloaded modules – even if you statically link them, since there is no preloaded symbol lookup table in this case.

## 18.5 User Module Loaders

While writing the module loading code for GNU M4 1.5, I found that libltdl did not provide a way for loading modules in exactly the way I required: As good as the preloading feature of libltdl may be, and as useful as it is for simplifying debugging, it doesn’t have

all the functionality of full dynamic module loading when the host platform is limited to static linking. After all, you can only ever load modules that were specified at link time, so for access to user supplied modules the whole application must be relinked to preload these new modules before `lt_dlopen` will be able to make use of the additional module code.

In this situation, it would be useful to be able to automate this process. That is, if a libltdl using process is unable to `lt_dlopen` a module in any other fashion, but can find a suitable static archive in the module search path, it should relink itself along with the static archive (using `libtool` to preload the module), and then `exec` the new executable. Assuming all of this is successful, the attempt to `lt_dlopen` can be tried again – if the ‘suitable’ static archive was chosen correctly it should now be possible to access the preloaded code.

### 18.5.1 Loader Mechanism

Since Libtool 1.4, libltdl has provided a generalized method for loading modules, which can be extended by the user. libltdl has a default built in list of module loading mechanisms, some of which are peculiar to a given platform, others of which are more general. When the ‘`libltdl`’ subdirectory of a project is configured, the list is narrowed to include only those *mechanisms*, or simply *loaders*, which can work on the host architecture. When ‘`lt_dlopen`’ is called, the loaders in this list are tried, in order, until the named module has loaded, or all of the loaders in the list have been exhausted. The entries in the final list of loaders each have a unique name, although there may be several candidate loaders for a single name before the list is narrowed. For example, the ‘`dlopen`’ loader is implemented differently on BeOS and Solaris – for a single host, there can be only one implementation of any named loader. The name of a module loader is something entirely different to the name of a loaded module, something that should become clearer as you read on.

In addition to the loaders supplied with libltdl, your project can add more loaders of its own. New loaders can be added to the end of the existing list, or immediately before any other particular loader, thus giving you complete control of the relative priorities of all of the active loaders in your project.

In your module loading API, you might even support the dynamic loading of user supplied loaders: that is your users would be able to create dynamic modules which added more loading mechanisms to the existing list of loaders!

Version 1.4 of Libtool has a default list that potentially contains an implementation of the following loaders (assuming all are supported by the host platform):

<code>dlpreopen</code>	If the named module was preloaded, use the preloaded symbol table for subsequent <code>lt_dlsym</code> calls.
<code>dlopen</code>	If the host machine has a native dynamic loader API use that to try and load the module.
<code>dld</code>	If the host machine has GNU <code>dld</code> <sup>5</sup> , use that to try and load the module.

Note that loader names with a ‘`d1`’ prefix are reserved for future use by Libtool, so you should choose something else for your own module names to prevent a name clash with future Libtool releases.

---

<sup>5</sup> <http://www.gnu.org/software/dld>

### 18.5.2 Loader Management

The API supplies all of the functions you need to implement your own module loading mechanisms to solve problems just like this:

**lt\_dlloader\_t \* lt\_dlloader\_find** (const char \*loader\_name) Function

Each of the module loaders implemented by libltdl is stored according to a unique name, which can be used to lookup the associated handle. These handles operate in much the same way as `lt_dlhandles`: They are used for passing references to modules in and out of the API, except that they represent a kind of *module loading method*, as opposed to a loaded module instance.

This function finds the ‘`lt_dlloader_t`’ handle associated with the unique name passed as the only argument, or else returns ‘`NULL`’ if there is no such module loader registered.

**int lt\_dlloader\_add** (lt\_dlloader\_t \*place, Function

lt\_user\_dlloader \*dlloader, const char \*loader\_name)

This function is used to register your own module loading mechanisms with libltdl. If *place* is given it must be a handle for an already registered module loader, which the new loader *dlloader* will be placed in front of for the purposes of which order to try loaders in. If *place* is ‘`NULL`’, on the other hand, the new *dlloader* will be added to the end of the list of loaders to try when loading a module instance. In either case *loader\_name* must be a unique name for use with `lt_dlloader_find`.

The *dlloader* argument must be a C structure of the following format, populated with suitable function pointers which determine the functionality of your module loader:

```
struct lt_user_dlloader {
    const char      *sym_prefix;
    lt_module_open_t *module_open;
    lt_module_close_t *module_close;
    lt_find_sym_t    *find_sym;
    lt_dlloader_exit_t *dlloader_exit;
    lt_dlloader_data_t dlloader_data;
};
```

**int lt\_dlloader\_remove** (const char \*loader\_name) Function

When there are no more loaded modules that were opened by the given module loader, the loader itself can be removed using this function.

When you come to set the fields in the `lt_user_dlloader` structure, they must each be of the correct type, as described below:

**const char \* sym\_prefix** Type

If a particular module loader relies on a prefix to each symbol being looked up (for example, the Windows module loader necessarily adds a ‘`_`’ prefix to each symbol name passed to `lt_dlsym`), it should be recorded in the ‘`sym_prefix`’ field.

**lt\_module\_t lt\_module\_open\_t** (lt\_dlloader\_data\_t *loader\_data*,  
const char \**module\_name*) Type

When `lt_dlopen` has reached your registered module loader when attempting to load a dynamic module, this is the type of the `module_open` function that will be called. The name of the module that libltdl is attempting to load, along with the module loader instance data associated with the loader being used currently, are passed as arguments to such a function call.

The `lt_module_t` returned by functions of this type can be anything at all that can be recognised as unique to a successfully loaded module instance when passed back into the `module_close` or `find_sym` functions in the `lt_user_dlloader` module loader structure.

**int lt\_module\_close\_t** (lt\_dlloader\_data\_t *loader\_data*,  
lt\_module\_t *module*) Type

In a similar vein, a function of this type will be called by `lt_dlclose`, where *module* is the returned value from the ‘`module_open`’ function which loaded this dynamic module instance.

**lt\_ptr\_t lt\_find\_sym\_t** (lt\_dlloader\_data\_t *loader\_data*,  
lt\_module\_t *module*, const char \**symbol\_name*) Type

In a similar vein once more, a function of this type will be called by `lt_dlsym`, and must return the address of *symbol\_name* in *module*.

**int lt\_dlloader\_exit\_t** (lt\_dlloader\_data\_t *loader\_data*) Type

When a user module loader is `lt_dlloader_removed`, a function of this type will be called. That function is responsible for releasing any resources that were allocated during the initialisation of the loader, so that they are not ‘leaked’ when the `lt_user_dlloader` structure is recycled.

Note that there is no initialisation function type: the initialisation of a user module loader should be performed before the loader is registered with `lt_dlloader_add`.

**lt\_dlloader\_data\_t dlloader\_data** Type

The *dlloader\_data* is a spare field which can be used to store or pass any data specific to a particular module loader. That data will always be passed as the value of the first argument to each of the implementation functions above.

### 18.5.3 Loader Errors

When writing the code to fill out each of the functions needed to populate the `lt_user_dlloader` structure, you will often need to raise an error of some sort. The set of standard errors which might be raised by the internal module loaders are available for use in your own loaders, and should be used where possible for the sake of uniformity if nothing else. On the odd occasion where that is not possible, libltdl has API calls to register and set your own error messages, so that users of your module loader will be able to call `lt_dLError` and have the error message you set returned:

**int lt\_dlseterror** (int *errorcode*) Function

By calling this function with one of the error codes enumerated in the header file, 'ltddl.h', **lt\_dlerror** will return the associated diagnostic until the error code is changed again.

**int lt\_dladderror** (const char \**diagnostic*) Function

Often you will find that the existing error diagnostics do not describe the failure you have encountered. By using this function you can register a more suitable diagnostic with **libltdl**, and subsequently use the returned integer as an argument to **lt\_dlseterror**.

**libltdl** provides several other functions which you may find useful when writing a custom module loader. These are covered in the Libtool manual, along with more detailed descriptions of the functions described in the preceding paragraphs.

In the next chapter, we will discuss the more complex features of Automake, before moving on to show you how to use those features and add **libltdl** module loading to the Sic project from [Chapter 12 \[A Large GNU Autotools Project\]](#), page 123 in the chapter after that.

## 19 Advanced GNU Automake Usage

This chapter covers a few seemingly unrelated Automake features which are commonly considered ‘advanced’: conditionals, user-added language support, and automatic dependency tracking.

### 19.1 Conditionals

Automake conditionals are a way to omit or include different parts of the ‘Makefile’ depending on what `configure` discovers. A conditional is introduced in ‘`configure.in`’ using the ‘`AM_CONDITIONAL`’ macro. This macro takes two arguments: the first is the name of the condition, and the second is a shell expression which returns true when the condition is true.

For instance, here is how to make a condition named ‘`TRUE`’ which is always true:

```
AM_CONDITIONAL(TRUE, true)
```

As another example, here is how to make a condition named ‘`DEBUG`’ which is true when the user has given the ‘`--enable-debug`’ option to `configure`:

```
AM_CONDITIONAL(DEBUG, test "$enable_debug" = yes)
```

Once you’ve defined a condition in ‘`configure.in`’, you can refer to it in your ‘`Makefile.am`’ using the ‘`if`’ statement. Here is a part of a sample ‘`Makefile.am`’ that uses the conditions defined above:

```
if TRUE
## This is always used.
bin_PROGRAMS = foo
endif

if DEBUG
AM_CFLAGS = -g -DDEBUG
endif
```

It’s important to remember that Automake conditionals are *configure-time* conditionals. They don’t rely on any special feature of `make`, and there is no way for the user to affect the conditionals from the `make` command line. Automake conditionals work by rewriting the ‘`Makefile`’ – `make` is unaware that these conditionals even exist.

Traditionally, Automake conditionals have been considered an advanced feature. However, practice has shown that they are often easier to use and understand than other approaches to solving the same problem. I now recommend the use of conditionals to everyone.

For instance, consider this example:

```
bin_PROGRAMS = echo
if FULL_ECHO
echo_SOURCES = echo.c extras.c getopt.c
else
echo_SOURCES = echo.c
endif
```

In this case, the equivalent code without conditionals is more confusing and correspondingly more difficult for the new Automake user to figure out:

```

bin_PROGRAMS = echo
echo_SOURCES = echo.c
echo_LDADD   = @echo_extras@
EXTRA_echo_SOURCES = extras.c getopt.c

```

Automake conditionals have some limitations. One known problem is that conditionals don't interact properly with '+=' assignment. For instance, consider this code:

```

bin_PROGRAMS = z
z_SOURCES = z.c
if SOME_CONDITION
z_SOURCES += cond.c
endif

```

This code appears to have an unambiguous meaning, but Automake 1.4 doesn't implement this and will give an error. This bug will be fixed in the next major Automake release.

## 19.2 Language support

Automake comes with built-in knowledge of the most common compiled languages: C, C++, Objective C, Yacc, Lex, assembly, and Fortran. However, programs are sometimes written in an unusual language, or in a custom language that is translated into something more common. Automake lets you handle these cases in a natural way.

Automake's notion of a 'language' is tied to the suffix appended to each source file written in that language. You must inform Automake of each new suffix you introduce. This is done by listing them in the 'SUFFIXES' macro. For instance, suppose you are writing part of your program in the language 'M', which is compiled to object code by a program named `mc`. The typical suffix for an 'M' source file is '.m'. In your 'Makefile.am' you would write:

```
SUFFIXES = .m
```

This differs from ordinary `make` usage, where you would use the special `.SUFFIX` target to list suffixes.

Now you need to tell Automake (and `make`) how to compile a '.m' file to a '.o' file. You do this by writing an ordinary `make` suffix rule:

```

MC = mc
.m.o:
    $(MC) $(MCFLAGS) $(AM_MCFLAGS) -c $<

```

Note that we introduced the 'MC', 'MCFLAGS', and 'AM\_MCFLAGS' variables. While not required, this is good style in case you want to override any of these later (for instance from the command line).

Automake understands enough about suffix rules to recognize that '.m' files can be treated just like any file it already understands, so now you can write:

```

bin_PROGRAMS = myprogram
myprogram_SOURCES = foo.c something.m

```

Note that Automake does not really understand chained suffix rules; however, frequently the right thing will happen anyway. For instance, if you have a `.m.c` rule, Automake will naively assume that '.m' files should be turned into '.o' files – and then it will proceed to rely on `make` to do the real work. In this example, if the translation takes three steps—from



‘.m’ to ‘.x’, then from ‘.x’ to ‘.c’, and finally to ‘.o’—then Automake’s simplistic approach will break. Fortunately, these cases are very rare.

### 19.3 Automatic dependency tracking

Keeping track of dependencies for a large program is tedious and error-prone. Many edits require the programmer to update dependencies, but for some changes, such as adding a `#include` to an existing header, the change is large enough that he simply refuses (or does it incorrectly). To fix this problem, Automake supports automatic dependency tracking.

The implementation of automatic dependency tracking in Automake 1.4 requires `gcc` and GNU `make`. These programs are only required for maintainers; the ‘Makefile’s generated by `make dist` are completely portable. If you can’t use `gcc` or GNU `make` for your project, then you are simply out of luck; you have to disable dependency tracking.

Automake 1.5 will include a completely new dependency tracking implementation. This new implementation will work with any compiler and any version of `make`.

Another limitation of the current scheme is that the dependencies included into the portable ‘Makefile’s by `make dist` are derived from the current build environment. First, this means that you must use `make all` before you can meaningfully run `make dist` (otherwise the dependencies won’t have been created). Second, this means that any files not built in your current tree will not have dependencies in the distributed ‘Makefile’s. The new implementation will avoid both of these shortcomings as well.

Automatic dependency tracking is on by default; you don’t have to do anything special to get it. To turn it off, either run `automake -i` instead of plain `automake`, or put ‘no-dependencies’ into the ‘AUTOMAKE\_OPTIONS’ macro in each ‘Makefile.am’.



## 20 A Complex GNU Autotools Project

This chapter polishes the worked example I introduced in [Chapter 9 \[A Small GNU Autotools Project\]](#), [page 51](#), and developed in [Chapter 12 \[A Large GNU Autotools Project\]](#), [page 123](#). As always, the ideas presented here are my own views and not necessarily the only way to do things. Everything I present here has, however, served me well for quite some time, and you should find plenty of interesting ideas for your own projects.

Herein, I will add a `libltdl` module loading system to Sic, as well as some sample modules to illustrate how extensible such a project can be. I will also explain how to integrate the `‘dmalloc’` library into the development of a project, and show why this is important.

If you noticed that, as it stands, Sic is only useful as an interactive shell unable to read commands from a file, then go to the top of the class! In order for it to be of genuine use, I will extend it to interpret commands from a file too.

### 20.1 A Module Loading Subsystem

As you saw in [Chapter 18 \[Using GNU libltdl\]](#), [page 185](#), I need to put an invocation of the macro `‘AC_LIBTOOL_DLOPEN’` just before `‘AC_PROG_LIBTOOL’`, in the file `‘configure.in’`. But, as well as being able to use `libtoolize --ltdl`, which adds `libltdl` in a subdirectory with its own `subconfigure`, you can also manually copy just the `ltdl` source files into your project<sup>1</sup>, and use `AC_LIB_LTDL` in your existing `‘configure.in’`. At the time of writing, this is still a very new and (as yet) undocumented feature, with a few kinks that need to be ironed out. In any case you probably shouldn’t use this method to add `‘ltdl.lo’` to a C++ library, since `‘ltdl.c’` is written in C. If you do want to use `libltdl` with a C++ library, things will work much better if you build it in a subdirectory generated with `libtoolize --ltdl`.

For this project, lets:

```
$ cp /usr/share/libtool/libltdl/ltdl.[ch] sic/
```

The Sic module loader is probably as complicated as any you will ever need to write, since it must support two kinds of modules: modules which contain additional built-in commands for the interpreter; and modules which extend the Sic syntax table. A single module can also provide both syntax extensions *and* additional built-in commands.

#### 20.1.1 Initialising the Module Loader

Before using this code (or any other `libltdl` based module loader for that matter), a certain amount of initialisation is required:

- `libltdl` itself requires initialisation.
  1. `libltdl` should be told to use the same memory allocation routines used by the rest of Sic.
  2. Any preloaded modules (see [Section 18.4 \[dlpreopen Loading\]](#), [page 198](#)) need to be initialised with `LTDL_SET_PRELOADED_SYMBOLS()`.

---

<sup>1</sup> If you have an early 1.3c snapshot of Libtool, you will also need to copy the `‘ltdl.m4’` file into your distribution.

3. `ltdl_init()` must be called.

- The module search path needs to be set. Here I allow the installer to specify a default search path to correspond with the installed Sic modules at compile time, but search the directories in the runtime environment variable `'SIC_MODULES_PATH'` first.
- The internal error handling needs to be initialised.

Here is the start of the module loader, `'sic/module.c'`, including the initialisation code for libltdl:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#include "common.h"
#include "builtin.h"
#include "eval.h"
#include "ltdl.h"
#include "module.h"
#include "sic.h"

#ifndef SIC_MODULE_PATH_ENV
# define SIC_MODULE_PATH_ENV "SIC_MODULE_PATH"
#endif

int
module_init (void)
{
    static int initialised = 0;
    int errors = 0;

    /* Only perform the initialisation once. */
    if (!initialised)
    {
        /* ltdl should use the same mallocation as us. */
        lt_dlmalloc = (lt_ptr_t (*) (size_t)) xmalloc;
        lt_dlfree = (void (*) (lt_ptr_t)) free;

        /* Make sure preloaded modules are initialised. */
        LTDL_SET_PRELOADED_SYMBOLS();

        last_error = NULL;

        /* Call ltdl initialisation function. */
        errors = lt_dlinit();

        /* Set up the module search directories. */
        if (errors == 0)
        {
            const char *path = getenv (SIC_MODULE_PATH_ENV);
```

```

        if (path != NULL)
            errors = lt_dladdsearchdir(path);
    }

    if (errors == 0)
        errors = lt_dladdsearchdir(MODULE_PATH);

    if (errors != 0)
        last_error = lt_dlerror ();

    ++initialised;

    return errors ? SIC_ERROR : SIC_OKAY;
}

last_error = multi_init_error;
return SIC_ERROR;
}

```

### 20.1.2 Managing Module Loader Errors

The error handling is a very simplistic wrapper for the `libltdl` error functions, with the addition of a few extra errors specific to this module loader code<sup>2</sup>. Here are the error messages from `'module.c'`:

```

static char multi_init_error[]
    = "module loader initialised more than once";
static char no_builtin_table_error[]
    = "module has no builtin or syntax table";
static char builtin_unload_error[]
    = "builtin table failed to unload";
static char syntax_unload_error[]
    = "syntax table failed to unload";
static char module_not_found_error[]
    = "no such module";
static char module_not_unloaded_error[]
    = "module not unloaded";

static const char *last_error = NULL;

const char *
module_error (void)
{
    return last_error;
}

```

---

<sup>2</sup> This is very different to the way errors are managed when writing a custom loader for `libltdl`. Compare this section with [Section 18.5.3 \[libltdl Loader Errors\]](#), page 203.

### 20.1.3 Loading a Module

Individual modules are managed by finding specified *entry points* (prescribed exported symbols) in the module:

<b>const Builtin * builtin_table</b>	Variable
An array of names of built-in commands implemented by a module, with associated handler functions.	
<b>void module_init (Sic *sic)</b>	Function
If present, this function will be called when the module is loaded.	
<b>void module_finish (Sic *sic)</b>	Function
If supplied, this function will be called just before the module is unloaded.	
<b>const Syntax * syntax_table</b>	Variable
An array of syntactically significant symbols, and associated handler functions.	
<b>int syntax_init (Sic *sic)</b>	Function
If specified, this function will be called by Sic before the syntax of each input line is analysed.	
<b>int syntax_finish (Sic *sic, BufferIn *in, BufferOut *out)</b>	Function
Similarly, this function will be call after the syntax analysis of each line has completed.	

All of the hard work in locating and loading the module, and extracting addresses for the symbols described above is performed by libltdl. The `module_load` function below simply registers these symbols with the Sic interpreter so that they are called at the appropriate times – or diagnoses any errors if things don't go according to plan:

```
int
module_load (Sic *sic, const char *name)
{
    lt_dlhandle module;
    Builtin *builtin_table;
    Syntax *syntax_table;
    int status = SIC_OKAY;

    last_error = NULL;

    module = lt_dlopenext (name);

    if (module)
    {
        builtin_table = (Builtin*) lt_dlsym (module, "builtin_table");
```

```

    syntax_table = (Syntax *) lt_dlsym (module, "syntax_table");
    if (!builtin_table && !syntax_table)
    {
        lt_dlclose (module);
        last_error = no_builtin_table_error;
        module = NULL;
    }
}

if (module)
{
    ModuleInit *init_func
        = (ModuleInit *) lt_dlsym (module, "module_init");
    if (init_func)
        (*init_func) (sic);
}

if (module)
{
    SyntaxFinish *syntax_finish
        = (SyntaxFinish *) lt_dlsym (module, "syntax_finish");
    SyntaxInit *syntax_init
        = (SyntaxInit *) lt_dlsym (module, "syntax_init");

    if (syntax_finish)
        sic->syntax_finish = list_cons (list_new (syntax_finish),
                                           sic->syntax_finish);
    if (syntax_init)
        sic->syntax_init = list_cons (list_new (syntax_init),
                                           sic->syntax_init);
}

if (module)
{
    if (builtin_table)
        status = builtin_install (sic, builtin_table);

    if (syntax_table && status == SIC_OKAY)
        status = syntax_install (sic, module, syntax_table);

    return status;
}

last_error = lt_dlerror();
if (!last_error)
    last_error = module_not_found_error;

return SIC_ERROR;
}

```

Notice that the generalised `List` data type introduced earlier (see [Chapter 9 \[A Small GNU Autotools Project\]](#), [page 51](#)) is reused to keep a list of accumulated module initialisation and finalisation functions.

### 20.1.4 Unloading a Module

When unloading a module, several things must be done:

- Any built-in commands implemented by this module must be unregistered so that Sic doesn't try to call them after the implementation has been removed.
- Any syntax extensions implemented by this module must be similarly unregistered, including `syntax_init` and `syntax_finish` functions.
- If there is a finalisation entry point in the module, '`module_finish`' (see [Section 20.1.3 \[Loading a Module\]](#), [page 212](#)), it must be called.

My first cut implementation of a module subsystem kept a list of the entry points associated with each module so that they could be looked up and removed when the module was subsequently unloaded. It also kept track of multiply loaded modules so that a module wasn't unloaded prematurely. libltdl already does all of this though, and it is wasteful to duplicate all of that work. This system uses `lt_dlforeach` and `lt_dlgetinfo` to access libltdl's records of loaded modules, and save on duplication. These two functions are described fully in [section "Libltdl interface" in \*The Libtool Manual\*](#).

```
static int unload_ltmodule (lt_dlhandle module, lt_ptr_t data);

struct unload_data { Sic *sic; const char *name; };

int
module_unload (Sic *sic, const char *name)
{
    struct unload_data data;

    last_error = NULL;

    data.sic = sic;
    data.name = name;

    /* Stopping might be an error, or we may have unloaded the module. */
    if (lt_dlforeach (unload_ltmodule, (lt_ptr_t) &data) != 0)
        if (!last_error)
            return SIC_OKAY;

    if (!last_error)
        last_error = module_not_found_error;

    return SIC_ERROR;
}
```



This function asks `libltdl` to call the function `unload_ltdmodule` for each of the modules it has loaded, along with some details of the module it wants to unload. The tricky part of the callback function below is recalculating the entry point addresses for the module to be unloaded and then removing all matching addresses from the appropriate internal structures. Otherwise, the balance of this callback is involved in informing the calling `lt_dlforeach` loop of whether a matching module has been found and handled:

```
static int userdata_address_compare (List *elt, void *match);

/* This callback returns 0 if the module was not yet found.
   If there is an error, LAST_ERROR will be set, otherwise the
   module was successfully unloaded. */
static int
unload_ltdmodule (lt_dlhandle module, void *data)
{
    struct unload_data *unload = (struct unload_data *) data;
    const lt_dlnfo *module_info = lt_dlgetinfo (module);

    if ((unload == NULL)
        || (unload->name == NULL)
        || (module_info == NULL)
        || (module_info->name == NULL)
        || (strcmp (module_info->name, unload->name) != 0))
    {
        /* No match, return 0 to keep searching */
        return 0;
    }

    if (module)
    {
        /* Fetch the addresses of the entrypoints into the module. */
        Builtin *builtin_table
            = (Builtin *) lt_dlsym (module, "builtin_table");
        Syntax *syntax_table
            = (Syntax *) lt_dlsym (module, "syntax_table");
        void *syntax_init_address
            = (void *) lt_dlsym (module, "syntax_init");
        void **syntax_finish_address
            = (void *) lt_dlsym (module, "syntax_finish");
        List *stale;

        /* Remove all references to these entry points in the internal
           data structures, before actually unloading the module. */
        stale = list_remove (&unload->sic->syntax_init,
                             syntax_init_address, userdata_address_compare);
        XFREE (stale);

        stale = list_remove (&unload->sic->syntax_finish,
                             syntax_finish_address, userdata_address_compare);
        XFREE (stale);
    }
}
```

```

    if (builtin_table
        && builtin_remove (unload->sic, builtin_table) != SIC_OKAY)
    {
        last_error = builtin_unload_error;
        module = NULL;
    }

    if (syntax_table
        && SIC_OKAY != syntax_remove (unload->sic, module,
                                      syntax_table))
    {
        last_error = syntax_unload_error;
        module = NULL;
    }
}

if (module)
{
    ModuleFinish *finish_func
        = (ModuleFinish *) lt_dlsym (module, "module_finish");

    if (finish_func)
        (*finish_func) (unload->sic);
}

if (module)
{
    if (lt_dlclose (module) != 0)
        module = NULL;
}

/* No errors? Stop the search! */
if (module)
    return 1;

/* Find a suitable diagnostic. */
if (!last_error)
    last_error = lt_dlerror();
if (!last_error)
    last_error = module_not_unloaded_error;

/* Error diagnosed. Stop the search! */
return -1;
}

static int
userdata_address_compare (List *elt, void *match)
{

```

```

    return (int) (elt->userdata - match);
}

```

The `userdata_address_compare` helper function at the end is used to compare the address of recalculated entry points against the already registered functions and handlers to find which items need to be unregistered.

There is also a matching header file to export the module interface, so that the code for loadable modules can make use of it:

```

#ifndef SIC_MODULE_H
#define SIC_MODULE_H 1

#include <sic/builtin.h>
#include <sic/common.h>
#include <sic/sic.h>

BEGIN_C_DECLS

typedef void ModuleInit      (Sic *sic);
typedef void ModuleFinish    (Sic *sic);

extern const char *module_error (void);
extern int module_init          (void);
extern int module_load          (Sic *sic, const char *name);
extern int module_unload        (Sic *sic, const char *name);

END_C_DECLS

#endif /* !SIC_MODULE_H */

```

This header also includes some of the other Sic headers, so that in most cases, the source code for a module need only `#include <sic/module.h>`.

To make the module loading interface useful, I have added built-ins for `'load'` and `'unload'`. Naturally, these must be compiled into the bare `sic` executable, so that it is able to load additional modules:

```

#if HAVE_CONFIG_H
# include <config.h>
#endif

#include "module.h"
#include "sic_repl.h"

/* List of built in functions. */
#define builtin_functions \
    BUILTIN(exit,      0, 1) \
    BUILTIN(load,      1, 1) \
    BUILTIN(unload,    1, -1)

```

```

BUILTIN_DECLARATION (load)
{
    int status = SIC_ERROR;

    if (module_load (sic, argv[1]) < 0)
    {
        sic_result_clear (sic);
        sic_result_append (sic, "module \"", argv[1], "\" not loaded: ",
                           module_error (), NULL);
    }
    else
        status = SIC_OKAY;

    return status;
}

BUILTIN_DECLARATION (unload)
{
    int status = SIC_ERROR;
    int i;

    for (i = 1; argv[i]; ++i)
        if (module_unload (sic, argv[i]) != SIC_OKAY)
        {
            sic_result_clear (sic);
            sic_result_append (sic, "module \"", argv[i],
                               "\" not unloaded: ", module_error (), NULL);
        }
    else
        status = SIC_OKAY;

    return status;
}

```

These new built-in commands are simply wrappers around the module loading code in 'module.c'.

As with 'dlopen', you can use libltdl to 'lt\_dlopen' the main executable, and then lookup *its* symbols. I have simplified the initialisation of Sic by replacing the `sic_init` function in 'src/sic.c' by 'loading' the executable itself as a module. This works because I was careful to use the same format in 'sic\_builtin.c' and 'sic\_syntax.c' as would be required for a genuine loadable module, like so:

```

/* initialise the module subsystem */
if (module_init () != SIC_OKAY)
    sic_fatal ("module initialisation failed");

if (module_load (sic, NULL) != SIC_OKAY)
    sic_fatal ("sic initialisation failed");

```

## 20.2 A Loadable Module

A feature of the Sic interpreter is that it will use the ‘unknown’ built-in to handle any command line which is not handled by any of the other registered built-in callback functions. This mechanism is very powerful, and allows me to lookup unhandled built-ins in the user’s ‘PATH’, for instance.

Before adding any modules to the project, I have created a separate subdirectory, ‘modules’, to put the module source code into. Not forgetting to list this new subdirectory in the AC\_OUTPUT macro in ‘configure.in’, and the SUBDIRS macro in the top level ‘Makefile.am’, a new ‘Makefile.am’ is needed to build the loadable modules:

```
## Makefile.am -- Process this file with automake to produce Makefile.in
INCLUDES      = -I$(top_builddir) -I$(top_srcdir) \
               -I$(top_builddir)/sic -I$(top_srcdir)/sic \
               -I$(top_builddir)/src -I$(top_srcdir)/src

pkglib_LTLIBRARIES = unknown.la
```

pkglibdir is a Sic specific directory where modules will be installed, See [Chapter 14 \[Installing and Uninstalling Configured Packages\]](#), page 143.

For a library to be maximally portable, it should be written so that it does not require back-linking<sup>3</sup> to resolve its own symbols. That is, if at all possible you should design all of your libraries (not just dynamic modules) so that all of their symbols can be resolved at linktime. Sometimes, it is impossible or undesirable to architect your libraries and modules in this way. In that case you sacrifice the portability of your project to platforms such as AIX and Windows.

The key to building modules with libtool is in the options that are specified when the module is linked. This is doubly true when the module must work with libltdl’s dlpreopening mechanism.

```
unknown_la_SOURCES = unknown.c
unknown_la_LDFLAGS = -no-undefined -module -avoid-version
unknown_la_LIBADD  = $(top_builddir)/sic/libsic.la
```

Sic modules are built without a ‘lib’ prefix (‘-module’), and without version suffixes (‘-avoid-version’). All of the undefined symbols are resolved at linktime by ‘libsic.la’, hence ‘-no-undefined’.

Having added ‘ltdl.c’ to the ‘sic’ subdirectory, and called the AC\_LIB\_LTDL macro in ‘configure.in’, ‘libsic.la’ cannot build correctly on those architectures which do not support back-linking. This is because ‘ltdl.c’ simply abstracts the native dlopen API with a common interface, and that local interface often requires that a special library be linked – ‘-ldl’ on linux, for example. AC\_LIB\_LTDL probes the system to determine the name of any such dlopen library, and allows you to depend on it in a portable way by using the configure substitution macro, ‘@LIBADD\_DL@’. If I were linking a libtool compiled libltdl at this juncture, the system library details would have already been taken care of. In this

---

<sup>3</sup> See [Section 18.1 \[Introducing libltdl\]](#), page 185

project, I have bypassed that mechanism by compiling and linking ‘ltdl.c’ myself, so I have altered ‘sic/Makefile.am’ to use ‘@LIBADD\_DL@’:

```
lib_LTLIBRARIES      = libcommon.la libsic.la

libsic_la_LIBADD      = $(top_builddir)/replace/libreplace.la \
                        libcommon.la @LIBADD_DL@
libsic_la_SOURCES     = builtin.c error.c eval.c list.c ltdl.c \
                        module.c sic.c syntax.c
```

Having put all this infrastructure in place, the code for the ‘unknown’ module is a breeze (helper functions omitted for brevity):

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#include <sys/types.h>
#include <sys/wait.h>
#include <sic/module.h>

#define builtin_table    unknown_LTX_builtin_table

static char *path_find (const char *command);
static int path_execute (Sic *sic, const char *path, char *const argv[]);

/* Generate prototype. */
SIC_BUILTIN (builtin_unknown);

Builtin builtin_table[] = {
  { "unknown", builtin_unknown, 0, -1 },
  { 0, 0, -1, -1 }
};

BUILTIN_DECLARATION(unknown)
{
  char *path = path_find (argv[0]);
  int status = SIC_ERROR;

  if (!path)
    sic_result_append (sic, "command \"", argv[0], "\" not found",
                      NULL);
  else if (path_execute (sic, path, argv) != SIC_OKAY)
    sic_result_append (sic, "command \"", argv[0], "\" failed: ",
                      strerror (errno), NULL);
  else
    status = SIC_OKAY;

  return status;
}
```

In the first instance, notice that I have used the preprocessor to redefine the entry point functions to be compatible with `libltdls dlpreopen`, hence the `unknown_LTX_builtin_table` cpp macro. The ‘unknown’ handler function itself looks for a suitable executable in the user’s path, and if something suitable *is* found, executes it.

Notice that Libtool doesn’t relink dependent libraries (‘libsic’ depends on ‘libcommon’, for example) on my GNU/Linux system, since they are not required for the static library in any case, and because the dependencies are also encoded directly into the shared archive, ‘libsic.so’, by the original link. On the other hand, Libtool *will* relink the dependent libraries if that is necessary for the target host.

```
$ make
/bin/sh ../libtool --mode=compile gcc -DHAVE_CONFIG_H -I. -I. -I.. \
-I.. -I.. -I../sic -I../sic -I../src -I../src -g -O2 -c unknown.c
mkdir .libs
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -I.. -I../sic -I../sic -I../src \
-I../src -g -O2 -Wp,-MD,.deps/unknown.pp -c unknown.c -fPIC -DPIC \
-o .libs/unknown.lo
gcc -DHAVE_CONFIG_H -I. -I. -I.. -I.. -I.. -I../sic -I../sic -I../src \
I../src -g -O2 -Wp,-MD,.deps/unknown.pp -c unknown.c -o unknown.o \
>/dev/null 2>&1
mv -f .libs/unknown.lo unknown.lo
/bin/sh ../libtool --mode=link gcc -g -O2 -o unknown.la -rpath \
/usr/local/lib/sic -no-undefined -module -avoid-version unknown.lo \
../sic/libsic.la
rm -fr .libs/unknown.la .libs/unknown.* .libs/unknown.*
gcc -shared unknown.lo -L/tmp/sic/sic/.libs ../sic/.libs/libsic.so \
-lc -Wl,-soname -Wl,unknown.so -o .libs/unknown.so
ar cru .libs/unknown.a unknown.o
creating unknown.la
(cd .libs && rm -f unknown.la && ln -s ../unknown.la unknown.la)
$ ./libtool --mode=execute ldd ./unknown.la
      libsic.so.0 => /tmp/sic/.libs/libsic.so.0 (0x40002000)
      libc.so.6 => /lib/libc.so.6 (0x4000f000)
      libcommon.so.0 => /tmp/sic/.libs/libcommon.so.0 (0x400ec000)
      libdl.so.2 => /lib/libdl.so.2 (0x400ef000)
      /lib/ld-linux.so.2 => /lib/ld-linux.so.2 (0x80000000)
```

After compiling the rest of the tree, I can now use the ‘unknown’ module:

```
$ SIC_MODULE_PATH='cd ../modules; pwd' ./sic
] echo hello!
command "echo" not found.
] load unknown
] echo hello!
hello!
] unload unknown
] echo hello!
command "echo" not found.
] exit
$
```

## 20.3 Interpreting Commands from a File

For all practical purposes, any interpreter is pretty useless if it only works interactively. I have added a ‘source’ built-in command to ‘sic\_builtin.c’ which takes lines of input from a file and evaluates them using ‘sic\_repl.c’ in much the same way as lines typed at the prompt are evaluated otherwise. Here is the built-in handler:

```
/* List of built in functions. */
#define builtin_functions
    BUILTIN(exit,          0, 1)  \
    BUILTIN(load,          1, 1)  \
    BUILTIN(source,        1, -1) \
    BUILTIN(unload,        1, -1)

BUILTIN_DECLARATION (source)
{
    int status = SIC_OKAY;
    int i;

    for (i = 1; status == SIC_OKAY && argv[i]; ++i)
        status = source (sic, argv[i]);

    return status;
}
```

And the source function from ‘sic\_repl.c’:

```
int
source (Sic *sic, const char *path)
{
    FILE *stream;
    int result = SIC_OKAY;
    int save_interactive = is_interactive;

    SIC_ASSERT (sic && path);

    is_interactive = 0;

    if ((stream = fopen (path, "rt")) == NULL)
    {
        sic_result_clear (sic);
        sic_result_append (sic, "cannot source '", path, "\": ",
                           strerror (errno), NULL);
        result = SIC_ERROR;
    }
    else
        result = evalstream (sic, stream);

    is_interactive = save_interactive;

    return result;
}
```



```
}

```

The reason for separating the `source` function in this way, is that it makes it easy for the startup sequence in `main` to evaluate a startup file. In traditional Unix fashion, the startup file is named `‘.sircrc’`, and is evaluated if it is present in the user’s home directory:

```
static int
evalsircrc (Sic *sic)
{
    int result = SIC_OKAY;
    char *home = getenv ("HOME");
    char *sircrcpath, *separator = "";
    int len;

    if (!home)
        home = "";

    len = strlen (home);
    if (len && home[len - 1] != '/')
        separator = "/";

    len += strlen (separator) + strlen (SIRCRCFILE) + 1;

    sircrcpath = XMALLOC (char, len);
    sprintf (sircrcpath, "%s%s%s", home, separator, SIRCRCFILE);

    if (access (sircrcpath, R_OK) == 0)
        result = source (sic, sircrcpath);

    return result;
}
```

## 20.4 Integrating Dmalloc

A huge number of bugs in C and C++ code are caused by mismanagement of memory. Using the wrapper functions described earlier (see [Section 9.2.1.2 \[Memory Management\]](#), [page 62](#)), or their equivalent, can help immensely in reducing the occurrence of such bugs. Ultimately, you will introduce a difficult-to-diagnose memory bug in spite of these measures.

That is where Dmalloc<sup>4</sup> comes in. I recommend using it routinely in all of your projects — you will find all sorts of leaks and bugs that might otherwise have lain dormant for some time. Automake has explicit support for Dmalloc to make using it in your own projects as painless as possible. The first step is to add the macro `‘AM_WITH_DMALLOC’` to `‘configure.in’`. Citing this macro adds a `‘--with-dmalloc’` option to `configure`, which, when specified by the user, adds `‘-ldmalloc’` to `‘LIBS’` and defines `‘WITH_DMALLOC’`.

The usefulness of Dmalloc is much increased by compiling an entire project with the header, `‘dmalloc.h’` — easily achieved in Sic by conditionally adding it to `‘common-h.in’`:

---

<sup>4</sup> Dmalloc is distributed from <http://www.dmalloc.com>.

```

BEGIN_C_DECLS

#define XCALLOC(type, num) \
    ((type *) xalloc ((num), sizeof(type)))
#define XMALLOC(type, num) \
    ((type *) xmalloc ((num) * sizeof(type)))
#define XREALLOC(type, p, num) \
    ((type *) xrealloc ((p), (num) * sizeof(type)))
#define XFREE(stale) \
    do { \
        if (stale) { free ((void *) stale); stale = 0; } \
    } while (0)

extern void *xalloc      (size_t num, size_t size);
extern void *xmalloc     (size_t num);
extern void *xrealloc    (void *p, size_t num);
extern char *xstrdup     (const char *string);

END_C_DECLS

#ifdef WITH_DMALLOC
# include <dmalloc.h>
#endif

```

I have been careful to include the ‘`dmalloc.h`’ header from the end of this file so that it overrides my own *definitions* without renaming the function *prototypes*. Similarly I must be careful to accommodate Dmalloc’s redefinition of the mallocation routines in ‘`sic/xmalloc.c`’ and ‘`sic/xstrdup.c`’, by putting each file inside an ‘`#ifndef WITH_DMALLOC`’. That way, when compiling the project, if ‘`--with-dmalloc`’ is specified and the ‘`WITH_DMALLOC`’ preprocessor symbol is defined, then Dmalloc’s debugging definitions of `xstrdup` et. al. will be used in place of the versions I wrote.

Enabling Dmalloc is now simply a matter of reconfiguring the whole package using the ‘`--with-dmalloc`’ option, and disabling it again is a matter of reconfiguring without that option.

The use of Dmalloc is beyond the scope of this book, and is in any case described very well in the documentation that comes with the package. I strongly recommend you become familiar with it – the time you invest here will pay dividends many times over in the time you save debugging.

This chapter completes the description of the Sic library project, and indeed this part of the book. All of the infrastructure for building an advanced command line shell is in place now – you need only add the builtin and syntax function definitions to create a complete shell of your own.

Each of the chapters in the next part of the book explores a more specialised application of the GNU Autotools, starting with a discussion of M4, a major part of the implementation of Autoconf.

## Part III



## 21 M4

M4 is a general purpose tool for processing text and has existed on Unix systems of all kinds for many years, rarely catching the attention of users. Text generation through macro processing is not a new concept. Originally M4 was designed as the preprocessor for the Rational FORTRAN system and was influenced by the General Purpose Macro generator, GPM, first described by Stratchey in 1965! GNU M4 is the GNU project's implementation of M4 and was written by René Seindal in 1990.

In recent years, awareness of M4 has grown through its use by popular free software packages. The Sendmail package incorporates a configuration system that uses M4 to generate its complex `'sendmail.cf'` file from a simple specification of the desired configuration. Autoconf uses M4 to generate output files such as a `'configure'` script.

It is somewhat unfortunate that users of GNU Autotools need to know so much about M4, because it has been too exposed. Many of these tools' implementation details were simply left up to M4, forcing the user to know about M4 in order to use them. It is a well-known problem and there is a movement amongst the development community to improve this shortcoming in the future. This deficiency is the primary reason that this chapter exists—it is important to have a good working knowledge of M4 in order to use the GNU Autotools and to extend it with your own macros (see [Chapter 23 \[Writing New Macros for Autoconf\]](#), page 253).

The GNU M4 manual provides a thorough tutorial on M4. Please refer to it for additional information.

### 21.1 What does M4 do?

`m4` is a general purpose tool suitable for all kinds of text processing applications—not unlike the C preprocessor, `cpp`, with which you are probably familiar. Its obvious application is as a front-end for a compiler—`m4` is in many ways superior to `cpp`.

Briefly, `m4` reads text from the input and writes processed text to the output. Symbolic macros may be defined which have replacement text. As macro invocations are encountered in the input, they are replaced ('expanded') with the macro's definition. Macros may be defined with a set of parameters and the definition can specify where the actual parameters will appear in the expansion. These concepts will be elaborated on in [Section 21.3 \[Fundamentals of M4 processing\]](#), page 228.

M4 includes a set of pre-defined macros that make it substantially more useful. The most important ones will be discussed in [Section 21.4 \[Features of M4\]](#), page 232. These macros perform functions such as arithmetic, conditional expansion, string manipulation and running external shell commands.

### 21.2 How GNU Autotools uses M4

The GNU Autotools may all appear to use M4, but in actual fact, it all boils down to `autoconf` that invokes `m4` to generate your `'configure'` script. You might be surprised to learn that the shell code in `'configure'` does not use `m4` to generate a final `'Makefile'` from `'Makefile.in'`. Instead, it uses `sed`, since that is more likely to be present on an end-user's system and thereby removes the dependency on `m4`.

Automake and Libtool include a lot of M4 input files. These are macros provided with each package that you can use directly (or indirectly) from your ‘`configure.in`’. These packages don’t invoke `m4` themselves.

If you have already installed Autoconf on your system, you may have encountered problems due to its strict M4 requirements. Autoconf *demands* to use GNU M4, mostly due to it exceeding limitations present in other M4 implementations. As noted by the Autoconf manual, this is not an onerous requirement, as it only affects package maintainers who must regenerate ‘`configure`’ scripts.

Autoconf’s own ‘`Makefile`’ will freeze some of the Autoconf ‘`.m4`’ files containing macros as it builds Autoconf. When M4 freezes an input file, it produces another file which represents the internal state of the M4 processor so that the input file does not need to be parsed again. This helps to reduce the startup time for `autoconf`.

## 21.3 Fundamentals of M4 processing

When properly understood, M4 seems like child’s play. However, it is common to learn M4 in a piecemeal fashion and to have an incomplete or inaccurate understanding of certain concepts. Ultimately, this leads to hours of furious debugging. It is important to understand the fundamentals well before progressing to the details.

### 21.3.1 Token scanning

`m4` scans its input stream, generating (often, just copying) text to the output stream. The first step that `m4` performs in processing is to recognize *tokens*. There are three kinds of tokens:

**Names**        A name is a sequence of characters that starts with a letter or an underscore and may be followed by additional letters, characters and underscores. The end of a name is recognized by the occurrence a character which is not any of the permitted characters—for example, a period. A name is always a candidate for macro expansion (Section 21.3.2 [Macros and macro expansion], page 229), whereby the name will be replaced in the output by a macro definition of the same name.

**Quoted strings**    A sequence of characters may be *quoted* (Section 21.3.3 [Quoting], page 231) with a starting quote at the beginning of the string and a terminating quote at the end. The default M4 quote characters are ‘`“`’ and ‘`”`’, however Autoconf reassigns them to ‘`[`’ and ‘`]`’, respectively. Suffice to say, M4 will remove the quote characters and pass the inner string to the output (Section 21.3.3 [Quoting], page 231).

**Other tokens**      All other tokens are those single characters which are not recognized as belonging to any of the other token types. They are passed through to the output unaltered.

Like most programming languages, M4 allows you to write comments in the input which will be ignored. Comments are delimited by the ‘`#`’ character and by the end of a line.

Comments in M4 differ from most languages, though, in that the text within the comment, including delimiters, is passed through to the output unaltered. Although the comment delimiting characters can be reassigned by the user, this is highly discouraged, as it may break GNU Autotools macros which rely on this fact to pass Bourne shell comment lines—which share the same comment delimiters—through to the output unaffected.

### 21.3.2 Macros and macro expansion

Macros are definitions of replacement text and are identified by a name—as defined by the syntax rules given in [Section 21.3.1 \[Token scanning\]](#), [page 228](#). M4 maintains an internal table of macros, some of which are built-ins defined when `m4` starts. When a name is found in the input that matches a name registered in M4’s macro table, the macro *invocation* in the input is replaced by the macro’s definition in the output. This process is known as *expansion*—even if the new text may be shorter! Many beginners to M4 confuse themselves the moment they start to use phrases like ‘I am going to call this particular macro, which returns this value’. As you will see, macros differ significantly from *functions* in other programming languages, regardless of how similar their syntax may seem. You should instead use phrases like ‘If I invoke this macro, it will expand to this text’.

Suppose M4 knows about a simple macro called ‘foo’ that is defined to be ‘bar’. Given the following input, `m4` would produce the corresponding output:

```
That is one big foo.
⇒That is one big bar.
```

The period character at the end of this sentence is not permitted in macro names, thus `m4` knows when to stop scanning the ‘foo’ token and consult the table of macro definitions for a macro named ‘foo’.

Curiously, macros are defined to `m4` using the built-in macro `define`. The example shown above would be defined to `m4` with the following input:

```
define('foo', 'bar')
```

Since `define` is itself a macro, it too must have an expansion—by definition, it is the empty string, or *void*. Thus, `m4` will appear to consume macro invocations like these from the input. The ‘ and ’ characters are M4’s default quote characters and play an important role ([Section 21.3.3 \[Quoting\]](#), [page 231](#)). Additional built-in macros exist for managing macro definitions ([Section 21.4.2 \[Macro management\]](#), [page 233](#)).

We’ve explored the simplest kind of macros that exist in M4. To make macros substantially more useful, M4 extends the concept to macros which accept a number of arguments<sup>1</sup>. If a macro is given arguments, the macro may address its arguments using the special macro names ‘\$1’ through to ‘\$n’, where ‘n’ is the maximum number of arguments that the macro cares to reference. When such a macro is invoked, the argument list must be delimited by commas and enclosed in parentheses. Any whitespace that precedes an argument is discarded, but trailing whitespace (for example, before the next comma) is preserved. Here is an example of a macro which expands to its third argument:

```
define('foo', '$3')
That is one big foo(3, '0x', 'beef').
```

---

<sup>1</sup> GNU M4 permits an unlimited number of arguments, whereas other versions of M4 limit the number of addressable arguments to nine.

```
⇒That is one big beef.
```

Arguments in M4 are simply text, so they have no type. If a macro which accepts arguments is invoked, `m4` will expand the macro regardless of how many arguments are provided. M4 will not produce errors due to conditions such as a mismatched number of arguments, or arguments with malformed values/types. It is the responsibility of the macro to validate the argument list and this is an important practice when writing GNU Autotools macros. Some common M4 idioms have developed for this purpose and are covered in [Section 21.4.3 \[Conditionals\]](#), page 234. A macro that expects arguments can still be invoked without arguments—the number of arguments seen by the macro will be zero:

```
This is still one big foo.
⇒That is one big .
```

A macro invoked with an empty argument list is not empty at all, but rather is considered to be a single empty string:

```
This is one big empty foo().
⇒That is one big .
```

It is also important to understand how macros are expanded. It is here that you will see why an M4 macro is not the same as a function in any other programming language. The explanation you’ve been reading about macro expansion thus far is a little bit simplistic: macros are not exactly matched in the input and expanded in the output. In actual fact, the macro’s expansion replaces the invocation in the input stream and it is *rescanned* for further expansions until there are none remaining. Here is an illustrative example:

```
define('foobar', 'FUBAR')
define('f', 'foo')
f()bar
⇒FUBAR
```

If the token `'a1'` were to be found in the input, `m4` would replace it with `'a2'` in the input stream and rescan. This continues until no definition can be found for `a4`, at which point the literal text `'a4'` will be sent to the output. This is *by far the biggest point of misunderstanding* for new M4 users.

The same principles apply for the collection of arguments to macros which accept arguments. Before a macro’s actual arguments are handed to the macro, they are expanded until there are no more expansions left. Here is an example—using the built-in `define` macro (where the problems are no different) which highlights the consequences of this. Normally, `define` will redefine any existing macro:

```
define(foo, bar)
define(foo, baz)
```

In this example, we expect `'foo'` to be defined to `'bar'` and then redefined to `'baz'`. Instead, we’ve defined a new macro `'bar'` that is defined to be `'baz'`! Why? The second `define` invocation has its arguments expanded prior to the expanding the `define` macro. At this stage, the name `'foo'` is expanded to its original definition, `bar`. In effect, we’ve stated:

```
define(foo, bar)
define(bar, baz)
```



Sometimes this can be a very useful property, but mostly it serves to thoroughly confuse the GNU Autotools macro writer. The key is to know that `m4` will expand as much text as it can as early as possible in its processing. Expansion can be prevented by quoting<sup>2</sup> and is discussed in detail in the following section.

### 21.3.3 Quoting

It has been shown how `m4` expands macros when it encounters a name that matches a defined macro in the input. There are times, however, when you wish to defer expansion. Principally, there are three situations when this is so:

#### Free-form text

There may be free-form text that you wish to appear at the output—and as such, be unaltered by any macros that may be inadvertently invoked in the input. It is not always possible to know if some particular name is defined as a macro, so it should be quoted.

#### Overcoming syntax rules

Sometimes you may wish to form strings which would violate M4's syntax rules – for example, you might wish to use leading whitespace or a comma in a macro argument. The solution is to quote the entire string.

#### Macro arguments

This is the most common situation for quoting: when arguments to macros are to be taken literally and not expanded as the arguments are collected. In the previous section, an example was given that demonstrates the effects of not quoting the first argument to `define`. Quoting macro arguments is considered a good practice that you should emulate.

Strings are quoted by surrounding the quoted text with the `‘‘` and `’’` characters. When `m4` encounters a quoted string—as a type of token (Section 21.3.1 [Token scanning], page 228)—the quoted string is expanded to the string itself, with the outermost quote characters removed.

Here is an example of a string that is triple quoted:

```
‘‘‘foo’’’  
⇒‘‘foo’’
```

A more concrete example uses quoting to demonstrate how to prevent unwanted expansion within macro definitions:

```
define('foo', '‘bar’')dnl  
define('bar', 'zog')dnl  
foo  
⇒bar
```

When the macro `'foo'` is defined, `m4` strips off the outermost quotes and registers the definition `'bar'`. The `dnl` text has a special purpose, too, which will be covered in Section 21.4.1 [Discarding input], page 232.

As the macro `'foo'` is expanded, the next pair of quote characters are stripped off and the string is expanded to `'bar'`. Since the expansion of the quoted string is the string itself

---

<sup>2</sup> Which is precisely what the `‘‘` and `’’` characters in all of the examples in this section are.

(minus the quote characters), we have prevented unwanted expansion from the string ‘`bar`’ to ‘`zog`’.

As mentioned in [Section 21.3.1 \[Token scanning\]](#), [page 228](#), the default M4 quote characters are ‘`“`’ and ‘`”`’. Since these are two commonly used characters in Bourne shell programming<sup>3</sup>, Autoconf reassigns these to the ‘`[`’ and ‘`]`’ characters—a symmetric looking pair of characters least likely to cause problems when writing GNU Autotools macros. From this point forward, we shall use ‘`[`’ and ‘`]`’ as the quote characters and you can forget about the default M4 quotes.

Autoconf uses M4’s built-in `changequote` macro to perform this reassignment and, in fact, this built-in is still available to you. In recent years, the common practice when needing to use the quote characters ‘`[`’ or ‘`]`’ or to quote a string with an legitimately imbalanced number of the quote characters has been to invoke `changequote` and temporarily reassign them around the affected area:

```

dnl Uh-oh, we need to use the apostrophe! And even worse, we have two
dnl opening quote marks and no closing quote marks.
changequote(<<, >>)dnl
perl -e 'print "$]\n";'
changequote([, ])dnl

```

This leads to a few potential problems, the least of which is that it’s easy to reassign the quote characters and then forget to reset them, leading to total chaos! Moreover, it is possible to entirely disable M4’s quoting mechanism by blindly changing the quote characters to a pair of empty strings.

In hindsight, the overwhelming conclusion is that using `changequote` within the GNU Autotools framework is a bad idea. Instead, leave the quote characters assigned as ‘`[`’ and ‘`]`’ and use the special strings `@<:@` and `@:>@` anywhere you want real square brackets to appear in your output. This is an easy practice to adopt, because it’s faster and less error prone than using `changequote`:

```
perl -e 'print "$@:>@\n";'
```

This, and other guidelines for using M4 in the GNU Autotools framework are covered in detail in [Section 21.5 \[Writing macros within the GNU Autotools framework\]](#), [page 236](#).

## 21.4 Features of M4

M4 includes a number of pre-defined macros that make it a powerful preprocessor. We will take a tour of the most important features provided by these macros. Although some of these features are not very relevant to GNU Autotools users, Autoconf is implemented using most of them. For this reason, it is useful to understand the features to better understand Autoconf’s behavior and for debugging your own ‘`configure`’ scripts.

### 21.4.1 Discarding input

A macro called `dnl` discards text from the input. The `dnl` macro takes no arguments and expands to the empty string, but it has the side effect of discarding all input up to and including the next newline character. Here is an example of `dnl` from the Autoconf source code:

---

<sup>3</sup> The ‘`“`’ is used in grave redirection and ‘`”`’ for the shell’s own quote character!

```
# AC_LANG_POP
# -----
# Restore the previous language.
define([AC_LANG_POP],
[popdef([_AC_LANG])dn1
ifelse(_AC_LANG, [_AC_LANG],
      [AC_FATAL([too many $0])])dn1
AC_LANG(_AC_LANG)])
```

It is important to remember `dn1`'s behavior: it discards the newline character, which can have unexpected effects on generated 'configure' scripts! If you want a newline to appear in the output, you must add an extra blank line to compensate.

`dn1` need not appear in the first column of a given line – it will begin discarding input at any point that it is invoked in the input file. However, be aware of the newline eating problem again! In the example of `AC_TRY_LINK_FUNC` above, note the deliberate use of `dn1` to remove surplus newline characters.

In general, `dn1` makes sense for macro invocations that appear on a single line, where you would expect the whole line to simply vanish from the output. In the following subsections, `dn1` will be used to illustrate where it makes sense to use it.

## 21.4.2 Macro management

A number of built-in macros exist in M4 to manage macros. We shall examine the most common ones that you're likely to encounter. There are others and you should consult the GNU M4 manual for further information.

The most obvious one is `define`, which defines a macro. It expands to the empty string:

```
define([foo], [bar])dn1
define([combine], [$1 and $2])dn1
```

It is worth highlighting again the liberal use of quoting. We wish to define a pair of macros whose names are *literally* `foo` and `combine`. If another macro had been previously defined with either of these names, `m4` would have expanded the macro immediately and passed the expansion of `foo` to `define`, giving unexpected results.

The `undefine` macro will remove a macro's definition from M4's macro table. It also expands to the empty string:

```
undefine([foo])dn1
undefine([combine])dn1
```

Recall that once removed from the macro table, unmatched text will once more be passed through to the output.

The `defn` macro expands to the definition of a macro, named by the single argument to `defn`. It is quoted, so that it can be used as the body of a new, renamed macro:

```
define([newbie], defn([foo]))dn1
undefine([foo])dn1
```

The `ifdef` macro can be used to determine if a macro name has an existing definition. If it does exist, `ifdef` expands to the second argument, otherwise it expands to the third:

```
ifdef([foo], [yes], [no])dn1
```

Again, **yes** and **no** have been quoted to prevent expansion due to any pre-existing macros with those names. *Always* consider this a real possibility!

Finally, a word about built-in macros: these macros are all defined for you when **m4** is started. One common problem with these macros is that they are not in any kind of name space, so it's easier to accidentally invoke them or want to define a macro with an existing name. One solution is to use the **define** and **defn** combination shown above to rename all of the macros, one by one. This is how Autoconf makes the distinction clear.

### 21.4.3 Conditionals

Macros which can expand to different strings based on runtime tests are extremely useful—they are used extensively throughout macros in GNU Autotools and third party macros. The macro that we will examine closely is **ifelse**. This macro compares two strings and expands to a different string based on the result of the comparison. The first form of **ifelse** is akin to the **if/then/else** construct in other programming languages:

```
ifelse(string1, string2, equal, not-equal)
```

The other form is unusual to a beginner because it actually resembles a **case** statement from other programming languages:

```
ifelse(string1, string2, equala, string3, string4, equalb, default)
```

If '**string1**' and '**string2**' are equal, this macro expands to '**equala**'. If they are not equal, **m4** will shift the argument list three positions to the left and try again:

```
ifelse(string3, string4, equalb, default)
```

If '**string3**' and '**string4**' are equal, this macro expands to '**equalb**'. If they are not equal, it expands to '**default**'. The number of cases that may be in the argument list is unbounded.

As it has been mentioned in [Section 21.3.2 \[Macros and macro expansion\]](#), page 229, macros that accept arguments may access their arguments through specially named macros like '**\$1**'. If a macro has been defined, no checking of argument counts is performed before it is expanded and the macro may examine the number of arguments given through the '**\$#**' macro. This has a useful result: you may invoke a macro with too few (or too many) arguments and the macro will still be expanded. In the example below, '**\$2**' will expand to the empty string.

```
define([foo], [$1 and $2])dnl
foo([a])
⇒ a and
```

This is useful because **m4** will expand the macro and give the macro the opportunity to test each argument for the empty string. In effect, we have the equivalent of default arguments from other programming languages. The macro can use **ifelse** to provide a default value if, say, '**\$2**' is the empty string. You will notice in much of the documentation for existing Autoconf macros that arguments may be left blank to accept the default value. This is an important idiom that you should practice in your own macros.

In this example, we wish to accept the default shell code fragment for the case where '**/etc/passwd**' is found in the build system's file system, but output '**Big trouble!**' if it is not.

```
AC_CHECK_FILE([/etc/passwd], [], [echo "Big trouble!"])
```

### 21.4.4 Looping

There is no support in M4 for doing traditional iterations (ie. ‘for-do’ loops), however macros may invoke themselves. Thus, it is possible to iterate using recursion. The recursive definition can use conditionals ([Section 21.4.3 \[Conditionals\], page 234](#)) to terminate the loop at its completion by providing a trivial case. The GNU M4 manual provides some clever recursive definitions, including a definition for a `forloop` macro that emulates a ‘for-do’ loop.

It is conceivable that you might wish to use these M4 constructs when writing macros to generate large amounts of in-line shell code or arbitrarily nested `if; then; fi` statements.

### 21.4.5 Diversions

Diversions are a facility in M4 for diverting text from the input stream into a holding buffer. There is a large number of diversion buffers in GNU M4, limited only by available memory. Text can be diverted into any one of these buffers and then ‘undiverted’ back to the output (diversion number 0) at a later stage.

Text is diverted and undiverted using the `divert` and `undivert` macros. They expand to the empty string, with the side effect of setting the diversion. Here is an illustrative example:

```
divert(1)dnl
This goes at the end.
divert(0)dnl
This goes at the beginning.
undivert(1)dnl
⇒This goes at the beginning.
⇒This goes at the end.
```

It is unlikely that you will want to use diversions in your own macros, and it is difficult to do reliably without understanding the internals of Autoconf. However, it is interesting to note that this is how `autoconf` generates fragments of shell code on-the-fly that must precede shell code at the current point in the ‘`configure`’ script.

### 21.4.6 Including files

M4 permits you to include files into the input stream using the `include` and `sinclude` macros. They simply expand to the contents of the named file. Of course, the expansion will be rescanned as the normal rules dictate ([Section 21.3 \[Fundamentals of M4 processing\], page 228](#)).

The difference between `include` and `sinclude` is subtle: if the filename given as an argument to `include` is not present, an error will be raised. The `sinclude` macro will instead expand to the empty string—presumably the ‘s’ stands for ‘silent’.

Older GNU Autotools macros that tried to be modular would use the `include` and `sinclude` macros to import libraries of macros from other sources. While this is still a workable mechanism, there is an active effort within the GNU Autotools development community to improve the packaging system for macros. An ‘`--install`’ option is being developed to improve the mechanism for importing macros from a library.

## 21.5 Writing macros within the GNU Autotools framework

With a good grasp of M4 concepts, we may turn our attention to applying these principles to writing ‘`configure.in`’ files and new ‘`.m4`’ macro files. There are some differences between writing generic M4 input files and macros within the GNU Autotools framework and these will be covered in this section, along with some useful hints on working within the framework. This section ties in closely with [Chapter 23 \[Writing New Macros for Autoconf\]](#), page 253.

Now that you are familiar with the capabilities of M4, you can forget about the names of the built-in M4 macros—they should be avoided in the GNU Autotools framework. Where appropriate, the framework provides a collection of macros that are laid on top of the M4 built-ins. For instance, the macros in the `AC_` family are just regular M4 macros that take a number of arguments and rely on an extensive library of `AC_` support macros.

### 21.5.1 Syntactic conventions

Some conventions have grown over the life of the GNU Autotools, mostly as a disciplined way of avoiding M4 pitfalls. These conventions are designed to make your macros more robust, your code easier to read and, most importantly, improve your chances for getting things to work the first time! A brief list of recommended conventions appears below:

- Do not use the M4 built-in `changequote`. Any good macro will already perform sufficient quoting.
- Never use the argument macros (e.g. ‘`$1`’) within shell comments and `dnl` remarks. If such a comment were to be placed within a macro definition, M4 will expand the argument macros leading to strange results. Instead, quote the argument number to prevent unwanted expansion. For instance, you would use ‘`[$1]`’ in the comment.
- Quote the M4 comment character, ‘`#`’. This can appear often in shell code fragments and can have undesirable effects if M4 ignores any expansions in the text between the ‘`#`’ and the next newline.
- In general, macros invoked from ‘`configure.in`’ should be placed one per line. Many of the GNU Autotools macros conclude their definitions with a `dnl` to prevent unwanted whitespace from accumulating in ‘`configure`’.
- Many of the `AC_` macros, and others which emulate their good behavior, permit default values for unspecified arguments. It is considered good style to explicitly show your intention to use an empty argument by using a pair of quotes, such as `[]`.
- Always quote the names of macros used within the definitions of other macros.
- When writing new macros, generate a small ‘`configure.in`’ that uses (and abuses!) the macro—particularly with respect to quoting. Generate a ‘`configure`’ script with `autoconf` and inspect the results.

### 21.5.2 Debugging with M4

After writing a new macro or a ‘`configure.in`’ template, the generated ‘`configure`’ script may not contain what you expect. Frequently this is due to a problem in quoting (see [Section 21.3.3 \[Quoting\]](#), page 231), but the interactions between macros can be complex. When you consider that the arguments to GNU Autotools macros are often shell scripts,

things can get rather hairy. A number of techniques exist for helping you to debug these kinds of problems.

Expansion problems due to over-quoting and under-quoting can be difficult to pinpoint. Autoconf half-heartedly tries to detect this condition by scanning the generated ‘`configure`’ script for any remaining invocations of the `AC_` and `AM_` families of macros. However, this only works for the `AC_` and `AM_` macros and not for third party macros.

M4 provides a comprehensive facility for tracing expansions. This makes it possible to see how macro arguments are expanded and how a macro is finally expanded. Often, this can be half the battle in discovering if the macro definition or the invocation is at fault. Autoconf 2.15 will include this tracing mechanism. To trace the generation of ‘`configure`’, Autoconf can be invoked like so:

```
$ autoconf --trace=AC_PROG_CC
```

Autoconf provides fine control over which macros are traced and the format of the trace output. You should refer to the Autoconf manual for further details.

GNU `m4` also provides a debugging mode that can be helpful in discovering problems such as infinite recursion. This mode is activated with the ‘`-d`’ option. In order to pass options to `m4`, invoke Autoconf like so:

```
$ M4='m4 -dV' autoconf
```

Another situation that can arise is the presence of shell syntax errors in the generated ‘`configure`’ script. These errors are usually obvious, as the shell will abort ‘`configure`’ when the syntax error is encountered. The task of then locating the troublesome shell code in the input files can be potentially quite difficult. If the erroneous shell code appears in ‘`configure.in`’, it should be easy to spot—presumably because you wrote it recently! If the code is imported from a third party macro, though, it may only be present because you invoked that macro. A trick to help locate these kinds of errors is to place some magic text (`__MAGIC__`) throughout ‘`configure.in`’:

```
AC_INIT
AC_PROG_CC
__MAGIC__
MY_SUSPECT_MACRO
__MAGIC__
AC_OUTPUT(Makefile)
```

After `autoconf` has generated ‘`configure`’, you can search through it for the magic text to determine the extremities of the suspect macro. If your erroneous code appears within the magic text markers, you’ve found the culprit! Don’t be afraid to hack up ‘`configure`’. It can easily be regenerated.

Finally, due to an error on your part, `m4` may generate a ‘`configure`’ script that contains semantic errors. Something as simple as inverted logic may lead to a nonsense test result:

```
checking for /etc/passwd... no
```

Semantic errors of this kind are usually easy to solve once you can spot them. A fast and simple way of tracing the shell execution is to use the shell’s ‘`-x`’ and ‘`-v`’ options to turn on its own tracing. This can be done by explicitly placing the required `set` commands into ‘`configure.in`’:

```
AC_INIT
```

```
AC_PROG_CC
set -x -v
MY_BROKEN_MACRO
set +x +v
AC_OUTPUT(Makefile)
```

This kind of tracing is invaluable in debugging shell code containing semantic errors.



## 22 Writing Portable Bourne Shell

This chapter is a whistle stop tour of the accumulated wisdom of the free software community, with respect to best practices for portable shell scripting, as encoded in the sources for Autoconf and Libtool, as interpreted and filtered by me. It is by no means comprehensive – entire books have been devoted to the subject – though it is, I hope, authoritative.

### 22.1 Why Use the Bourne Shell?

Unix has been around for more than thirty years and has splintered into hundreds of small and not so small variants, See [Section 2.1 \[Unix Diversity\]](#), [page 9](#). Much of the subject matter of this book is concerned with how best to approach writing programs which will work on as many of these variants as possible. One of the few programming tools that is absolutely guaranteed to be present on every flavour of Unix in use today is Steve Bourne's original shell, **sh** – the Bourne Shell. That is why Libtool is written as a Bourne Shell script, and why the **configure** files generated by Autoconf are Bourne Shell scripts: they can be executed on all known Unix flavours, and as a bonus on most POSIX based non-Unix operating systems too.

However, there are complications. Over the years, OS vendors have improved Steve Bourne's original shell or have reimplemented it in an almost, but not quite, compatible way. There also a great number of Bourne compatible shells which are often used as a system's default `‘/bin/sh’`: **ash**, **bash**, **bsh**, **ksh**, **sh5** and **zsh** are some that you may come across. For the rest of this chapter, when I say ‘shell’, I mean a Bourne compatible shell.

This leads us to the black art known as *portable shell programming*, the art of writing a single script which will run correctly through all of these varying implementations of `‘/bin/sh’`. Of course, Unix systems are constantly evolving and new variations are being introduced all the time (and very old systems which have fallen into disuse can perhaps be ignored by the pragmatic). The amount of system knowledge required to write a truly portable shell script is vast, and a great deal of the information that sets a precedent for a given idiom is necessarily second or third (or tenth) hand. Practically, this means that some of the knowledge accumulated in popular portable shell scripts is very probably folklore – but that doesn't really matter too much, the important thing is that if you adhere to these idioms, you shouldn't have any problems from people who can't run your program on their system.

### 22.2 Implementation

By their very nature, a sizeable part of the functionality of shell scripts, is provided by the many utility programs that they routinely call to perform important subsidiary tasks. Addressing the portability of the script involves issues of portability in the host operating system environment, and portability of the utility programs as well as the portability of the shell implementation itself.

This section discusses differences between shell implementations to which you must cater when writing a portable script. It is broken into several subsections, each covering a single aspect of shell programming that needs to be approached carefully to avoid pitfalls with

unexpected behaviour in some shell implementations. The following section discusses how to cope with the host environment in a portable fashion. The last section in this chapter addresses the portability of common shell utilities.

### 22.2.1 Size Limitations

Quite a lot of the Unix vendor implementations of the Bourne shell have a fixed buffer for storing command lines, as small as 512 characters in the worst cases. You may have an error akin to this:

```
$ ls -d /usr/bin/* | wc -l
sh: error: line too long
```

Notice that the limit applies to the *expanded* command line, not just the characters typed in for the line. A portable way to write this would be:

```
$ ( cd /usr/bin && ls | wc -l )
1556
```

### 22.2.2 #!

When the kernel executes a program from the file system, it checks the first few bytes of the file, and compares them with its internal list of known *magic numbers*, which encode how the file can be executed. This is a similar, but distinct, system to the `/etc/magic` magic number list used by user space programs.

Having determined that the file is a script by examining its magic number, the kernel finds the path of the interpreter by removing the `#!` and any intervening space from the first line of the script. One optional argument is allowed (additional arguments are not ignored, they constitute a syntax error), and the resulting command line is executed. There is a 32 character limit to the significant part of the `#!` line, so you must ensure that the full path to the interpreter plus any switches you need to pass to it do not exceed this limit. Also, the interpreter must be a real binary program, it cannot be a `#!` file itself.

It used to be thought, that the semantics between different kernels' idea of the magic number for the start of an interpreted script varied slightly between implementations. In actual fact, all look for `#!` in the first two bytes – in spite of commonly held beliefs, there is no evidence that there are others which require `#! /`.

A portable script must give an absolute path to the interpreter, which causes problems when, say, some machines have a better version of Bourne shell in an unusual directory – say `/usr/sysv/bin/sh`. See [Section 22.2.4 \[Functions\], page 242](#) for a way to re-execute the script with a better interpreter.

For example, imagine a script file called `/tmp/foo.pl` with the following first line:

```
#! /usr/local/bin/perl
```

Now, the script can be executed from the `tmp` directory, with the following sequence of commands:

```
$ cd /tmp
$ ./foo.pl
```

When executing these commands, the kernel will actually execute the following from the `tmp` directory:

```
/usr/local/bin/perl ./foo.pl
```

This can pose problems of its own though. A script such as the one described above will not work on a machine where the perl interpreter is installed as `/usr/bin/perl`. There is a way to circumvent this problem, by using the `env` program to find the interpreter by looking in the user's `PATH` environment variable. Change the first line of the `foo.pl` to read as follows:

```
#!/usr/bin/env perl
```

This idiom does rely on the `env` command being installed as `/usr/bin/env`, and that, in this example, `perl` can be found in the user's `PATH`. But that is indeed the case on the great majority of machines. In contrast, `perl` is installed in `usr/local/bin` as often as `/usr/bin`, so using `env` like this is a net win overall. You can also use this method to get around the 32 character limit if the path to the interpreter is too long.

Unfortunately, you lose the ability to pass an option flag to the interpreter if you choose to use `env`. For example, you can't do the following, since it requires two arguments:

```
#!/usr/bin/env guile -s
```

### 22.2.3 :

In the beginning, the magic number for Bourne shell scripts used to be a colon followed by a newline. Most Unices still support this, and will correctly pass a file with a single colon as its first line to `/bin/sh` for interpretation. Nobody uses this any more and I suspect some very new Unices may have forgotten about it entirely, so you should stick to the more usual `#!/bin/sh` syntax for your own scripts. You may occasionally come across a very old script that starts with a `:'` though, and it is nice to know why!

In addition, all known Bourne compatible shells have a builtin command, `:` which always returns success. It is equivalent to the system command `/bin/true`, but can be used from a script without the overhead of starting another process. When setting a shell variable as a flag, it is good practice to use the commands, `:` and `false` as values, and choose the sense of the variable to be `:` in the common case: When you come to test the value of the variable, you will avoid the overhead of additional processes most of the time.

```
var=:
if $var; then
    foo
fi
```

The `:` command described above can take any number of arguments, which it will fastidiously ignore. This allows the `:'` character to double up as a comment leader of sorts. Be aware that the characters that follow are not discarded, they are still interpreted by the shell, so metacharacters can have unexpected effects:

```
$ cat foo
:
: echo foo
: 'echo bar'
: 'echo baz >&2'
$ ./foo
baz
```

You may find very old shell scripts that are commented using `:`, or new scripts that exploit this behavior in some esoteric fashion. My advice is, don't: It will bite you later.

#### 22.2.4 ()

There are still a great number of shells that, like Steve Bourne's original implementation, do not have functions! So, strictly speaking, you can't use shell functions in your scripts. Luckily, in this day and age, even though `/bin/sh` itself may not support shell functions, it is not too far from the truth to say that almost every machine will have *some* shell that does.

Taking this assumption to its logical conclusion, it is a simple matter of writing your script to find a suitable shell, and then feed itself to that shell so that the rest of the script can use functions with impunity:

```
#!/bin/sh

# Zsh is not Bourne compatible without the following:
if test -n "$ZSH_VERSION"; then
    emulate sh
    NULLCMD=:
fi

# Bash is not POSIX compliant without the following:
test -n "$BASH_VERSION" && set -o posix

SHELL="${SHELL-/bin/sh}"
if test x"$1" = x--re-executed; then
    # Functional shell was found. Remove option and continue
    shift
elif "$SHELL" -c 'foo () { exit 0; }; foo' 2>/dev/null; then
    # The current shell works already!
    :
else
    # Try alternative shells that (sometimes) support functions
    for cmd in sh bash ash bsh ksh zsh sh5; do
        set IFS=:; X="$PATH:/bin:/usr/bin:/usr/afsws/bin:/usr/ucb"; echo $X
        for dir
            shell="$dir/$cmd"
            if (test -f "$shell" || test -f "$shell.exe") &&
                "$shell" -c 'foo () { exit 0; }; foo 2>/dev/null
            then
                # Re-execute with discovered functional shell
                SHELL="$shell" exec "$shell" "$0" --re-executed ${1+"$@"}
            fi
        done
    done
    echo "Unable to locate a shell interpreter with function support" >&2
    exit 1
fi
```

```

foo () {
    echo "$SHELL: ta da!"
}

foo

exit 0

```

Note that this script finds a shell that supports functions of the following syntax, since the use of the `function` keyword is much less widely supported:

```
foo () { ... }
```

A notable exception to the assertion that all machines have a shell that can handle functions is 4.3BSD, which has only a single shell: a shell function deprived Bourne shell. There are two ways you can deal with this:

1. Ask 4.3BSD users of your script to install a more featureful shell such as `bash`, so that the technique above will work.
2. Have your script run itself through `sed`, chopping itself into pieces, with each function written to it's own script file, and then feed what's left into the original shell. Whenever a function call is encountered, one of the fragments from the original script will be executed in a subshell.

If you decide to split the script with `sed`, you will need to be careful not to rely on shell variables to communicate between functions, since each 'function' will be executed in its own subshell.

### 22.2.5 .

The semantics of `'.'` are rather peculiar to say the least. Here is a simple script – it just displays its positional parameters:

```

#!/bin/sh
echo "$0" ${1+"$@"}

```

Put this in a file, `'foo'`. Here is another simple script – it calls the first script. Put this in another file, `'wrapper'`:

```

#!/bin/sh
. ./foo
. ./foo bar baz

```

Observe what happens when you run this from the command line:

```

$ ./wrapper
./wrapper
./wrapper bar baz

```

So `'$0'` is inherited from the calling script, and the positional parameters are as passed to the command. Observe what happens when you call the wrapper script with arguments:

```

$ ./wrapper 1 2 3
./wrapper 1 2 3
./wrapper bar baz

```

So the sourced script has access to the calling scripts positional parameters, *unless you override them in the `'.'` command*.

This can cause no end of trouble if you are not expecting it, so you must either be careful to omit all parameters to any `.'` command, or else don't reference the parameters inside the sourced script. If you are reexecuting your script with a shell that understands functions, the best use for the `.'` command is to load libraries of functions which can subsequently be used in the calling script.

Most importantly, don't forget that, if you call the `exit` command in a script that you load with `.'`, it will cause the calling script to exit too!

## 22.2.6 [

Although technically equivalent, `test` is preferable to `[` in shell code written in conjunction with Autoconf, since `[` is also used for M4 quoting in Autoconf. Your code will be much easier to read (and write) if you abstain from the use of `[`.

Except in the most degenerate shells, `test` is a shell builtin to save the overhead of starting another process, and is no slower than `[`. It does mean, however, that there is a huge range of features which are not implemented often enough that you can use them freely within a truly portable script. The less obvious ones to avoid are `-a` and `-o` – the logical 'and' and 'or' operations. A good litmus test for the portability of any shell feature is to see whether that feature is used in the source of Autoconf, and it turns out that `-a` and `-o` are used here and there, but never more than once in a single command. All the same, to avoid any confusion, I always avoid them entirely. I would not use the following, for example:

```
test foo -a bar
```

Instead I would run `test` twice, like this:

```
test foo && test bar
```

The negation operator of `test` is quite portable and can be used in portable shell scripts. For example:

```
if test ! foo; then bar; fi
```

The negation operator of `if` is not at all portable and should be avoided. The following would generate a syntax error on some shell implementations:

```
if ! test foo; then bar; fi
```

An implication of this axiom is that when you need to branch if a command fails, and that command is not `test`, you cannot use the negation operator. The easiest way to work around this is to use the `'else'` clause of the un-negated `if`, like this:

```
if foo; then ;; else bar; fi
```

Notice the use of the `:` builtin as a null operation when `foo` doesn't fail.

The `test` command does not cope with missing or additional arguments, so you must take care to ensure that the shell does not remove arguments or introduce new ones during variable and quote expansions. The best way to do that is to enclose any variables in double quotes. You should also add a single character prefix to both sides in case the value of the expansion is a valid option to `test`:

```
$ for foo in "" "!" "bar" "baz quux"; do
>   test x"$foo" = x"bar" && echo 1 || echo 0
> done
```

```
0
0
1
0
```

Here, you can see that using the ‘x’ prefix for the first operand saves **test** from interpreting the ‘!’ argument as a real option, or from choking on an empty string – something you must always be aware of, or else the following behaviour will ensue:

```
$ foo=!
$ test "$foo" = "bar" && echo 1 || echo 0
test: argument expected
0
$ foo=""
$ test "$foo" = "bar" && echo 1 || echo 0
test: argument expected
0
```

Also, the double quote marks help **test** cope with strings that contain whitespace. Without the double quotes, you will see this errors:

```
$ foo="baz quux"
$ test x$foo = "bar" && echo 1 || echo 0
test: too many arguments
0
```

You shouldn’t rely on the default behaviour of **test** (to return ‘true’ if its single argument has non-zero length), use the ‘-n’ option to force that behaviour if it is what you want. Beyond that, the other thing you need to know about **test**, is that if you use operators other than those below, you are reducing the portability of your code:

‘-n’ *string* *string* is non-empty.

‘-z’ *string* *string* is empty.

*string1* = *string2*  
Both strings are identical.

*string1* != *string2*  
The strings are not the same.

‘-d’ *file* *file* exists and is a directory.

‘-f’ *file* *file* exists and is a regular file.

You can also use the following, provided that you don’t mix them within a single invocation of **test**:

*expression* ‘-a’ *expression*  
Both expressions evaluate to ‘true’.

*expression* ‘-o’ *expression*  
Neither expression evaluates to ‘false’.

### 22.2.7 \$

When using shell variables in your portable scripts, you need to write them in a somewhat stylised fashion to maximise the number of shell implementations that will interpret your code as expected:

- Convenient though it is, the POSIX ‘\$(command parameters)’ syntax for command substitution is not remotely portable. Despite it being more difficult to nest, you must use ‘`command parameters`’ instead.
- The most portable way to set a default value for a shell variable is:

```
$ echo ${no_such_var-"default value"}
default value
```

If there is any whitespace in the default value, as there is here, you must be careful to quote the entire value, since some shells will raise an error:

```
$ echo ${no_such_var-default value}
sh: bad substitution
```

- The `unset` command is not available in many of the degenerate Bourne shell implementations. Generally, it is not too difficult to get by without it, but following the logic that led to the shell script in [Section 22.2.4 \[Functions\]](#), page 242, it would be trivial to extend the test case for confirming a shell’s suitability to include a check for `unset`. Although it has not been put to the test, the theory is that all the interesting machines in use today have *some* shell that supports `unset`.
- Be religious about double quoting variable expansions. Using ‘“\$foo”’ will avoid trouble with unexpected spaces in filenames, and compression of all whitespace to a single space in unquoted variable expansions.
- To avoid accidental interpretation of variable expansions as command options you can use the following technique:

```
$ foo=-n
$ echo $foo
$ echo x"$foo" | sed -e 's/^x//'
-n
```

- If it is set, `IFS` splits words on whitespace by default. If you change it, be sure to put it back when you’re done, or the shell may behave very strangely from that point. For example, when you need to examine each element of ‘\$PATH’ in turn:

```
# The whitespace at the end of the following line is a space
# followed by literal tab and newline characters.
save_IFS="${IFS=
}"; IFS=":"
set dummy $PATH
IFS="$save_IFS"
shift
```

Alternatively, you can take advantage of the fact that command substitutions occur in a separate subshell, and do not corrupt the environment of the calling shell:

```
set dummy `IFS=:; echo $PATH`
```



`shift`

Strictly speaking, the ‘dummy’ argument is required to stop the `set` command from interpreting the first word of the expanded backquote expression as a command option. Realistically, no one is going to have ‘-x’, for example, as the first element of their ‘PATH’ variable, so the ‘dummy’ could be omitted – as I did earlier in the script in [Section 22.2.4 \[Functions\]](#), page 242.

- Some shells expand ‘\$@’ to the empty string, even when there are no actual parameters (‘\$#’ is 0). If you need to replicate the parameters that were passed to the executing script, when feeding the script to a more suitable interpreter for example, you must use the following:

```
${1+"$@"}
```

Similarly, although all known shells do correctly use ‘\$@’ as the default argument to a `for` command, you must write it like this:

```
for arg
do
    stuff
done
```

When you rely on implicit ‘\$@’ like this, it is important to write the `do` keyword on a separate line. Some degenerate shells can not parse the following:

```
for arg; do
    stuff
done
```

### 22.2.8 \* versus .\*

This section compares *file globbing* with *regular expression matching*. There are many Unix commands which are regularly used from shell scripts, and which provide some sort of pattern matching mechanism: `expr`, `egrep` and `sed`, to name a few. Unfortunately they each have different quoting rules regarding whether particular meta-characters must be backslash escaped to revert to their literal meaning and vice-versa. There is no real logic to the particular dialect of regular expressions accepted by these commands. To confirm the correctness of each regular expression, you should always check them from the shell prompt with the relevant tool before committing to a script, so I won’t belabour the specifics.

Shell globbing however is much more regular (no pun intended), and provides a reasonable and sometimes more cpu efficient solution to many shell matching problems. The key is to make good use of the `case` command, which is easier to use (because it uses globbing rules) and doesn’t require additional processes to be spawned. Unfortunately, GNU Bash doesn’t handle backslashes correctly in glob character classes – the backslash must be the first character in the class, or else it will never match. For example, if you want to detect absolute directory paths on Unix and Windows using `case`, you should write the code like this:

```
case $dir in
    [\\/*]* | ?:[\\/*]* ) echo absolute ;;
    * ) echo relative ;;
esac
```

Even though `expr` uses regular expressions rather than shell globbing, it is often<sup>1</sup> a shell builtin, so using it to extract sections of strings can be faster than spawning a `sed` process to do the same. As with `echo` and `set`, for example, you must be careful that variable or command expansions for the first argument to `expr` are not accidentally interpreted as reserved keywords. As with `echo`, you can work around this problem by prefixing any expansions with a literal `'x'`, as follows:

```
$ foo=substr
$ expr $foo : '.*\ (str\)'
expr: syntax error
$ expr x$foo : '.*\ (str\)'
str
```

## 22.3 Environment

In addition to the problems with portability in shell implementations discussed in the previous section, the behaviour of the shell can also be drastically affected by the contents of certain environment variables, and the operating environment provided by the host machine.

It is important to be aware of the behavior of some of the operating systems within which your shell script might run. Although not directly related to the implementation of the shell interpreter, the characteristics of some of target architectures do influence what is considered to be portable. To ensure your script will work on as many shell implementations as possible, you must observe the following points.

SCO Unix doesn't like `LANG=C` and friends, but without `LC_MESSAGES=C`, Solaris will translate variable values in `set`! Similarly, without `LC_CTYPE=C`, compiled C code can behave unexpectedly. The trick is to set the values to `'C'`, except for if they are not already set at all:

```
for var in LANG LC_ALL LC_MESSAGES LC_CTYPE LANGUAGES
do
  if eval test x"${${var}+set}" = xset; then
    eval $var=C; eval export $var
  fi
done
```

HP-UX `ksh` and all POSIX shells print the target directory to standard output if `'CDPATH'` is set.

```
if test x"${CDPATH+set}" = xset; then CDPATH=.; export CDPATH; fi
```

The target architecture file system may impose limits on your scripts. IF you want your scripts to run on the architectures which impose these limits, then your script must adhere to these limits:

- The ISO9660 filesystem, as used on most CD-ROMs, limits nesting of directories to a maximum depth of twelve levels.
- Many old Unix filesystems place a 14 character limit on the length of any filename. If you care about portability to DOS, *that* has an 8 character limit with an optional extension of 3 or fewer characters (known as 8.3 notation).

---

<sup>1</sup> Notable exceptions are GNU Bash, and both Ksh and the Bourne shell on Solaris.

A useful idiom when you need to determine whether a particular pathname is relative or absolute, which works for DOS targets to follows:

```
case "$file" in
  [\\/* | ?:[\\/*]*) echo absolute ;;
  *)                echo default ;;
esac
```

## 22.4 Utilities

The utility programs commonly executed by shell scripts can have a huge impact on the portability of shell scripts, and it is important to know which utilities are universally available, and any differences certain implementations of these utilities may exhibit. According to the GNU standards document, you can rely on having access to these utilities from your scripts:

```
cat cmp cp diff echo egrep expr false grep install-info
ln ls mkdir mv pwd rm rmdir sed sleep sort tar test touch true
```

Here are some things that you must be aware of when using some of the tools listed above:

**cat** Host architectures supply **cat** implementations with conflicting interpretations of, or entirely missing, the various command line options. You should avoid using any command line options to this command.

**cp and mv** Unconditionally duplicated or otherwise open file descriptors can not be deleted on many operating systems, and worse on Windows the destination files cannot even be moved. Constructs like this must be avoided, for example.

```
exec > foo
mv foo bar
```

**echo** The **echo** command has at least two flavors: the one takes a **-n** option to suppress the automatic newline at the end of the echoed string; the other uses an embedded **\c** notation as the last character in the echoed string for the same purpose.

If you need to emit a string without a trailing newline character, you can use the following script fragment to discover which flavor of **echo** you are using:

```
case echo "testing\c" '','echo -n testing' in
  *c*,-n*) echo_n= echo_c=''2
  ' ;;
  *c*,*)   echo_n=-n echo_c= ;;
  *)      echo_n= echo_c='\c' ;;
esac
```

Any **echo** command after the shell fragment above, which shouldn't move the cursor to a new line, can now be written like so:

```
echo $echo_n "prompt:$echo_c"
```

---

<sup>2</sup> This is a literal newline.

In addition, you should try to avoid backslashes in `echo` arguments unless they are expanded by the shell. Some implementations interpret them and effectively perform another backslash expansion pass, where equally many implementations do not. This can become a really hairy problem if you need to have an `echo` command which doesn't perform backslash expansion, and in fact the first 150 lines of the `ltconfig` script distributed with Libtool are devoted to finding such a command.

**ln** Not all systems support soft links. You should use the Autoconf macro `'AC_PROG_LN_S'` to discover what the target architecture supports, and assign the result of that test to a variable. Whenever you subsequently need to create a link you can use the command stored in the variable to do so.

```
LN_S=@LN_S@
...
$LN_S $top_srcdir/foo $dist_dir/foo
```

Also, you cannot rely on support for the `'-f'` option from all implementations of `ln`. Use `rm` before calling `ln` instead.

**mkdir** Unfortunately, `'mkdir -p'` is not as portable as we might like. You must either create each directory in the path in turn, or use the `mkinstalldirs` script supplied by Automake.

**sed** When you resort to using `sed` (rather, use `case` or `expr` if you can), there is no need to introduce command line scripts using the `'-e'` option. Even when you want to supply more than one script, you can use `';`' as a command separator. The following two lines are equivalent, though the latter is cleaner:

```
$ sed -e 's/foo/bar/g -e '12q' < infile > outfile
$ sed 's/foo/bar/g;12q' < infile > outfile
```

Some portability zealots still go to great lengths to avoid *here documents* of more than twelve lines. The twelve line limit is actually a limitation in some implementations of `sed`, which has gradually seeped into the portable shell folklore as a general limit in all here documents. Autoconf, however, includes many here documents with far more than twelve lines, and has not generated any complaints from users. This is testament to the fact that at worst the limit is only encountered in very obscure cases – and most likely that it is not a real limit after all.

Also, be aware that branch labels of more than eight characters are not portable to some implementations of `sed`.

*Here documents* are a way of redirecting literal strings into the standard input of a command. You have certainly seen them before if you have looked at other peoples shell scripts, though you may not have realised what they were called:

```
cat >> /tmp/file$$ << _EOF_
This is the text of a "here document"
_EOF_
```

Something else to be aware of is that the temporary files created by your scripts can become a security problem if they are left in `'/tmp'` or if the names are predictable. A simple way around this is to create a directory in `'/tmp'` that is unique to the process and owned

by the process user. Some machines have a utility program for just this purpose – `mktemp -d` – or else you can always fall back to `umask 077 && mkdir /tmp/$$`. Having created this directory, all of the temporary files for this process should be written to that directory, and its contents removed as soon as possible.

Armed with the knowledge of how to write shell code in a portable fashion as discussed in this chapter, in combination with the M4 details from the last chapter, the specifics of combining the two to write your own Autoconf macros are covered in the next chapter.



## 23 Writing New Macros for Autoconf

Autoconf is an extensible system which permits new macros to be written and shared between Autoconf users. Although it is possible to perform custom tests by placing fragments of shell code into your `configure.in` file, it is better practice to encapsulate that test in a macro. This encourages macro authors to make their macros more general purpose, easier to test and easier to share with other users.

This chapter presents some guidelines for designing and implementing good Autoconf macros. It will conclude with a discussion of the approaches being considered by the Autoconf development community for improving the creation and distribution of macros. A more general discussion of macros can be found in [Section 21.3.2 \[Macros and macro expansion\]](#), page 229.

### 23.1 Autoconf Preliminaries

In a small package which only uses Autoconf, your own macros are placed in the `aclocal.m4` file—this includes macros that you may have obtained from third parties such as the Autoconf macro archive (see [Section 23.5.1 \[Autoconf macro archive\]](#), page 258). If your package additionally uses Automake, then these macros should be placed in `acinclude.m4`. The `aclocal` program from Automake reads in macro definitions from `acinclude.m4` when generating `aclocal.m4`. When using Automake, for instance, `aclocal.m4` will include the definitions of `AM_` macros needed by Automake.

In larger projects, it's advisable to keep your custom macros in a more organized structure. Autoconf version 2.15 will introduce a new facility to explicitly include files from your `configure.in` file. The details have not solidified yet, but it will almost certainly include a mechanism for automatically included files with the correct filename extension from a subdirectory, say `m4/`.

### 23.2 Reusing Existing Macros

It goes without saying that it makes sense to reuse macros where possible—indeed, a search of the Autoconf macro archive might turn up a macro which does exactly what you want, alleviating the need to write a macro at all (see [Section 23.5.1 \[Autoconf macro archive\]](#), page 258).

It's more likely, though, that there will be generic, parameterized tests available that you can use to help you get your job done. Autoconf's 'generic' tests provide one such collection of macros. A macro that wants to test for support of a new language keyword, for example, should rely on the `AC_TRY_COMPILE` macro. This macro can be used to attempt to compile a small program and detect a failure due to, say, a syntax error.

In any case, it is good practice when reusing macros to adhere to their publicized interface—do not rely on implementation details such as shell variables used to record the test's result unless this is explicitly mentioned as part of the macro's behavior. Macros in the Autoconf core can, and do, change their implementation from time to time.

Reusing a macro does not imply that the macro is necessarily invoked from within the definition of your macro. Sometimes you might just want to rely on some action performed

by a macro earlier in the configuration run—this is still a form of reuse. In these cases, it is necessary to ensure that this macro has indeed run at least once before your macro is invoked. It is possible to state such a dependency by invoking the `AC_REQUIRE` macro at the beginning of your macro's definition.

Should you need to write a macro from scratch, the following sections will provide guidelines for writing better macros.

## 23.3 Guidelines for writing macros

There are some guidelines which should be followed when writing a macro. The criteria for a well-written macro are that it should be easy to use, well documented and, most importantly, portable. Portability is a difficult problem that requires much anticipation on the part of the macro writer. This section will discuss the design considerations for using a static Autoconf test at compile time versus a test at runtime. It will also cover some of the characteristics of a good macro including non-interactive behavior, properly formatted output and a clean interface for the user of the macro.

### 23.3.1 Non-interactive behavior

Autoconf's generated `'configure'` scripts are designed to be non-interactive – they should not prompt the user for input. Many users like the fact that `'configure'` can be used as part of a automated build process. By introducing code into `'configure'` which prompts a user for more information, you will prohibit unattended operation. Instead, you should use the `AC_ARG_ENABLE` macro in `'configure.in'` to add extra options to `'configure'` or consider runtime configuration (see [Section 23.3.2 \[Testing system features at application runtime\]](#), page 254).

### 23.3.2 Testing system features at application runtime

When pondering how to handle a difficult portability problem or configurable option, consider whether the problem is better solved by performing tests at runtime or by providing a configuration file to customize the application. Keep in mind that the results of tests that Autoconf can perform will ultimately affect how the program will be built—and can limit the number of machines that the program can be moved to without recompiling it. Here is an example where this consideration had to be made in a real life project:

The pthreads for Win32 project has sought to provide a standards compliant implementation for the POSIX threads API. It does so by mapping the POSIX API functions into small functions which achieve the desired result using the Win32 thread API. Windows 95, Windows 98 and Windows NT have different levels of support for a system call primitive that attempts to enter a critical section without blocking. The `TryEnterCriticalSection` function is missing on Windows 95, is an inoperative stub on Windows 98, and works as expected on Windows NT. If this behavior was to be checked by `'configure'` at compile time, then the resultant library would only work on the variant of Windows that it was compiled for. Because it's more common to distribute packages for Windows in binary form, this would be an unfortunate situation. Instead, it is sometimes preferable to handle this kind of portability problem with a test, performed by your code at runtime.



### 23.3.3 Output from macros

Users who run ‘`configure`’ expect a certain style of output as tests are performed. As such, you should use the well-defined interface to the existing Autoconf macros for generating output. Your tests should not arbitrarily echo messages to the standard output.

Autoconf provides the following macros to output the messages for you in a consistent way (see [Chapter 3 \[Invoking `configure`\]](#), page 17). They are introduced here with a brief description of their purpose and are documented in more detail in [Appendix D \[Autoconf Macro Reference\]](#), page 317. Typically, a test starts by invoking `AC_MSG_CHECKING` to describe to the user what the test is doing and `AC_MSG_RESULT` is invoked to output the result of the test.

‘`AC_MSG_CHECKING`’

This macro is used to notify the user that a test is commencing. It prints the text ‘`checking`’ followed by your message and ends with ‘`...`’. You should use ‘`AC_MSG_RESULT`’ after this macro to output the result of the test.

‘`AC_MSG_RESULT`’

This macro notifies the user of a test result. In general, the result should be the word ‘`yes`’ or ‘`no`’ for boolean tests, or the actual value of the result, such as a directory or filename.

‘`AC_MSG_ERROR`’

This macro emits a hard error message and aborts ‘`configure`’—this should be used for fatal errors.

‘`AC_MSG_WARN`’

This macro emits a warning to the user and proceeds.

### 23.3.4 Naming macros

Just like functions in a C program, it’s important to choose a good name for your Autoconf macros. A well-chosen name helps to unambiguously describe the purpose of the macro. Macros in M4 are all named within a single namespace and, thus, it is necessary to follow a convention to ensure that names retain uniqueness. This reasoning goes beyond just avoiding collisions with other macros—if you happen to choose a name that is already known to M4 as a definition of any kind, your macro’s name could be rewritten by the prior definition during macro processing.

One naming convention has emerged—prefixing each macro name with the name of the package that the macro originated in or the initials of the macro’s author. Macros are usually named in a hierarchical fashion, with each part of the name separated by underscores. As you move left-to-right through each component of the name, the description becomes more detailed. There are some high-level categories of macros suggested by the Autoconf manual that you may wish to use when forming a descriptive name for your own macro. For example, if your macro tries to discover the existence of a particular C structure, you might wish to use `C` and `STRUCT` as components of its name.

‘`C`’            Tests related to constructs of the C programming language.

‘`DECL`’        Tests for variable declarations in header files.

<code>'FUNC'</code>	Tests for functions present in (or absent from) libraries.
<code>'HEADER'</code>	Tests for header files.
<code>'LIB'</code>	Tests for libraries.
<code>'PATH'</code>	Tests to discover absolute filenames (especially programs).
<code>'PROG'</code>	Tests to determine the base names of programs.
<code>'STRUCT'</code>	Tests for definitions of C structures in header files.
<code>'SYS'</code>	Tests for operating system features, such as restartable system calls.
<code>'TYPE'</code>	Tests for built-in or declared C data types.
<code>'VAR'</code>	Tests for C variables in libraries.

Some examples of macro names formed in this way include:

<code>'AC_PROG_CC'</code>	A test that looks for a program called <code>cc</code> .
<code>'AC_C_INLINE'</code>	A test that discovers if the C keyword <code>inline</code> is recognized.
<code>'bje_CXX_MUTABLE'</code>	A test, written by "bje", that discovers if the C++ keyword <code>mutable</code> is recognized.

### 23.3.5 Macro interface

When designing your macro, it is worth spending some time deciding on what your macro's interface—the macro's name and argument list—will be. Often, it will be possible to extract general purpose functionality into a generic macro and to write a second macro which is a client of the generic one. Like planning the prototype for a C function, this is usually a straightforward process of deciding what arguments are required by the macro to perform its function. However, there are a couple of further considerations and they are discussed below.

M4 macros refer to their arguments by number with a syntax such as `$1`. It is typically more difficult to read an M4 macro definition and understand what each argument's designation is than in a C function body, where the formal argument is referred to by its name. Therefore, it's a good idea to include a standard comment block above each macro that documents the macro and gives an indication of what each argument is for. Here is an example from the Autoconf source code:

```
# AC_CHECK_FILE(FILE, [ACTION-IF-FOUND], [ACTION-IF-NOT-FOUND])
# -----
#
# Check for the existence of FILE.
```

To remain general purpose, the existing Autoconf macros follow the convention of keeping side-effects outside the definition of the macro. Here, when a user invokes `'AC_CHECK_FILE'`, they must provide shell code to implement the side effect that they want to occur if the `'FILE'` is found or is not found. Some macros implement a basic and desirable action like

defining a symbol like `'HAVE_UNISTD_H'` if no user-defined actions are provided. In general, your macros should provide an interface which is consistent with the interfaces provided by the core Autoconf macros.

M4 macros may have variable argument lists, so it is possible to implement macros which have defaults for arguments. By testing each individual argument against the empty string with `'ifelse'`, it is possible for users to accept the default behavior for individual arguments by passing empty values:

```
AC_CHECK_FILE([/etc/passwd], [],
              [AC_MSG_ERROR([something is really wrong])])
```

One final point to consider when designing the interface for a macro is how to handle macros that are generic in nature and, say, wish to set a cache variable whose name is based on one of the arguments. Consider the `'AC_CHECK_HEADER'` macro—it defines a symbol and makes an entry in the cache that reflects the result of the test it performs. `'AC_CHECK_HEADER'` takes an argument – namely the name of a header file to look for. This macro cannot just make a cache entry with a name like `ac_cv_check_header`, since it would only work once; any further uses of this macro in `'configure.in'` would cause an incorrect result to be drawn from the cache. Instead, the name of the symbol that is defined and the name of the cache variable that is set need to be computed from one of the arguments: the name of the header file being sought. What we really need is to define `HAVE_UNISTD_H` and set the cache variable `ac_cv_header_unistd_h`. This can be achieved with some `sed` and `tr` magic in the macro which transforms the filename into uppercase characters for the call to `AC_DEFINE` and into lowercase for the cache variable name. Unknown characters such as `'.'` need to be transformed into underscores.

Some existing macros also allow the user to pass in the name of a cache variable name so that the macro does not need to compute a name. In general, this should be avoided, as it makes the macro harder to use and exposes details of the caching system to the user.

## 23.4 Implementation specifics

This section provides some tips about how to actually go about writing your macros once you've decided what it is that you want to test and how to go about testing for it. It covers writing shell code for the test and optionally caching the results of those tests.

### 23.4.1 Writing shell code

It is necessary to adopt a technique of writing portable Bourne shell code. Often, shell programming tricks you might have learned are actually extensions provided by your favorite shell and are non-portable. When in doubt, check documentation or try the construct on another system's Bourne shell. For a thorough treatment of this topic, [Chapter 22 \[Writing Portable Bourne Shell\]](#), page 239.

### 23.4.2 Using M4 correctly

Writing macros involves interacting with the M4 macro processor, which expands your macros when they are used in `'configure.in'`. It is crucial that your macros use M4 correctly—and in particular, that they quote strings correctly. [Chapter 21 \[M4\]](#), page 227 for a thorough treatment of this topic.

### 23.4.3 Caching results

Autoconf provides a caching facility, whereby the results of a test may be stored in a cache file. The cache file is itself a Bourne shell script which is sourced by the ‘configure’ script to set any ‘cache variables’ to values that are present in the cache file.

The next time ‘configure’ is run, the cache will be consulted for a prior result. If there is a prior result, the value is re-used and the code that performs that test is skipped. This speeds up subsequent runs of ‘configure’ and configuration of deep trees, which can share a cache file in the top-level directory (see [Chapter 3 \[Invoking configure\]](#), page 17).

A custom macro is not required to do caching, though it is considered best practice. Sometimes it doesn’t make sense for a macro to do caching—tests for system aspects which may frequently change should not be cached. For example, a test for free disk space should not employ caching as it is a dynamic characteristic.

The ‘AC\_CACHE\_CHECK’ macro is a convenient wrapper for caching the results of tests. You simply provide a description of the test, the name of a cache variable to store the test result to, and the body of the test. If the test has not been run before, the cache will be primed with the result. If the result is already in the cache, then the cache variable will be set and the test will be skipped. Note that the name of the cache variable must contain ‘\_cv\_’ in order to be saved correctly.

Here is the code for an Autoconf macro that ties together many of the concepts introduced in this chapter:

```
# AC_PROG_CC_G
# -----
AC_DEFUN([AC_PROG_CC_G],
[AC_CACHE_CHECK([whether ${CC-cc} accepts -g, ac_cv_prog_cc_g,
[echo 'void f(){}' > conftest.c
if test -z "${CC-cc} -g -c conftest.c 2>&1"; then
    ac_cv_prog_cc_g=yes
else
    ac_cv_prog_cc_g=no
fi
rm -f conftest*
]]) # AC_PROG_CC_G
```

## 23.5 Future directions for macro writers

A future trend for Autoconf is to make it easier to write reliable macros and re-use macros written by others. This section will describe some of the ideas that are currently being explored by those actively working on Autoconf.

### 23.5.1 Autoconf macro archive

In mid-1999, an official Autoconf macro archive was established on the World Wide Web by Peter Simons in Germany. The archive collects useful Autoconf macros that might be useful to some users, but are not sufficiently general purpose to include in the core Autoconf distribution. The URL for the macro archive is:

<http://www.gnu.org/software/ac-archive/>

It is possible to retrieve macros that perform different kinds of tests from this archive. The macros can then be inserted, in line, into your ‘`aclocal.m4`’ or ‘`acinclude.m4`’ file. The archive has been steadily growing since its inception. Please try and submit your macros to the archive!

### 23.5.2 Primitive macros to aid in building macros

Writing new macros is one aspect of Autoconf that has proven troublesome to users in the past, since this is one area where Autoconf’s implementation details leak out. Autoconf extensively uses `m4` to perform the translation of ‘`configure.in`’ to ‘`configure`’. Thus, it is necessary to understand implementation details such as `M4`s quoting rules in order to write Autoconf macros (Chapter 21 [M4], page 227).

Another aspect of macro writing which is extremely hard to get right is writing portable Bourne shell scripts (see Chapter 22 [Writing Portable Bourne Shell], page 239). Writing portable software, be it in Bourne shell or C++, is something that can only be mastered with years of experience—and exposure to many different kinds of machines! Rather than expect all macro writers to acquire this experience, it makes sense for Autoconf to become a ‘knowledge base’ for this experience.

With this in mind, one future direction for Autoconf will be to provide a library of low-level macros to assist in writing new macros. By way of hypothetical example, consider the benefit of using a macro named `AC_FOREACH` instead of needing to learn the hard way that some vendor’s implementation of Bourne shell has a broken `for` loop construct. This idea will be explored in future versions of Autoconf.

When migrating existing packages to the GNU Autotools, which is the topic of the next chapter, it is worth remembering these guidelines for best practices as you write the necessary tests to make those packages portable.



## 24 Migrating an Existing Package to GNU Autotools

Sometimes you have to take an existing package and wrap it in an Autoconf framework. This is called *autoconfiscating*<sup>1</sup> a package.

This chapter gives an overview of various approach that have been taken when autoconfiscating, explains some important points through examples, and discusses some of potential pitfalls. It is not an exhaustive guide to autoconfiscation, as this process is much more art than it is science.

### 24.1 Why autconfiscate

There are a few reasons to autoconfiscate a package. You might be porting your package to a new platform for the first time, or your might have outstripped the capabilities of an ad hoc system. Or, you might be assuming maintenance of a package and you want to make it fit in with other packages that use the GNU Autotools.

For instance, for libgcj, we wanted to distribute some libraries needed for proper operation, such as the zip archiving program and the Boehm garbage collector. In neither case was an autoconf framework available. However, we felt one was required in order to give the overall package a seamless and easy-to-use configuration and build system. This attention to ease of install by users is important; it is one reason that the GNU Autotools were written.

In another case, a group I worked with was taking over maintenance of a preexisting package. We preferred an Autoconf-based solution to the home-grown one already in use by the package – the existing system was based on platform tests, not feature tests, and was difficult to navigate and extend.

### 24.2 Overview of the Two Approaches

The two fundamental approaches to autoconfiscation, which we call ‘quick and dirty’, and ‘the full pull’. In practice each project is a mix of the two.

There are no hard-and-fast rules when autoconfiscating an existing package, particularly when you are planning to track future releases of the original source. However, since Autoconf is so flexible, it is usually possible to find some reasonable way to implement whatever is required. Automake isn’t as flexible, and with ‘strangely’ constructed packages you’re sometimes required to make a difficult choice: restructure the package, or avoid automake.

#### 1. Quick And Dirty.

In the quick and dirty approach, the goal is to get the framework up and running with the least effort. This is the approach we took when we autoconfiscated both zip and the Boehm garbage collector. Our reasons were simple: we knew we would be tracking the original packages closely, so we wanted to minimize the amount of work involved in importing the next release and subsequently merging in our changes. Also, both packages were written to be portable (but in very different ways), so major modifications to the source were not required.

---

<sup>1</sup> A term coined by Noah Friedman in the early days of Autoconf to denote the process of converting a package that configures itself without Autoconf to one which does.

## 2. The Full Pull.

Sometimes you'd rather completely convert a package to GNU Autotools. For instance, you might have just assumed maintenance of a package. Or, you might read this book and decide that your company's internal projects should use a state-of-the-art configuration system.

The full pull is more work than the quick-and-dirty approach, but in the end it yields a more easily understood, and more idiomatic package. This in turn has maintenance benefits due to the relative absence of quirks, traps, and special cases – oddities which creep into quick and dirty ports due to the need, in that case, to structure the build system around the package instead of having the ability to restructure the package to fit the build system.

## 24.3 Example: Quick And Dirty

As part of the `libgcj` project<sup>2</sup>, I had to incorporate the `zip` program into our source tree. Since this particular program is only used in one part of the build, and since this program was already fairly portable, I decided to take a quick-and-dirty approach to autoconfiscation.

First I read through the 'README' and 'install.doc' files to see how `zip` is ordinarily built. From there I learned that `zip` came with a 'Makefile' used to build all Unix ports (and, for the initial autoconfiscation, Unix was all I was interested in), so I read that. This file indicated that `zip` had few configurability options.

Running `ifnames` on the sources, both Unix and generic, confirmed that the `zip` sources were mostly self-configuring, using system-specific '#defines'—a practice which we recommend against; however for a quicky-and-dirty port it is not worth cleaning up:

```
$ ifnames *. [ch] unix/*. [ch] | grep ^__ | head
__386BSD__  unix/unix.c
__CYGWIN32__  unix/osdep.h
__CYGWIN__   unix/osdep.h
__DATE__    unix/unix.c zipcloak.c zipnote.c zipsplit.c
__DEBUG__   zip.c
__ELF__     unix/unix.c
__EMX__     fileio.c ttyio.h util.c zip.c
__FreeBSD__  unix/unix.c
__G         ttyio.h
__GNUC__    unix/unix.c zipcloak.c zipnote.c zipsplit.c
```

Based on this information I wrote my initial 'configure.in', which is the one still in use today:

```
AC_INIT(ziperr.h)
AM_INIT_AUTOMAKE(zip, 2.1)
AM_MAINTAINER_MODE

AC_PROG_CC
```

---

<sup>2</sup> See <http://sourceware.cygnum.com/java/>



```

AC_HEADER_DIRENT
AC_DEFINE(UNIX)

AC_LINK_FILES(unix/unix.c, unix.c)

AC_OUTPUT(Makefile)

```

The one mysterious part of this ‘`configure.in`’ is the define of the ‘`UNIX`’ preprocessor macro. This define came directly from `zip`’s ‘`unix/Makefile`’ file; `zip` uses this define to enable certain Unix-specific pieces of code.

In this particular situation, I lucked out. `zip` was unusually easy to autoconfigure. Typically more actual checks are required in ‘`configure.in`’, and more than a single iteration is required to get a workable configuration system.

From ‘`unix/Makefile`’ I also learned which files were expected to be built in order to produce the `zip` executable. This information let me write my ‘`Makefile.am`’:

```

## Process this file with automake to create Makefile.in.

## NOTE: this file doesn't really try to be complete. In particular
## 'make dist' won't work at all. We're just aiming to get the
## program built. We also don't bother trying to assemble code, or
## anything like that.

AUTOMAKE_OPTIONS = no-dependencies

INCLUDES = -I$(srcdir)/unix

bin_PROGRAMS = zip

zip_SOURCES = zip.c zipfile.c zipup.c fileio.c util.c globals.c \
    crypt.c ttyio.c unix.c crc32.c crctab.c deflate.c trees.c bits.c

## This isn't really correct, but we don't care.
$(zip_OBJECTS) : zip.h ziperr.h tailor.h unix/osdep.h crypt.h \
    revision.h ttyio.h unix/zipup.h

```

This file provides a good look at some of the tradeoffs involved. In my case, I didn’t care about full correctness of the resulting ‘`Makefile.am`’ – I wasn’t planning to maintain the project, I just wanted it to build in my particular set of environments.

So, I sacrificed ‘`dist`’ capability to make my work easier. Also, I decided to disable dependency tracking and instead make all the resulting object files depend on all the headers in the project. This approach is inefficient, but in my situation perfectly reasonable, as I wasn’t planning to do any actual development on this package – I was simply looking to make it build so that it could be used to build the parts of the package I was actually hacking.

## 24.4 Example: The Full Pull

Suppose instead that I wanted to fully autoconfiscate `zip`. Let's ignore for now that `zip` can build on systems to which the GNU Autotools have not been ported, like TOPS-20—perhaps a big problem back in the real world.

The first step should always be to run `autoscan`. `autoscan` is a program which examines your source code and then generates a file called `'configure.scan'` which can be used as a rough draft of a `'configure.in'`. `autoscan` isn't perfect, and in fact in some situations can generate a `'configure.scan'` which `autoconf` won't directly accept, so you should examine this file by hand before renaming it to `'configure.in'`.

`autoscan` doesn't take into account macro names used by your program. For instance, if `autoscan` decides to generate a check for `'<fcntl.h>'`, it will just generate ordinary `autoconf` code which in turn might define `'HAVE_FCNTL_H'` at `configure` time. This just means that `autoscan` isn't a panacea – you will probably have to modify your source to take advantage of the code that `autoscan` generates.

Here is the `'configure.scan'` I get when I run `autoscan` on `zip`:

```

dnl Process this file with autoconf to produce a configure script.
AC_INIT(bits.c)

dnl Checks for programs.
AC_PROG_AWK
AC_PROG_CC
AC_PROG_CPP
AC_PROG_INSTALL
AC_PROG_LN_S
AC_PROG_MAKE_SET

dnl Checks for libraries.
dnl Replace 'main' with a function in -lx:
AC_CHECK_LIB(x, main)

dnl Checks for header files.
AC_HEADER_DIRENT
AC_HEADER_STDC
AC_CHECK_HEADERS(fcntl.h malloc.h sgtty.h strings.h sys/ioctl.h \
termio.h unistd.h)

dnl Checks for typedefs, structures, and compiler characteristics.
AC_C_CONST
AC_TYPE_SIZE_T
AC_STRUCT_ST_BLKSIZE
AC_STRUCT_ST_BLOCKS
AC_STRUCT_ST_RDEV
AC_STRUCT_TM

dnl Checks for library functions.
AC_PROG_GCC_TRADITIONAL
AC_FUNC_MEMCMP

```

```
AC_FUNC_MMAP
AC_FUNC_SETVBUF_REVERSED
AC_TYPE_SIGNAL
AC_FUNC_UTIME_NULL
AC_CHECK_FUNCS(getcwd mktime regcomp rmdir strstr)
```

```
AC_OUTPUT(acorn/makefile unix/Makefile Makefile atari/Makefile)
```

As you can see, this isn't suitable for immediate use as 'configure.in'. For instance, it generates several 'Makefile's which we know we won't need. At this point there are two things to do in order to fix this file.

First, we must fix outright flaws in 'configure.scan', add checks for libraries, and the like. For instance, we might also add code to see if we are building on Windows and set a variable appropriately:

```
AC_CANONICAL_HOST
case "$target" in
  *-cygwin* | *-mingw*)
    INCLUDES='-I$(srcdir)/win32'
    ;;
  *)
    # Assume Unix.
    INCLUDES='-I$(srcdir)/unix'
    ;;
esac
AC_SUBST(INCLUDES)
```

Second, we must make sure that the zip sources use the results we compute. So, for instance, we would check the zip source to see if we should use 'HAVE\_MMAP', which is the result of calling AC\_FUNC\_MMAP.

At this point you might also consider using a configuration header such as is generated by AC\_CONFIG\_HEADER. Typically this involves editing all your source files to include the header, but in the long run this is probably a cleaner way to go than using many -D options on the command line. If you are making major source changes in order to fully adapt your code to autoconf's output, adding a '#include' to each file will not be difficult.

This step can be quite difficult if done thoroughly, as it can involve radical changes to the source. After this you will have a minimal but functional 'configure.in' and a knowledge of what portability information your program has already incorporated.

Next, you want to write your 'Makefile.am's. This might involve restructuring your package so that it can more easily conform to what Automake expects. This work might also involve source code changes if the program makes assumptions about the layout of the install tree – these assumptions might very well break if you follow the GNU rules about the install layout.

At the same time as you are writing your 'Makefile.am's, you might consider *libtoolizing* your package. This makes sense if you want to export shared libraries, or if you have libraries which several executables in your package use.

In our example, since there is no library involved, we won't use Libtool. The 'Makefile.am' used in the minimal example is nearly sufficient for our use, but not quite. Here's how we change it to add dependency tracking and dist support:

```

## Process this file with automake to create Makefile.in.

bin_PROGRAMS = zip

if UNIX
bin_SCRIPTS = unix/zipgrep
os_sources = unix/unix.c
else
os_sources = win32/win32.c win32zip.c
endif
zip_SOURCES = zip.c zipfile.c zipup.c fileio.c util.c globals.c \
              crypt.c ttyio.c crc32.c crctab.c deflate.c trees.c \
              bits.c $(os_sources)

## It was easier to just list all the source files than to pick out the
## non-source files.
EXTRA_DIST = algorithm.doc README TODO Where crc_i386.S bits.c crc32.c \
acorn/RunMe1st acorn/ReadMe acorn/acornzip.c acorn/makefile \
acorn/match.s acorn/osdep.h acorn/riscos.c acorn/riscos.h \
acorn/sendbits.s acorn/swiven.h acorn/swiven.s acorn/zipup.h crctab.c \
crypt.c crypt.h deflate.c ebcdic.h fileio.c globals.c history \
...
wizdll/wizdll.def wizdll/wizmain.c wizdll/wizzip.h wizdll/zipdll16.mak \
wizdll/zipdll32.mak

```

The extremely long ‘EXTRA\_DIST’ macro above has been truncated for brevity, denoted by the ‘...’ line.

Note that we no longer define `INCLUDES` – it is now automatically defined by `configure`. Note also that, due to a small technicality, this ‘`Makefile.am`’ won’t really work with Automake 1.4. Instead, we must modify things so that we don’t try to compile ‘`unix/unix.c`’ or other files from subdirectories.

## 25 Using GNU Autotools with Cygnus Cygwin

It is possible to use the GNU Autotools to build software packages on Windows. Since the tools were developed on Unix, it is easier to get them to work using Cygnus Solutions' Cygwin distribution which provides a POSIX wrapper for the Win32 API, See [Section 2.1 \[The Diversity of Unix Systems\]](#), page 9, but it is certainly possible to run the tools within other Windows environments, notably Colin Peters' *Mingw32* and D.J. Delorie's DJGPP. These development environments are freely available on the Internet<sup>1</sup>. Unlike Cygwin, these other environments are designed for developing with the Win32 API directly and consequently they are not as useful for porting Unix projects to Windows or writing code that works on both Windows and Unix, see [Section 15.3 \[Unix/Windows Portability\]](#), page 155 for more details. This chapter describes the process of using GNU Autotools with Cygwin, although some of this advice also applies to employing some of the other GNU based Windows development environments.

It is notable that the recent Cygwin ports of GCC and *binutils* can produce binaries which will run with the 'cygwin1.dll' emulation layer, or linked against 'CRTDLL.DLL', the Windows native **C RunTime Dynamic Link Library** depending on the needs of particular source code. Recent versions<sup>2</sup> of the *binutils* implement the PE-COFF binary format used by Windows, so by specifying the '-mno-cygwin' compiler option to the Cygwin compiler and using only the API from 'CRTDLL.DLL', you can build binaries which are independent of the 'cygwin1.dll' DLL. Such binaries will generally run faster, since they bypass the POSIX emulation, and give easier access to Windows specific things such as drive letters. Source code designed to be compiled this way will not compile on Unix however, since it will be limited to the Win32 API provided by 'CRTDLL.DLL'.

After reading this chapter, you will be able to install and use GNU Autotools *natively* under Windows using Cygnus Solutions' Cygwin environment, both to develop your own packages with the aid of Cygwin, and to compile, install, and to a certain degree port other peoples packages for use with Cygwin. As a Unix package developer, you will learn how to write your configury to be Windows friendly, and to be aware of certain quirks of Windows which can affect the portability of packages which need to work on Windows in addition to your Unix development machine.

### 25.1 Preliminaries

As explained in [Section 25.2 \[Installing GNU Autotools on Cygwin\]](#), page 268, GNU Autotools requires several other tools to operate. Most Unices provide the majority, if not all, of these prerequisites by default. Windows, unfortunately, does not. Cygwin is better than most in this respect, and only a few extras are required. The latest net release of Cygwin<sup>3</sup> has a packaging mechanism which downloads and installs various Unix tools that have been precompiled for the Cygwin environment by the Cygnus folks. To develop with

<sup>1</sup> Mingw32 home page, <http://www.geocities.com/Tokyo/Towers/6162/gcc.html>; and DJGPP home page, <http://www.delorie.com/djgpp/>.

<sup>2</sup> since Cygwin-b20.1, I believe.

<sup>3</sup> 1.1.1 at the time of writing.

GNU Autotools and Cygwin, you need to install all of these packages to make sure you have all of the necessary header files and compiler tools.

Bourne shell

Cygwin provides a port of *ash* which is smaller and faster than *bash*, but sometimes rejects arcane Bourne shell scripts. If you can stand to sacrifice a little speed, it is worth copying the supplied `bash.exe` to `‘/bin/sh.exe’` to forestall any such problems.

GNU M4     Cygwin provides a port of GNU M4.

GNU Make     At the time of writing, developers need GNU Make in order to do dependency tracking (see [Chapter 19 \[Automatic dependency tracking\]](#), page 205), though this is set to change in a future release of Automake. Cygwin version 1.1.1 comes with a port of GNU `make-3.77`, which I have personally never had any problems with. The received wisdom from users is to manually upgrade to the latest version, `make-3.79`<sup>4</sup>, which compiles and installs from source without modification. Should you experience (or anticipate) any Make related problems, you might try upgrading to this version or later.

GNU GCC     At the time of writing, GNU GCC is also needed by Automake in order to do dependency tracking. Cygwin version 1.1.1 comes with a port of the latest GNU GCC compiler.

Perl     The current implementation of Automake (1.4) is written in `perl4`, though it is likely that `perl5` will be needed for Automake 1.5. The very latest versions of Perl now compile out of the box on Cygwin<sup>5</sup>.

There are some other pitfalls to installing a fully working Cygwin environment on your Windows machine, but that is outside the scope of this chapter. Cygnus host a mailing list archive and an FAQ<sup>6</sup> to provide some level of support, and these should be your first port of call in case the installation does not go according to plan.

## 25.2 Installing GNU Autotools on Cygwin

With all of the above infrastructure in place, each of the GNU Autotools can be built natively and installed from source right out of the box. It is worth taking care with the installation directories, as there is no package management under Cygwin, and it is easy to let everything get thrown into a big pile in `‘/usr/local’`, which makes it relatively difficult to upgrade and remove packages.

Support for Cygwin has been in Autoconf for several years, as far back as version 2.0 as best as I can tell. Building it has never been a problem as long as GNU M4 and a Bourne Shell are available, it is the macros themselves which offer this support. Of course, any Autoconf macros you write yourself must be designed carefully to not make any assumptions about being executed on Unix if the Cygwin compatibility is to remain. A binary package of Autoconf for Cygwin version 1.1.1 is available from the CygUtils website<sup>7</sup>.

<sup>4</sup> <ftp://ftp.gnu.org/gnu/make/make-3.79.tar.gz>

<sup>5</sup> You can get a precompiled package from <http://cygutils.netpedia.net/>, also an excellent resource for other packages ported to Cygwin.

<sup>6</sup> <http://sourceware.cygnus.com/cygwin/>

<sup>7</sup> The CygUtils website is <http://cygutils.netpedia.net/V1.1/>.

Automake joined the fray much later than the Cygwin support code was added to Autoconf, and has consequently always supported Cygwin. Until the last release of Cygwin, the stumbling block has always been finding (or building) a Cygwin compatible Perl interpreter for Automake to use. Thanks to the work of Eric Fifer, Perl 5.6.0 builds right out of the box on Cygwin, removing this problem entirely. Ready built packages of Perl and Automake are available from the CygUtils website.

The initial Libtool support for Windows was written by Ian Lance Taylor of Cygnus Solutions, when Cygwin was at release b18, See [Section 2.6 \[Microsoft Windows\]](#), page 12. More recent releases of Cygwin in general, and GCC in particular have much better facilities for building and linking with Windows DLLs, to the extent that with a little perseverance it is possible to build DLLs with GCC from C++ sources, and to have those DLLs interoperate with DLLs built with Windows development environments. In time, automation of these facilities will make their way into Libtool. The method that Libtool currently uses to build DLLs works with Cygwin releases at least as far back as b18, and at least as far forward as the version I am now using, Cygwin-1.1.1. The same code will also build DLLs correctly with Mingw32. There are certainly simpler ways to assemble a DLL, but Libtool aims to combine two goals which are somewhat in contention with Windows' treatment of DLLs; Libtool is aiming for maximum portability across the various flavours of DLL-using Windows build environments; not forgetting Libtool's *raison d'être* which is to abstract the many and varied ways of building libraries on different targets behind a single unified interface. To meet these two goals, Libtool must only use tools which exist across the range of versions it supports, and must at the same time try to make DLLs appear to have the same characteristics as a modern ELF shared library, such as the shared libraries under GNU/Linux. This is no mean feat, and in fact Libtool still has some way to go in order to be able to do this convincingly. It turns out that Windows DLLs lack many, many features that packages developed on Unix are likely to take for granted. Emulation of these missing features are making their way into Libtool. Although support for DLLs is improving steadily with every release, there are some severe technical problems with the Windows library architecture that will prevent Libtool from ever being able to build DLLs completely transparently. The details are extremely technical and beyond the scope of this book.

As noted in [Section A.3 \[Installing the tools\]](#), page 304, things will only work correctly if each of Autoconf, Automake and Libtool are installed with the same '`--prefix`' argument, since they all share a macro directory in '`$prefix/share/aclocal`'.

## 25.3 Writing A Cygwin Friendly Package

One approach to using the Cygwin support offered by GNU Autotools in your own package is to have an eye towards having it compile nicely on Unix and on Windows, or indeed of tweaking the configuration of existing packages which use GNU Autotools but which do not compile under Cygwin, or do not behave quite right after compilation. There are several things you need to be aware of in order to design a package to work seamlessly under Cygwin, and yet several more if portability to DOS and (non-Cygwin) Windows is important too. We discussed many of these issues in [Section 15.3.5 \[Unix/Windows Issues\]](#), page 157. In this section, we will expand on those issues with ways in which GNU Autotools can help deal with them.



If you only need to build executables and static libraries, then Cygwin provides an environment close enough to Unix that any packages which ship with a relatively recent configuration will compile pretty much out of the box, except for a few peculiarities of Windows which are discussed throughout the rest of this section. If you want to build a package which has not been maintained for a while, and which consequently uses an old Autoconf, then it is usually just a matter of removing the generated files, rebootstraping the package with the installed (up to date!) Autoconf, and rerunning the ‘`configure`’ script. On occasion some tweaks will be needed in the ‘`configure.in`’ to satisfy the newer `autoconf`, but `autoconf` will almost always diagnose these for you while it is being run.

### 25.3.1 Text vs Binary Modes

As discussed in [Section 15.3.5.1 \[Unix/Windows Text/Binary\]](#), page 157, text and binary files are different on Windows. Lines in a Windows text files end in a carriage return/line feed pair, but a C program reading the file in text mode will see a single line feed.

Cygwin has several ways to hide this dichotomy, and the solution(s) you choose will depend on how you plan to use your program. I will outline the relative tradeoffs you make with each choice:

mounting Before installing an operating system to your hard drive, you must first organise the disk into *partitions*. Under Windows, you might only have a single partition on the disk, which would be called ‘C:’<sup>8</sup>. Provided that some media is present, Windows allows you to access the contents of any drive letter – that is you can access ‘A:’ when there is a floppy disk in the drive, and ‘F:’ provided you divided you available drives into sufficient partitions for that letter to be in use. With Unix, things are somewhat different: hard disks are still divided into partitions (typically several), but there is only a single filesystem *mounted* under the root directory. You can use the `mount` command to hook a partition (or floppy drive or CD-ROM, etc.) into a subdirectory of the root filesystem:

```
$ mount /dev/fd0 /mnt/floppy
$ cd /mnt/floppy
```

Until the directory is *unmounted*, the contents of the floppy disk will be available as part of the single Unix filesystem in the directory, ‘`/mnt/floppy`’. This is in contrast with Windows’ multiple root directories which can be accessed by changing filesystem root – to access the contents of a floppy disk:

```
C:\WINDOWS\> A:
A:> DIR
...
```

Cygwin has a mounting facility to allow Cygwin applications to see a single unified file system starting at the root directory, by *mounting* drive letters to subdirectories. When mounting a directory you can set a flag to determine whether the files in that partition should be treated the same whether they are TEXT or BINARY mode files. Mounting a file system to treat TEXT files the same as BINARY files, means that Cygwin programs can behave in the same way as they might on Unix and treat all files as equal. Mounting a file system to treat

---

<sup>8</sup> Typically you would also have a floppy drive named ‘A:’, and a CD-ROM named ‘D:’.



TEXT files properly, will cause Cygwin programs to translate between Windows CR-LF line end sequences and Unix CR line endings, which plays havoc with file seeking, and many programs which make assumptions about the size of a `char` in a `FILE` stream. However ‘binmode’ is the default method because it is the only way to interoperate between Windows binaries and Cygwin binaries. You can get a list of which drive letters are mounted to which directories, and the modes they are mounted with by running the `mount` command without arguments:

```
BASH.EXE-2.04$ mount
Device                Directory            Type      flags
C:\cygwin             /                    user      binmode
C:\cygwin\bin         /usr/bin            user      binmode
C:\cygwin\lib         /usr/lib            user      binmode
D:\home               /home               user      binmode
```

As you can see, the Cygwin `mount` command allows you to ‘mount’ arbitrary Windows directories as well as simple drive letters into the single filesystem seen by Cygwin applications.

**binmode** The `CYGWIN` environment variable holds a space separated list of setup options which exert some minor control over the way the ‘`cygwin1.dll`’ (or ‘`cygwinb19.dll`’ etc.) behaves. One such option is the ‘binmode’ setting; if `CYGWIN` contains the ‘binmode’ option, files which are opened through ‘`cygwin1.dll`’ without an explicit text or binary mode, will default to binary mode which is closest to how Unix behaves.

**system calls**

‘`cygwin1.dll`’, GNU `libc` and other modern C API implementations accept extra flags for `fopen` and `open` calls to determine in which mode a file is opened. On Unix it makes no difference, and sadly most Unix programmers are not aware of this subtlety, so this tends to be the first thing that needs to be fixed when porting a Unix program to Cygwin. The best way to use these calls portably is to use the following macros with a package’s ‘`configure.in`’ to be sure that the extra arguments are available:

```
# _AB_AC_FUNC_FOPEN(b | t, USE_FOPEN_BINARY | USE_FOPEN_TEXT)
# -----
define([_AB_AC_FUNC_FOPEN],
[AC_CACHE_CHECK([whether fopen accepts "$1" mode], [ab_cv_func_fopen_$1],
[AC_TRY_RUN([#include <stdio.h>
int
main ()
{
FILE *fp = fopen ("conftest.bin", "w$1");
fprintf (fp, "\n");
fclose (fp);
return 0;
}],
[ab_cv_func_fopen_$1=yes],
[ab_cv_func_fopen_$1=no],
[ab_cv_func_fopen_$1=no])])
```

```

if test x$ab_cv_func_fopen_$1 = xyes; then
  AC_DEFINE([$2], 1,
    [Define this if we can use the "$1" mode for fopen safely.])
fi[]dnl
])# _AB_AC_FUNC_FOPEN

# AB_AC_FUNC_FOPEN_BINARY
# -----
# Test whether fopen accepts a "b" in the mode string for binary file
# opening. This makes no difference on most unices, but some OSes
# convert every newline written to a file to two bytes (CR LF), and
# every CR LF read from a file is silently converted to a newline.
AC_DEFUN([AB_AC_FUNC_FOPEN_BINARY], [_AB_AC_FUNC_FOPEN(b, USE_FOPEN_BINARY)])

# AB_AC_FUNC_FOPEN_TEXT
# -----
# Test whether open accepts a "t" in the mode string for text file
# opening. This makes no difference on most unices, but other OSes
# use it to assert that every newline written to a file writes two
# bytes (CR LF), and every CR LF read from a file are silently
# converted to a newline.
AC_DEFUN([AB_AC_FUNC_FOPEN_TEXT], [_AB_AC_FUNC_FOPEN(t, USE_FOPEN_TEXT)])

# _AB_AC_FUNC_OPEN(O_BINARY|O_TEXT)
# -----
AC_DEFUN([_AB_AC_FUNC_OPEN],
[AC_CACHE_CHECK([whether fcntl.h defines $1], [ab_cv_header_fcntl_h_$1],
[AC_EGREP_CPP([$1],
    [#include <sys/types.h>
#include <sys/stat.h>
#include <fcntl.h>
$1
],
    [ab_cv_header_fcntl_h_$1=no],
    [ab_cv_header_fcntl_h_$1=yes])
if test "x$ab_cv_header_fcntl_h_$1" = xno; then
  AC_EGREP_CPP([_ $1],
    [#include <sys/types.h>
#include <sys/stat.h>
#include <fcntl.h>
_ $1
],
    [ab_cv_header_fcntl_h_$1=0],
    [ab_cv_header_fcntl_h_$1=_$1])
fi])
if test "x$ab_cv_header_fcntl_h_$1" != xyes; then
  AC_DEFINE_UNQUOTED([$1], [$ab_cv_header_fcntl_h_$1],
    [Define this to a usable value if the system provides none])

```

```

fi[]\n\
])# _AB_AC_FUNC_OPEN

# AB_AC_FUNC_OPEN_BINARY
# -----
# Test whether open accepts O_BINARY in the mode string for binary
# file opening. This makes no difference on most unices, but some
# OSes convert every newline written to a file to two bytes (CR LF),
# and every CR LF read from a file is silently converted to a newline.
#
AC_DEFUN([AB_AC_FUNC_OPEN_BINARY], [_AB_AC_FUNC_OPEN([O_BINARY]))]

# AB_AC_FUNC_OPEN_TEXT
# -----
# Test whether open accepts O_TEXT in the mode string for text file
# opening. This makes no difference on most unices, but other OSes
# use it to assert that every newline written to a file writes two
# bytes (CR LF), and every CR LF read from a file are silently
# converted to a newline.
#
AC_DEFUN([AB_AC_FUNC_OPEN_TEXT], [_AB_AC_FUNC_OPEN([O_TEXT]))]

```

Add the following preprocessor code to a common header file that will be included by any sources that use `fopen` calls:

```
#define fopen rpl_fopen
```

Save the following function to a file, and link that into your program so that in combination with the preprocessor magic above, you can always specify text or binary mode to `open` and `fopen`, and let this code take care of removing the flags on machines which do not support them:

```

#if HAVE_CONFIG_H
# include <config.h>
#endif

#include <stdio.h>

/* Use the system size_t if it has one, or fallback to config.h */
#if STDC_HEADERS || HAVE_STDDEF_H
# include <stddef.h>
#endif
#if HAVE_SYS_TYPES_H
# include <sys/types.h>
#endif

/* One of the following headers will have prototypes for malloc
   and free on most systems. If not, we don't add explicit

```

```

    prototypes which may generate a compiler warning in some
    cases -- explicit prototypes would certainly cause
    compilation to fail with a type clash on some platforms. */
#if STDC_HEADERS || HAVE_STDLIB_H
# include <stdlib.h>
#endif
#if HAVE_MEMORY_H
# include <memory.h>
#endif

#if HAVE_STRING_H
# include <string.h>
#else
# if HAVE_STRINGS_H
#   include <strings.h>
# endif /* !HAVE_STRINGS_H */
#endif /* !HAVE_STRING_H */

#if ! HAVE_STRCHR

/* BSD based systems have index() instead of strchr() */
# if HAVE_INDEX
#   define strchr index
# else /* ! HAVE_INDEX */

/* Very old C libraries have neither index() or strchr() */
#   define strchr rpl_strchr

static inline const char *strchr (const char *str, int ch);

static inline const char *
strchr (const char *str, int ch)
{
    const char *p = str;
    while (p && *p && *p != (char) ch)
    {
        ++p;
    }

    return (*p == (char) ch) ? p : 0;
}
# endif /* HAVE_INDEX */

#endif /* HAVE_STRCHR */

/* BSD based systems have bcopy() instead of strcpy() */
#if ! HAVE_STRCPY
# define strcpy(dest, src)      bcopy(src, dest, strlen(src) + 1)
#endif

```

```

/* Very old C libraries have no strdup(). */
#if ! HAVE_STRDUP
# define strdup(str)          strcpy(malloc(strlen(str) + 1), str)
#endif

char*
rpl_fopen (const char *pathname, char *mode)
{
    char *result = NULL;
    char *p = mode;

    /* Scan to the end of mode until we find 'b' or 't'. */
    while (*p && *p != 'b' && *p != 't')
    {
        ++p;
    }

    if (!*p)
    {
        fprintf(stderr,
            "*WARNING* rpl_fopen called without mode 'b' or 't'\n");
    }

    #if USE_FOPEN_BINARY && USE_FOPEN_TEXT
        result = fopen(pathname, mode);
    #else
        {
            char ignore[3] = "bt";
            char *newmode = strdup(mode);
            char *q        = newmode;

            p = newmode;

            # if ! USE_FOPEN_TEXT
                strcpy(ignore, "b")
            # endif
            # if ! USE_FOPEN_BINARY
                strcpy(ignore, "t")
            # endif

            /* Copy characters from mode to newmode missing out
               b and/or t. */
            while (*p)
            {
                while (strchr(ignore, *p))
                {
                    ++p;
                }
            }
        }
    #endif
}

```

```

        *q++ = *p++;
    }
    *q = '\\0';

    result = fopen(pathname, newmode);

    free(newmode);
}
#endif /* USE_FOPEN_BINARY && USE_FOPEN_TEXT */

    return result;
}

```

The correct operation of the file above relies on several things having been checked by the `configure` script, so you will also need to ensure that the following macros are present in your `'configure.in'` before you use this code:

```

# configure.in -- Process this file with autoconf to produce configure
AC_INIT(rpl_fopen.c)

AC_PROG_CC
AC_HEADER_STDC
AC_CHECK_HEADERS(string.h strings.h, break)
AC_CHECK_HEADERS(stdlib.h stddef.h sys/types.h memory.h)

AC_C_CONST
AC_TYPE_SIZE_T

AC_CHECK_FUNCS(strchr index strcpy strdup)
AB_AC_FUNC_FOPEN_BINARY
AB_AC_FUNC_FOPEN_TEXT

```

## 25.3.2 File System Limitations

We discussed some differences between Unix and Windows file systems in [Section 15.3.5.2 \[Unix/Windows Filesystems\]](#), page 157. You learned about some of the differences between Unix and Windows file systems. This section expands on that discussion, covering filename differences and separator and drive letter distinctions.

### 25.3.2.1 8.3 Filenames

As discussed earlier, DOS file systems have severe restrictions on possible file names: they must follow an 8.3 format. See [Section 15.3.5.3 \[DOS Filename Restrictions\]](#), page 157.

This is quite a severe limitation, and affects some of the inner workings of GNU Autotools in two ways. The first is handled automatically, in that if `.libs` isn't a legal directory name on the host system, Libtool and Automake will use the directory `_libs` instead. The other is that the traditional `'config.h.in'` file is not legal under this scheme, and it must be worked around with a little known feature of Autoconf:

```
AC_CONFIG_HEADER(config.h:config.hin)
```

### 25.3.2.2 Separators and Drive Letters

As discussed earlier (see [Section 15.3.5.6 \[Windows Separators and Drive Letters\]](#), [page 158](#)), the Windows file systems use different delimiters for separating directories and path elements than their Unix cousins. There are three places where this has an effect:

the shell command line

Up until Cygwin b20.1, it was possible to refer to drive letter prefixed paths from the shell using the ‘//c/path/to/file’ syntax to refer to the directory root at ‘C:\path\to\file’. Unfortunately, the Windows kernel confused this with the its own network share notation, causing the shell to pause for a short while to look for a machine named ‘c’ in its network neighbourhood. Since release 1.0 of Cygwin, the ‘//c/path/to/file’ notation now really does refer to a machine named ‘c’ from Cygwin as well as from Windows. To refer to drive letter rooted paths on the local machine from Cygwin there is a new hybrid ‘c:/path/to/file’ notation. This notation also works in Cygwin b20, and is probably the system you should use.

On the other hand, using the new hybrid notation in shell scripts means that they won’t run on old Cygwin releases. Shell code embedded in ‘`configure.in`’ scripts, should test whether the hybrid notation works, and use an alternate macro to translate hybrid notation to the old style if necessary.

I must confess that from the command line I now use the longer ‘/cygdrive/c/path/to/file’ notation, since `<TAB>` completion doesn’t yet work for the newer hybrid notation. It is important to use the new notation in shell scripts however, or they will fail on the latest releases of Cygwin.

shell scripts

For a shell script to work correctly on non-Cygwin development environments, it needs to be aware of and handle Windows path and directory separator and drive letters. The Libtool scripts use the following idiom:

```
case "$path" in
# Accept absolute paths.
[\[/]* | [A-Za-\.]:[\\/]*)
    # take care of absolute paths
    insert some code here
    ;;
*)
    # what is left must be a relative path
    insert some code here
    ;;
esac
```

source code

When porting Unix software to Cygwin, this is much less of an issue because these differences are hidden beneath the emulation layer, and by the `mount` command respectively; although I have found that GCC, for example, returns

a mixed mode ‘/’ and ‘\’ delimited include path which upsets Automake’s dependency tracking on occasion.

Cygwin provides convenience functions to convert back and forth between the different notations, which we call *POSIX paths* or path lists, and *WIN32 paths* or path lists:

**int posix\_path\_list\_p** (const char \*path) Function  
 Return ‘0’, unless *path* is a ‘/’ and ‘:’ separated path list. The determination is rather simplistic, in that a string which contains a ‘;’ or begins with a single letter followed by a ‘:’ causes the ‘0’ return.

**void cygwin\_win32\_to\_posix\_path\_list** (const char \*win32, char \*posix) Function  
 Converts the ‘\’ and ‘;’ delimiters in *win32*, into the equivalent ‘/’ and ‘:’ delimiters while copying into the buffer at address *posix*. This buffer must be preallocated before calling the function.

**void cygwin\_conv\_to\_posix\_path** (const char \*path, char \*posix\_path) Function  
 If *path* is a ‘\’ delimited path, the equivalent, ‘/’ delimited path is written to the buffer at address *posix\_path*. This buffer must be preallocated before calling the function.

**void cygwin\_conv\_to\_full\_posix\_path** (const char \*path, char \*posix\_path) Function  
 If *path* is a, possibly relative, ‘\’ delimited path, the equivalent, absolute, ‘/’ delimited path is written to the buffer at address *posix\_path*. This buffer must be preallocated before calling the function.

**void cygwin\_posix\_to\_win32\_path\_list** (const char \*posix, char \*win32) Function  
 Converts the ‘/’ and ‘:’ delimiters in *posix*, into the equivalent ‘\’ and ‘;’ delimiters while copying into the buffer at address *win32*. This buffer must be preallocated before calling the function.

**void cygwin\_conv\_to\_win32\_path** (const char \*path, char \*win32\_path) Function  
 If *path* is a ‘/’ delimited path, the equivalent, ‘\’ delimited path is written to the buffer at address *win32\_path*. This buffer must be preallocated before calling the function.

**void cygwin\_conv\_to\_full\_win32\_path** (const char \*path, char \*win32\_path) Function  
 If *path* is a, possibly relative, ‘/’ delimited path, the equivalent, absolute, ‘\’ delimited path is written to the buffer at address *win32\_path*. This buffer must be preallocated before calling the function.



You can use these functions something like this:

```
void
display_canonical_path(const char *maybe_relative_or_win32)
{
    char buffer[MAX_PATH];
    cygwin_conv_to_full_posix_path(maybe_relative_or_win32,
                                   buffer);
    printf("canonical path for %s: %s\n",
           maybe_relative_or_win32, buffer);
}
```

For your code to be fully portable however, you cannot rely on these Cygwin functions as they are not implemented on Unix, or even mingw or DJGPP. Instead you should add the following to a shared header, and be careful to use it when processing and building paths and path lists:

```
#if defined __CYGWIN32__ && !defined __CYGWIN__
/* For backwards compatibility with Cygwin b19 and
   earlier, we define __CYGWIN__ here, so that
   we can rely on checking just for that macro. */
# define __CYGWIN__ __CYGWIN32__
#endif

#if defined _WIN32 && !defined __CYGWIN__
/* Use Windows separators on all _WIN32 defining
   environments, except Cygwin. */
# define DIR_SEPARATOR_CHAR '\\'
# define DIR_SEPARATOR_STR "\\"
# define PATH_SEPARATOR_CHAR ';'
# define PATH_SEPARATOR_STR ";"
#else
# define DIR_SEPARATOR_CHAR '/'
# define DIR_SEPARATOR_STR "/"
# define PATH_SEPARATOR_CHAR ':'
# define PATH_SEPARATOR_STR ":"
#endif /* !DIR_SEPARATOR_CHAR */
```

With this in place we can use the macros defined above to write code which will compile and work just about anywhere:

```
char path[MAXBUFLEN];
snprintf(path, MAXBUFLEN, "%ctmp%c%s\n",
          DIR_SEPARATOR_CHAR, DIR_SEPARATOR_CHAR, foo);
file = fopen(path, "tw+");
```

### 25.3.3 Executable Filename Extensions

As I already noted in [Section 25.5 \[Package Installation\]](#), page 290, the fact that Windows requires that all program files be named with the extension `.exe`, is the cause of several inconsistencies in package behaviour between Windows and Unix.

For example, where Libtool is involved, if a package builds an executable which is linked against an as yet uninstalled library, `libtool` puts the real executable in the `‘.libs’` (or `‘_libs’`) subdirectory, and writes a shell script to the original destination of the executable<sup>9</sup>, which ensures the runtime library search paths are adjusted to find the correct (uninstalled) libraries that it depends upon. On Windows, only a PE-COFF executable is allowed to bear the `.exe` extension, so the wrapper script has to be named differently to the executable it is substituted for (i.e the script is only executed correctly by the operating system if it does **not** have an `‘.exe’` extension). The result of this confusion is that the `‘Makefile’` can’t see some of the executables it builds with Libtool because the generated rules assume an `‘.exe’` extension will be in evidence. This problem will be addressed in some future revision of Automake and Libtool. In the mean time, it is sometimes necessary to move the executables from the `‘.libs’` directory to their install destination by hand. The continual rebuilding of wrapped executables at each invocation of `make` is another symptom of using wrapper scripts with a different name to the executable which they represent.

It is very important to correctly add the `‘.exe’` extension to program file names in your `‘Makefile.am’`, otherwise many of the generated rules will not work correctly while they await a file without the `‘.exe’` extension. Fortunately, Automake will do this for you where ever it is able to tell that a file is a program – everything listed in `‘bin_PROGRAMS’` for example. Occasionally you will find cases where there is no way for Automake to be sure of this, in which case you must be sure to add the `‘$(EXEEXT)’` suffix. By structuring your `‘Makefile.am’` carefully, this can be avoided in the majority of cases:

```
TESTS = $(check_SCRIPTS) script-test bin1-test$(EXEEXT)
```

could be rewritten as:

```
check_PROGRAMS = bin1-test
TESTS = $(check_SCRIPTS) script-test $(check_PROGRAMS)
```

The value of `‘EXEEXT’` is always set correctly with respect to the host machine if you use Libtool in your project. If you don’t use Libtool, you must manually call the Autoconf macro, `‘AC_EXEEXT’` in your `‘configure.in’` to make sure that it is initialised correctly. If you don’t call this macro (either directly or implicitly with `‘AC_PROG_LIBTOOL’`), your project will almost certainly not build correctly on Cygwin.

## 25.4 DLLs with Libtool

Windows’ DLLs, are very different to their nearest equivalent on Unix: shared libraries. This makes Libtool’s job of hiding both behind the same abstraction extremely difficult – it is not fully implemented at the time of writing. As a package author that wants to use DLLs on Windows with Libtool, you must construct your packages very carefully to enable them to build and link with DLLs in the same way that they build and link with shared libraries on Unix.

Some of the difficulties that must be addressed follow:

- At link time, a DLL effectively consists of two parts; the DLL itself which contains the shared object code, and an import library which consists of the *stub*<sup>10</sup> functions which

<sup>9</sup> See [Section 10.5 \[Executing Uninstalled Binaries\]](#), page 96.

<sup>10</sup> In general, a stub function will satisfy the linker’s requirements to resolve an undefined symbol at link time, but has no functionality of its own. In this context, the stubs do have some boilerplate code to pass execution flow into the correct full function in the DLL.

are actually linked into the executable, at a rate of one stub per entry point. Unix has a run time loader which links shared libraries into the main program as it is executed, so the shared library is but a single file.

- Pointer comparisons do not always work as expected when the pointers cross a DLL boundary, since you can be comparing the addresses of the stubs in the import library rather than the addresses of the actual objects in the DLL. GCC provides the `__declspec` extension to alleviate this problem a little.
- The search algorithm for the runtime library loader is very different to the algorithms typically used on Unix; I'll explain how to deal with this in [Section 25.4.5 \[Runtime Loading of DLLs\]](#), page 290.
- All of the symbols required by a DLL at runtime, must be resolved at link time. With some creative use of import libraries, it is usually possible to work around this shortcoming, but it is easy to forget this limitation if you are developing on a modern system which has lazy symbol resolution. Be sure to keep it at the back of your mind if you intend to have your package portable to Windows.
- Worst of all, is that it is impossible to reference a non-pointer item imported from a DLL. In practice, when you think you have exported a data item from a DLL, you are actually exporting its address (in fact the address of the address if you take the import library into consideration), and it is necessary to add an extra level of indirection to any non-pointers imported from a DLL to take this into account. The GNU gcc `__declspec` extension can handle this automatically too, at the expense of obfuscating your code a little.

Cygwin support in Libtool is very new, and is being developed very quickly, so newer versions generally improve vastly over their predecessors when it comes to Cygwin, so you should get the newest release you can. The rest of this section is correct with respect to Libtool version 1.3.5.

In some future version, Libtool might be able to work as transparently as Autoconf and Automake, but for now designing your packages as described in this chapter will help Libtool to help us have DLLs and Unix shared libraries from the same codebase.

The bottom line here is that setting a package up to build and use modules and libraries as both DLLs *and* Unix shared libraries is not straightforward, but the rest of this section provides a recipe which I have used successfully in several projects, including the module loader for GNU m4 1.5 which works correctly with DLLs on Windows. Lets create *hello world* as a DLL, and an executable where the runtime loader loads the DLL.

### 25.4.1 DLL Support with GNU Autotools

Here are the contents of the three source files used as an example for the remainder of this chapter (for brevity, they are missing most of the special code one would normally use to maximise portability):

`'hello.h'` documents the interface to `'libhello.dll'`:

```

#ifndef HELLO_H
#define HELLO_H 1

extern int hello (const char *who);

#endif /* !HELLO_H */

```

‘hello.c’ is the implementation of ‘libhello.dll’:

```

#if HAVE_CONFIG_H
# include <config.h>
#endif

#include <stdio.h>

#include "hello.h"

int
hello (const char *who)
{
    printf("Hello, %s!\n", who);
    return 0;
}

```

‘main.c’ is the source for the executable which uses ‘libhello.dll’:

```

#if HAVE_CONFIG_H
# include <config.h>
#endif

#include "hello.h"

int
main (int argc, const char *const argv[])
{
    return hello("World");
}

```

## 25.4.2 A Makefile.am for DLLs

First of all we will *autoconfiscate*<sup>11</sup> the source files above with a minimal setup:

‘Makefile.am’ is used to generate the ‘Makefile.in’ template for the ‘configure’ script:

---

<sup>11</sup> Some people prefer to use the term *autoconfuse* – if you should meet any, be sure to tell them about this book

```

## Process this file with automake to produce Makefile.in.

lib_LTLIBRARIES = libhello.la
libhello_la_SOURCES      = hello.c
libhello_la_LDFLAGS      = -no-undefined -version-info 0:0:0

include_HEADERS          = hello.h

bin_PROGRAMS             = hello
hello_SOURCES             = main.c
hello_LDADD               = libhello.la

```

The new feature introduced in this file is the use of the ‘`-no-undefined`’ flag in the `libhello_la_LDFLAGS` value. This flag is required for Windows DLL builds. It asserts to the linker that there are no undefined symbols in the ‘`libhello.la`’ target, which is one of the requirements for building a DLL outlined earlier. See [Section 11.2.1 \[Creating Libtool Libraries with Automake\]](#), page 108.

For an explanation of the contents of the rest of this ‘`Makefile.am`’, See [Chapter 7 \[Introducing GNU automake\]](#), page 41.

### 25.4.3 A `configure.in` for DLLs

‘`configure.in`’ is used to generate the ‘`configure`’ script:

```

# Process this file with autoconf to create configure.

AC_INIT(hello.h)
AM_CONFIG_HEADER(config.h:config.hin)
AM_INIT_AUTOMAKE(hello, 1.0)

AC_PROG_CC
AM_PROG_CC_STDC
AC_C_CONST
AM_PROG_LIBTOOL

AC_OUTPUT(Makefile)

```

The ‘`AC_PROG_CC`’ and ‘`AM_PROG_CC_STDC`’ macros in the ‘`configure.in`’ above will conspire to find a suitable compiler for the C code in this example, and to discover any extra switches required to put that compiler into an ANSI mode. I have used the `const` keyword in the sources, so I need to specify the ‘`AC_C_CONST`’ macro, in case the compiler doesn’t understand it, and finally I have specified the ‘`AM_PROG_LIBTOOL`’ macro since I want the library to be built with Libtool.

In order to set the build environment up we need to create the autogenerated files:

```

$ ls
Makefile.in  hello.c  main.c
configure.in  hello.h
$ aclocal
$ autoheader
$ libtoolize --force --copy
$ automake --foreign --add-missing --copy
automake: configure.in: installing ./install-sh
automake: configure.in: installing ./mkinstalldirs
automake: configure.in: installing ./missing
$ autoconf
$ ls
Makefile.am  config.hin  hello.c  ltmain.sh  stamp-h.in
Makefile.in  config.sub  hello.h  main.c
aclocal.m4   configure  install-sh  missing
config.guess  configure.in  ltconfig  mkinstalldirs

```

If you have already tried to build DLLs with Libtool, you have probably noticed that the first point of failure is during the configuration process. For example, running the new `configure` script you might see:

```

...
checking if libtool supports shared libraries... yes
checking if package supports dlls... no
checking whether to build shared libraries... no
...

```

libtool provides a macro, `AC_LIBTOOL_WIN32_DLL`, which must be added to a package's `configure.in` to communicate to the libtool machinery that the package supports DLLs. Without this macro, libtool will never try to build a DLL on Windows. Add this macro to `configure.in` before the `AM_PROG_LIBTOOL` macro, and try again:

```

$ make
cd . && aclocal
cd . && automake --foreign Makefile
cd . && autoconf
...
checking if libtool supports shared libraries... yes
checking if package supports dlls... yes
checking whether to build shared libraries... yes
...
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -Wp,-MD,.deps/hello.pp \
-c -DDLL_EXPORT -DPIC hello.c -o .libs/hello.lo
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -Wp,-MD,.deps/hello.pp \
-c hello.c -o hello.o >/dev/null 2>&1
mv -f .libs/hello.lo hello.lo
...
gcc -g -O2 -o ./libs/hello main.o .libs/libimp-hello-0-0-0.a \
-Wl,--rpath -Wl,/usr/local/lib
creating hello
...
$ ./hello
Hello, World!

```

If you run this and watch the full output of the ‘make’ command, Libtool uses a rather contorted method of building DLLs, with several invocations each of `dlltool` and `gcc`. I have omitted these from the example above, since they really are very ugly, and in any case are almost incomprehensible to most people. To see it all in its full horror you can always examine the output after running the commands yourself! In a future release of Cygwin, recent work on the binutils linker by DJ Delorie, will allow `gcc` to link DLLs in a single pass using the same syntax used on other systems to produce shared libraries. Libtool will adopt this method when it becomes available, deprecating the use of `dlltool`.

I have extracted the interesting lines from amongst the many calls to `dlltool`<sup>12</sup> and `gcc` generated by `make` in the shell log. The main thing to notice is that we have a ‘hello’ binary, which is executable, and which gives the right result when we run it! From the partial log above, it certainly appears that it has built ‘libhello’ as a DLL and linked that into ‘hello’, but just to double check we can use `ldd`<sup>13</sup>:

```
$ libtool --mode=execute ldd ./hello
lt-hello.exe      -> /tmp/.libs/lt-hello.exe
libhello-0-0-0.dll -> /tmp/.libs/libhello-0-0-0.dll
cygwin1.dll       -> /usr/bin/cygwin1.dll
kernel32.dll      -> /WINNT/system32/kernel32.dll
ntdll.dll         -> /WINNT/system32/ntdll.dll
advapi32.dll      -> /WINNT/system32/advapi32.dll
user32.dll        -> /WINNT/system32/user32.dll
gdi32.dll         -> /WINNT/system32/gdi32.dll
rpcrt4.dll        -> /WINNT/system32/rpcrt4.dll
```

So now you know how to build and link a simple Windows DLL using GNU Autotools: You add ‘-no-undefined’ to the Libtool library ‘LDFLAGS’, and include the ‘AC\_LIBTOOL\_WIN32\_DLL’ macro in your ‘configure.in’.

#### 25.4.4 Handling Data Exports from DLLs

Unfortunately, things are not quite that simple in reality, except in the rare cases where no data symbols are exported across a DLL boundary. If you look back at the example in [Section 25.4.3 \[A configure.in for DLLs\], page 283](#), you will notice that the Libtool object, ‘hello.lo’ was built with the preprocessor macro ‘DLL\_EXPORT’ defined. Libtool does this deliberately so that it is possible to distinguish between a static object build and a Libtool object build, from within the source code.

Lets add a data export to the DLL source to illustrate:

The ‘hello.h’ header must be changed quite significantly:

```
#ifndef HELLO_H
#define HELLO_H 1

#if HAVE_CONFIG_H
# include <config.h>
#endif
```

<sup>12</sup> Part of the Binutils port to Windows, and necessary to massage compiler objects into a working DLL.

<sup>13</sup> This is a shell script for Cygwin which emulates the behaviour of `ldd` on GNU/Linux, available online from <http://www.oranda.demon.co.uk/dist/ldd>.

```

#ifdef _WIN32
#  ifdef DLL_EXPORT
#    define HELLO_SCOPE      __declspec(dllexport)
#  else
#    ifdef LIBHELLO_DLL_IMPORT
#      define HELLO_SCOPE    extern __declspec(dllimport)
#    endif
#  endif
#endif
#ifdef HELLO_SCOPE
#  define HELLO_SCOPE        extern
#endif

HELLO_SCOPE const char *greet;
extern int hello (const char *who);

#endif /* !HELLO_H */

```

The nasty block of preprocessor would need to be shared among all the source files which comprise the ‘libhello.la’ Libtool library, which in this example is just ‘hello.c’. It needs to take care of five different cases:

compiling ‘hello.lo’

When compiling the Libtool object which will be included in the DLL, we need to tell the compiler which symbols are exported data so that it can do the automatic extra dereference required to refer to that data from a program which uses this DLL. We need to flag the data with `__declspec(dllexport)`, See [Section 25.4 \[DLLs with Libtool\]](#), page 280.

compilation unit which will link with ‘libhello-0-0-0.dll’

When compiling an object which will import data from the DLL, again we need to tell the compiler so that it can perform the extra dereference, except this time we use `extern __declspec(dllimport)`. From the preprocessor block, you will see that we need to define ‘LIBHELLO\_DLL\_IMPORT’ to get this define, which I will describe shortly.

compiling ‘hello.o’

When compiling the object for inclusion in the static archive, we must be careful to hide the `__declspec()` declarations from the compiler, or else it will start dereferencing variables for us by mistake at runtime, and in all likelihood cause a segmentation fault. In this case we want the compiler to see a simple `extern` declaration.

compilation unit which will link with ‘libhello.a’

Similarly, an object which references a data symbol which will be statically linked into the final binary from a static archive must not see any of the `__declspec()` code, and requires a simple `extern`.

non Windows host

It seems obvious, but we must also be careful not to contaminate the code when it is compiled on a machine which doesn’t need to jump through the DLL hoops.



The changes to ‘hello.c’ are no different to what would be required on a Unix machine. I have declared the `greet` variable to allow the caller to override the default greeting:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#include <stdio.h>

#include "hello.h"

const char *greet = "Hello";

int
hello (const char *who)
{
    printf("%s, %s!\n", greet, who);
    return 0;
}
```

Again, since the DLL specific changes have been encapsulated in the ‘hello.h’ file, enhancements to ‘main.c’ are unsurprising too:

```
#if HAVE_CONFIG_H
# include <config.h>
#endif

#include "hello.h"

int
main (int argc, const char *const argv[])
{
    if (argc > 1)
    {
        greet = argv[1];
    }
    return hello("World");
}
```

The final thing to be aware of is to be careful about ensuring that ‘LIBHELLO\_DLL\_IMPORT’ is defined when we link an executable against the ‘libhello’ DLL, but not defined if we link it against the static archive. It is impossible to automate this completely, particularly when the executable in question is from another package and is using the installed ‘hello.h’ header. In that case it is the responsibility of the author of that package to probe the system with `configure` to decide whether it will be linking with the DLL or the static archive, and defining ‘LIBHELLO\_DLL\_IMPORT’ as appropriate.

Things are a little simpler when everything is under the control of a single package, but even then it isn’t quite possible to tell for sure whether Libtool is going to build a DLL or only a static library. For example, if some dependencies are dropped for being static, Libtool may disregard ‘-no-undefined’ (see [Section 11.2.1 \[Creating Libtool Libraries with Automake\]](#), page 108). One possible solution is:

1. Define a function in the library that invokes ‘return 1’ from a DLL. Fortunately that’s easy to accomplish thanks to ‘-DDLL\_EXPORT’, in this case, by adding the following to ‘hello.c’:

```
#if defined WIN32 && defined DLL_EXPORT
char
libhello_is_dll (void)
{
    return 1;
}
#endif /* WIN32 && DLL_EXPORT */
```

2. Link a program with the library, and check whether it is a DLL by seeing if the link succeeded.
3. To get cross builds to work, you must, in the same vein, test whether linking a program which calls ‘libhello\_is\_dll’ succeeds to tell whether or not to define ‘LIBHELLO\_DLL\_IMPORT’.

As an example of building the ‘hello’ binary we can add the following code to ‘configure.in’, just before the call to ‘AC\_OUTPUT’:

```
# -----
# Win32 objects need to tell the header whether they will be linking
# with a dll or static archive in order that everything is imported
# to the object in the same way that it was exported from the
# archive (extern for static, __declspec(dllimport) for dlls)
# -----
LIBHELLO_DLL_IMPORT=
case "$host" in
  *-*-cygwin* | *-*-mingw* )
    if test X"$enable_shared" = Xyes; then
      AC_TRY_LINK_FUNC([libhello_is_dll],
        [LIBHELLO_DLL_IMPORT=-DLIBHELLO_DLL_IMPORT])
    fi
  ;;
esac
AC_SUBST(LIBHELLO_DLL_IMPORT)
```

And we must also arrange for the flag to be passed while compiling any objects which will end up in a binary which links with the dll. For this simple example, only ‘main.c’ is affected, and we can add the following rule to the end of ‘Makefile.am’:

```
main.o: main.c
    $(COMPILE) @LIBHELLO_DLL_IMPORT@ -c main.c
```

In a more realistic project, there would probably be dozens of files involved, in which case it would probably be easier to move them all to a separate subdirectory, and give them a ‘Makefile.am’ of their own which could include:

```
CPPFLAGS      = @LIBHELLO_DLL_IMPORT@
```

Now, let’s put all this into practice, and check that it works:

```

$ make
cd . && aclocal
cd . && automake --foreign Makefile
cd . && autoconf
...
checking for gcc option to produce PIC ... -DDLL_EXPORT
checking if gcc PIC flag -DDLL_EXPORT works... yes
...
checking whether to build shared libraries... yes
...
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -Wp,-MD,.deps/hello.pp \
-c -DDLL_EXPORT -DPIC hello.c -o .libs/hello.lo
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -Wp,-MD,.deps/hello.pp \
-c hello.c -o hello.o >/dev/null 2>&1
...
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -DLIBHELLO_DLL_IMPORT \
-c main.c
...
gcc -g -O2 -o ./libs/hello main.o .libs/libimp-hello-0-0-0.a \
-Wl,--rpath -Wl,/usr/local/lib
creating hello
...
$ ./hello
Hello, World!
$ ./hello Howdy
Howdy, World!

```

The recipe also works if I use only the static archives:

```

$ make clean
...
$ ./configure --disable-shared
...
checking whether to build shared libraries... no
...
$ make
...
gcc -DHAVE_CONFIG_H -I. -I. -I. -f -O2 -Wp,-MD,.deps/hello.pp \
-c hello.c -o hello.o
...
ar cru ./libs/libhello.a hello.o
...
gcc -DHAVE_CONFIG_H -I. -I. -I. -g -O2 -c main.c
...
gcc -g -O2 -o hello main.o ./libs/libhello.a
$ ./hello
Hello, World!
$ ./hello "G'Day"
G'day, World!

```

And just to be certain that I am really testing a new statically linked executable:

```

$ ldd ./hello
hello.exe      -> /tmp/hello.exe
cygwin1.dll    -> /usr/bin/cygwin1.dll
kernel32.dll   -> /WINNT/system32/kernel32.dll
ntdll.dll     -> /WINNT/system32/ntdll.dll
advapi32.dll   -> /WINNT/system32/advapi32.dll
user32.dll     -> /WINNT/system32/user32.dll
gdi32.dll     -> /WINNT/system32/gdi32.dll
rpcrt4.dll    -> /WINNT/system32/rpcrt4.dll

```

### 25.4.5 Runtime Loading of DLLs

DLLs built using the recipe described in this chapter can be loaded at runtime in at least three different ways:

- Using the Cygwin emulation of the POSIX `dlopen/dlclose/dlsym` API. Note however that the emulation is broken up until at least version b20.1, and `dlopen(NULL)` doesn't work at all.
- Using the Windows `LoadLibrary/FreeLibrary/GetProcAddress` API.
- Using `libltdl`, which is covered in more detail in [Chapter 18 \[Using GNU libltdl\]](#), [page 185](#).

## 25.5 Package Installation

Having successfully built a GNU Autotools managed package, a Systems Administrator will typically want to install the binaries, libraries and headers of the package. The GNU standards dictate that this be done with the command `make install`, and indeed Automake always generates 'Makefile's which work in this way.

Unfortunately, this `make install` command is often thwarted by the peculiarities of Window's file system, and after an apparently successful installation, often the Windows installation conventions are not always satisfied, so the installed package may not work, even though the uninstalled build is fully operational.

There are a couple of issues which are worthy of discussion:

Prior to release 1.1.0, the Cygwin `install` program did not understand the `.exe` file extension. Fixing it was only a matter of writing a shell script wrapper for the `install` binary. Even though the current release is well behaved in this respect, `.exe` handling is still the cause of some complications. See [Section 25.3.3 \[Executable Filename Extensions\]](#), [page 279](#).

If a package builds any DLLs with `libtool`, they are installed to `$prefix/lib` by default, since this is where shared libraries would be installed on Unix. Windows searches for DLLs at runtime using the user's executable search path (`$PATH`), which generally doesn't contain library paths. The first evidence you will see of this problem is when DLLs you have installed are not found by executables which depend on them, and there are two ways to fix it: The installed DLLs can be moved by hand from their installation directory into the equivalent executable destination, say from `'/usr/local/lib'` to `'/usr/local/bin'`; or better, you can extend your binary search path to include library directories. Adding the following to your `'profile'` would be a good start:

```
PATH=$PATH:/usr/local/lib:/usr/lib:/lib
```

Once you are comfortable with setting your packages up like this, they will be relatively well behaved on Windows and Unix. Of course, you must also write portable code, see [Chapter 15 \[Writing Portable C with GNU Autotools\]](#), page 149.



## 26 Cross Compilation with GNU Autotools

Normally, when you build a program, it runs on the system on which you built it. For example, if you compile a simple program, you can immediately run it on the same machine.

This is normally how GNU Autotools is used as well. You run the ‘`configure`’ script on a particular machine, you run `make` on the same machine, and the resulting program also runs on the same machine. However, there are cases where it is useful to build a program on one machine and run it on another.

One common example is a program which runs on an *embedded system*. An embedded system is a special purpose computer, often part of a larger system, such as the computers found within modern automobiles. An embedded system often does not support a general programming environment, so there is no way to run a shell or a compiler on the embedded system. However, it is still necessary to write programs to run on the embedded system. These programs are built on a different machine, normally a general purpose computer. The resulting programs can not be run directly on the general purpose computer. Instead, they are copied onto the embedded system and run there. (We are omitting many details and possibilities of programming embedded systems here, but this should be enough to understand the the points relevant to GNU Autotools. For more information, see a book such as *Programming Embedded Systems* by Michael Barr.)

Another example where it is useful to build a program on one machine and run it on another is the case when one machine is much faster. It can sometimes be useful to use the faster machine as a compilation server, to build programs which are then copied to the slower machine and run there.

Building a program on one type of system which runs on a different type of system is called *cross compiling*. Doing this requires a specially configured compiler, known as a *cross compiler*. Similarly, we speak of cross assemblers, cross linkers, etc. When it is necessary to explicitly distinguish the ordinary sort of compiler, whose output runs on the same type of system, from a cross compiler, we call the ordinary compiler a *native compiler*. Although the debugger is not strictly speaking a compilation tool, it is meaningful to speak of a cross debugger: a debugger which is used to debug code which runs on another system.

GNU Autotools supports cross compilation in two distinct though related ways. Firstly, GNU Autotools supports configuring and building a cross compiler or other cross compilation tools. Secondly, GNU Autotools supports building tools using a cross compiler (this is sometimes called a *Canadian Cross*). In the rest of this chapter we will explain how to use GNU Autotools to do these tasks.

If you are not interested in doing cross compilation, you may skip this chapter. However, if you are developing ‘`configure`’ scripts, we recommend that you at least skim this chapter to get some hints as to how to write them so that it is possible to build your package using a cross compiler; in particular, see [Section 26.4.6 \[Supporting Cross Compiler\]](#), page 298. Even if your package is useless for an embedded system, it is possible that somebody with a very fast compilation server will want to use it to cross compile your package.

## 26.1 Host and Target

We will first discuss using GNU Autotools to build cross compilation tools. For example, the information in this section will explain how to configure and build the GNU `cc` compiler as a cross compiler.

When building cross compilation tools, there are two different systems involved: the system on which the tools will run, and the system for which the tools will generate code. The system on which the tools will run is called the *host* system. The system for which the tools generate code is called the *target* system.

For example, suppose you have a compiler which runs on a GNU/Linux system and generates ELF programs for a MIPS-based embedded system. In this case, the GNU/Linux system is the host, and the MIPS ELF system is the target. Such a compiler could be called a GNU/Linux cross MIPS ELF compiler, or, equivalently, a `'i386-linux-gnu'` cross `'mips-elf'` compiler. We discussed the latter sorts of names earlier; see [Section 3.4 \[Configuration Names\]](#), page 23.

Naturally, most programs are not cross compilation tools. For those programs, it does not make sense to speak of a target. It only makes sense to speak of a target for programs like the GNU compiler or the GNU binutils which actually produce running code. For example, it does not make sense to speak of the target of a program like `make`.

Most cross compilation tools can also serve as native tools. For a native compilation tool, it is still meaningful to speak of a target. For a native tool, the target is the same as the host. For example, for a GNU/Linux native compiler, the host is GNU/Linux, and the target is also GNU/Linux.

## 26.2 Specifying the Target

By default, the `'configure'` script will assume that the target is the same as the host. This is the more common case; for example, when the target is the same as the host, you get a native compiler rather than a cross compiler.

If you want to build a cross compilation tool, you must specify the target explicitly by using the `'--target'` option when you run `'configure'`. See [Chapter 3 \[Invoking configure\]](#), page 17. The argument to `'--target'` is the configuration name of the system for which you wish to generate code. See [Section 3.4 \[Configuration Names\]](#), page 23. For example, to build tools which generate code for a MIPS ELF embedded system, you would use `'--target mips-elf'`.

## 26.3 Using the Target Type

A `'configure'` script for a cross compilation tool will use the `'--target'` option to control how it is built, so that the resulting program will produce programs which run on the appropriate system. In this section we explain how you can write your own configure scripts to support the `'--target'` option.

You must start by putting `'AC_CANONICAL_SYSTEM'` in `'configure.in'`. `'AC_CANONICAL_SYSTEM'` will look for a `'--target'` option and canonicalize it using the `'config.sub'` shell script (for more information about configuration names,



canonicalizing them, and `'config.sub'`, see [Section 3.4 \[Configuration Names\]](#), page 23). `'AC_CANONICAL_SYSTEM'` will also run `'AC_CANONICAL_HOST'` to get the host information.

The host and target type will be recorded in the following shell variables:

- `'host'`        The canonical configuration name of the host. This will normally be determined by running the `'config.guess'` shell script, although the user is permitted to override this by using an explicit `'--host'` option.
- `'target'`     The canonical configuration name of the target.
- `'host_alias'`     The argument to the `'--host'` option, if used. Otherwise, the same as the `'host'` variable.
- `'target_alias'`    The argument to the `'--target'` option. If the user did not specify a `'--target'` option, this will be the same as `'host_alias'`.
- `'host_cpu'`
- `'host_vendor'`
- `'host_os'`    The first three parts of the canonical host configuration name.
- `'target_cpu'`
- `'target_vendor'`
- `'target_os'`    The first three parts of the canonical target configuration name.

Note that if `'host'` and `'target'` are the same string, you can assume a native configuration. If they are different, you can assume a cross configuration.

It is possible for `'host'` and `'target'` to represent the same system, but for the strings to not be identical. For example, if `'config.guess'` returns `'sparc-sun-sunos4.1.4'`, and somebody configures with `'--target sparc-sun-sunos4.1'`, then the slight differences between the two versions of SunOS may be unimportant for your tool. However, in the general case it can be quite difficult to determine whether the differences between two configuration names are significant or not. Therefore, by convention, if the user specifies a `'--target'` option without specifying a `'--host'` option, it is assumed that the user wants to configure a cross compilation tool.

The `'target'` variable should not be handled in the same way as the `'target_alias'` variable. In general, whenever the user may actually see a string, `'target_alias'` should be used. This includes anything which may appear in the file system, such as a directory name or part of a tool name. It also includes any tool output, unless it is clearly labelled as the canonical target configuration name. This permits the user to use the `'--target'` option to specify how the tool will appear to the outside world. On the other hand, when checking for characteristics of the target system, `'target'` should be used. This is because a wide variety of `'--target'` options may map into the same canonical configuration name. You should not attempt to duplicate the canonicalization done by `'config.sub'` in your own code.

By convention, cross tools are installed with a prefix of the argument used with the `'--target'` option, also known as `'target_alias'`. If the user does not use the `'--target'` option, and thus is building a native tool, no prefix is used. For example, if `gcc` is configured

with `--target mips-elf`, then the installed binary will be named `mips-elf-gcc`. If `gcc` is configured without a `--target` option, then the installed binary will be named `gcc`.

The Autoconf macro `AC_ARG_PROGRAM` will handle the names of binaries for you. If you are using Automake, no more need be done; the programs will automatically be installed with the correct prefixes. Otherwise, see the Autoconf documentation for `AC_ARG_PROGRAM`.

## 26.4 Building with a Cross Compiler

It is possible to build a program which uses GNU Autotools on one system and to run it on a different type of system. In other words, it is possible to build programs using a cross compiler. In this section, we explain what this means, how to build programs this way, and how to write your `configure` scripts to support it. Building a program on one system and running it on another is sometimes referred to as a *Canadian Cross*<sup>1</sup>.

### 26.4.1 Canadian Cross Example

We'll start with an example of a Canadian Cross, to make sure that the concepts are clear. Using a GNU/Linux system, you can build a program which will run on a Solaris system. You would use a GNU/Linux cross Solaris compiler to build the program. You could not run the resulting programs on your GNU/Linux system. After all, they are Solaris programs. Instead, you would have to copy the result over to a Solaris system before you could run it.

Naturally, you could simply build the program on the Solaris system in the first place. However, perhaps the Solaris system is not available for some reason; perhaps you don't actually have one, but you want to build the tools for somebody else to use. Or perhaps your GNU/Linux system is much faster than your Solaris system.

A Canadian Cross build is most frequently used when building programs to run on a non-Unix system, such as DOS or Windows. It may be simpler to configure and build on a Unix system than to support the GNU Autotools tools on a non-Unix system.

### 26.4.2 Canadian Cross Concepts

When building a Canadian Cross, there are at least two different systems involved: the system on which the tools are being built, and the system on which the tools will run. The system on which the tools are being built is called the *build* system. The system on which the tools will run is called the host system. For example, if you are building a Solaris program on a GNU/Linux system, as in the previous example, the build system would be GNU/Linux, and the host system would be Solaris.

Note that we already discussed the host system above; see [Section 26.1 \[Host and Target\], page 294](#). It is, of course, possible to build a cross compiler using a Canadian Cross (i.e., build a cross compiler using a cross compiler). In this case, the system for which the resulting cross compiler generates code is the target system.

---

<sup>1</sup> The name Canadian Cross comes from the most complex case, in which three different types of systems are used. At the time that these issues were being hashed out, Canada had three national political parties.

An example of building a cross compiler using a Canadian Cross would be building a Windows cross MIPS ELF compiler on a GNU/Linux system. In this case the build system would be GNU/Linux, the host system would be Windows, and the target system would be MIPS ELF.

### 26.4.3 Build Cross Host Tools

In order to configure a program for a Canadian Cross build, you must first build and install the set of cross tools you will use to build the program. These tools will be build cross host tools. That is, they will run on the build system, and will produce code that runs on the host system. It is easy to confuse the meaning of build and host here. Always remember that the build system is where you are doing the build, and the host system is where the resulting program will run. Therefore, you need a build cross host compiler.

In general, you must have a complete cross environment in order to do the build. This normally means a cross compiler, cross assembler, and so forth, as well as libraries and header files for the host system. Setting up a complete cross environment can be complex, and is beyond the scope of this book. You may be able to get more information from the ‘crossgcc’ mailing list and FAQ; see <http://www.objsw.com/CrossGCC/>.

### 26.4.4 Build and Host Options

When you run ‘configure’ for a Canadian Cross, you must use both the ‘--build’ and ‘--host’ options. The ‘--build’ option is used to specify the configuration name of the build system. This can normally be the result of running the ‘config.guess’ shell script, and when using a Unix shell it is reasonable to use ‘--build=‘config.guess’’. The ‘--host’ option is used to specify the configuration name of the host system.

As we explained earlier, ‘config.guess’ is used to set the default value for the ‘--host’ option (see [Section 26.3 \[Using the Target Type\]](#), page 294). We can now see that since ‘config.guess’ returns the type of system on which it is run, it really identifies the build system. Since the host system is normally the same as the build system (or, in other words, people do not normally build using a cross compiler), it is reasonable to use the result of ‘config.guess’ as the default for the host system when the ‘--host’ option is not used.

It might seem that if the ‘--host’ option were used without the ‘--build’ option that the ‘configure’ script could run ‘config.guess’ to determine the build system, and presume a Canadian Cross if the result of ‘config.guess’ differed from the ‘--host’ option. However, for historical reasons, some configure scripts are routinely run using an explicit ‘--host’ option, rather than using the default from ‘config.guess’. As noted earlier, it is difficult or impossible to reliably compare configuration names (see [Section 26.3 \[Using the Target Type\]](#), page 294). Therefore, by convention, if the ‘--host’ option is used, but the ‘--build’ option is not used, then the build system defaults to the host system. (This convention may be changing in the Autoconf 2.5 release. Check the release notes.)

### 26.4.5 Canadian Cross Tools

You must explicitly specify the cross tools which you want to use to build the program. This is done by setting environment variables before running the ‘configure’ script. You must normally set at least the environment variables ‘CC’, ‘AR’, and ‘RANLIB’ to the cross

tools which you want to use to build. For some programs, you must set additional cross tools as well, such as ‘AS’, ‘LD’, or ‘NM’. You would set these environment variables to the build cross host tools which you are going to use.

For example, if you are building a Solaris program on a GNU/Linux system, and your GNU/Linux cross Solaris compiler were named ‘solaris-gcc’, then you would set the environment variable ‘CC’ to ‘solaris-gcc’.

## 26.4.6 Supporting Building with a Cross Compiler

If you want to make it possible to build a program which you are developing using a cross compiler, you must take some care when writing your ‘configure.in’ and make rules. Simple cases will normally work correctly. However, it is not hard to write configure tests which will fail when building with a cross compiler, so some care is required to avoid this.

You should write your ‘configure’ scripts to support building with a cross compiler if you can, because that will permit others to build your program on a fast compilation server.

### 26.4.6.1 Supporting Building with a Cross Compiler in Configure Scripts

In a ‘configure.in’ file, after calling ‘AC\_PROG\_CC’, you can find out whether the program is being built by a cross compiler by examining the shell variable ‘cross\_compiling’. If the compiler is a cross compiler, which means that this is a Canadian Cross, ‘cross\_compiling’ will be ‘yes’. In a normal configuration, ‘cross\_compiling’ will be ‘no’.

You ordinarily do not need to know the type of the build system in a ‘configure’ script. However, if you do need that information, you can get it by using the macro ‘AC\_CANONICAL\_SYSTEM’, the same macro which is used to determine the target system. This macro will set the variables ‘build’, ‘build\_alias’, ‘build\_cpu’, ‘build\_vendor’, and ‘build\_os’, which correspond to the similar ‘target’ and ‘host’ variables, except that they describe the build system. See [Section 26.3 \[Using the Target Type\]](#), page 294.

When writing tests in ‘configure.in’, you must remember that you want to test the host environment, not the build environment. Macros which use the compiler, such as like ‘AC\_CHECK\_FUNCS’, will test the host environment. That is because the tests will be done by running the compiler, which is actually a build cross host compiler. If the compiler can find the function, that means that the function is present in the host environment.

Tests like ‘test -f /dev/ptyp0’, on the other hand, will test the build environment. Remember that the ‘configure’ script is running on the build system, not the host system. If your ‘configure’ scripts examines files, those files will be on the build system. Whatever you determine based on those files may or may not be the case on the host system.

Most Autoconf macros will work correctly when building with a cross compiler. The main exception is ‘AC\_TRY\_RUN’. This macro tries to compile and run a test program. This will fail when building with a cross compiler, because the program will be compiled for the host system, which means that it will not run on the build system.

The ‘AC\_TRY\_RUN’ macro provides an optional argument to tell the ‘configure’ script what to do when building with a cross compiler. If that argument is not present, you will get a warning when you run ‘autoconf’:

warning: AC\_TRY\_RUN called without default to allow cross compiling

This tells you that the resulting ‘configure’ script will not work when building with a cross compiler.

In some cases while it may better to perform a test at configure time, it is also possible to perform the test at run time (see [Section 23.3.2 \[Testing system features at application run-time\]](#), page 254). In such a case you can use the cross compiling argument to ‘AC\_TRY\_RUN’ to tell your program that the test could not be performed at configure time.

There are a few other autoconf macros which will not work correctly when building with a cross compiler: a partial list is ‘AC\_FUNC\_GETPGRP’, ‘AC\_FUNC\_SETPGRP’, ‘AC\_FUNC\_SETVBUF\_REVERSED’, and ‘AC\_SYS\_RESTARTABLE\_SYSCALLS’. The ‘AC\_CHECK\_SIZEOF’ macro is generally not very useful when building with a cross compiler; it permits an optional argument indicating the default size, but there is no way to know what the correct default should be.

### 26.4.6.2 Supporting Building with a Cross Compiler in Makefiles

The main cross compiling issue in a ‘Makefile’ arises when you want to use a subsidiary program to generate code or data which you will then include in your real program. If you compile this subsidiary program using ‘\$(CC)’ in the usual way, you will not be able to run it. This is because ‘\$(CC)’ will build a program for the host system, but the program is being built on the build system. You must instead use a compiler for the build system, rather than the host system. This compiler is conventionally called ‘\$(CC\_FOR\_BUILD)’.

A ‘configure’ script should normally permit the user to define ‘CC\_FOR\_BUILD’ explicitly in the environment. Your configure script should help by selecting a reasonable default value. If the ‘configure’ script is not being run with a cross compiler (i.e., the ‘cross\_compiling’ shell variable is ‘no’ after calling ‘AC\_PROG\_CC’), then the proper default for ‘CC\_FOR\_BUILD’ is simply ‘\$(CC)’. Otherwise, a reasonable default is simply ‘cc’.

Note that you should not include ‘config.h’ in a file you are compiling with ‘\$(CC\_FOR\_BUILD)’. The ‘configure’ script will build ‘config.h’ with information for the host system. However, you are compiling the file using a compiler for the build system (a native compiler). Subsidiary programs are normally simple filters which do no user interaction, and it is often possible to write them in a highly portable fashion so that the absence of ‘config.h’ is not crucial.

The gcc ‘Makefile.in’ shows a complex situation in which certain files, such as ‘rtl.c’, must be compiled into both subsidiary programs run on the build system and into the final program. This approach may be of interest for advanced GNU Autotools hackers. Note that, at least in GCC 2.95, the build system compiler is rather confusingly called ‘HOST\_CC’.



## Appendices





## Appendix A Installing GNU Autotools

The GNU Autotools may already be installed at your site, particularly if you are using a GNU/Linux system. If you don't have these tools installed, or do not have the most recent versions, this appendix will help you install them.

### A.1 Prerequisite tools

The GNU Autotools make use of a few additional tools to get their jobs done. This makes it necessary to gather all of the prerequisite tools to get started. Before installing GNU Autotools, it is necessary to obtain and install these tools.

The GNU Autotools are all built around the assumption that the system will have a relatively functional version of the Bourne shell. If your system is missing a Bourne shell or your shell behaves different to most, as is the case with the Bourne shell provided with Ultrix, then you might like to obtain and install GNU `bash`. See [Section A.2 \[Downloading GNU Autotools\], page 303](#), for details on obtaining GNU packages. If you are using a Windows system, the easiest way to obtain a Bourne shell and all of the shell utilities that you will need is to download and install Cygnus Solutions' Cygwin product. You can locate further information about Cygwin by reading <http://www.cygnus.com/cygwin/>.

Autoconf requires GNU M4. Vendor-provided versions of M4 have proven to be troublesome, so Autoconf checks that GNU M4 is installed on your system. Again, see [Section A.2 \[Downloading GNU Autotools\], page 303](#), for details on obtaining GNU packages such as M4. At the time of writing, the latest version is 1.4. Earlier versions of GNU M4 will work, but they may not be as efficient.

Automake requires Perl version 5 or greater. You should download and install a version of Perl for your platform which meets these requirements.

### A.2 Downloading GNU Autotools

The GNU Autotools are distributed as part of the GNU project, under the terms of the GNU General Public License. Each tool is packaged in a compressed archive that you can retrieve from sources such as Internet FTP archives and CD-ROM distributions. While you may use any source that is convenient to you, it is best to use one of the recognized GNU mirror sites. A current list of mirror sites is listed at <http://www.gnu.org/order/ftp.html>.

The directory layout of the GNU archives has recently been improved to make it easier to locate particular packages. The new scheme places package archive files under a subdirectory whose name reflects the base name of the package. For example, GNU Autoconf 2.13 can be found at:

```
/gnu/autoconf/autoconf-2.13.tar.gz
```

The filenames corresponding to the latest versions of GNU Autotools, at the time of writing, are:

```
autoconf-2.13.tar.gz
automake-1.4.tar.gz
libtool-1.3.5.tar.gz
```

These packages are stored as **tar** archives and compressed with the **gzip** compression utility. Once you have obtained all of these packages, you should unpack them using the following commands:

```
gunzip TOOL-VERSION.tar.gz
tar xfv TOOL-VERSION.tar
```

GNU **tar** archives are created with a directory name prefixed to all of the files in the archive. This means that files will be tidily unpacked into an appropriately named subdirectory, rather than being written all over your current working directory.

### A.3 Installing the tools

When installing GNU Autotools, it is a good idea to install the tools in the same location (eg. `/usr/local`). This allows the tools to discover each others' presence at installation time. The location shown in the examples below will be the default, `/usr/local`, as this choice will make the tools available to all users on the system.

Installing Autoconf is usually a quick and simple exercise, since Autoconf itself uses `'configure'` to prepare itself for building and installation. Automake and Libtool can be installed using the same steps as for Autoconf. As a matter of personal preference, I like to create a separate build tree when configuring packages to keep the source tree free of derived files such as object files. Applying what we know about invoking `'configure'` (see [Chapter 3 \[Invoking configure\], page 17](#)), we can now configure and build Autoconf. The only `'configure'` option we're likely to want to use is `'--prefix'`, so if you want to install the tools in another location, include this option on the command line. It might be desirable to install the package elsewhere when operating in networked environments.

```
$ mkdir ac-build && cd ac-build
$ ~/autoconf-2.13/configure
```

You will see `'configure'` running its tests and producing a `'Makefile'` in the build directory:

```
creating cache ./config.cache
checking for gm4... no
checking for gnum4... no
checking for m4... /usr/bin/m4
checking whether we are using GNU m4... yes
checking for mawk... no
checking for gawk... gawk
checking for perl... /usr/bin/perl
checking for a BSD compatible install... /usr/bin/install -c
updating cache ./config.cache
creating ./config.status
creating Makefile
creating testsuite/Makefile
```

To build Autoconf, type the following:

```
$ make all
```

Autoconf has no architecture-specific files to be compiled, so this process finishes quickly. To install files into `/usr/local`, it may be necessary to become the root user before installing.

```
# make install
```

Autoconf is now installed on your system.



## Appendix B PLATFORMS

This table lists platforms and toolchains known to be supported by Libtool. Each row represents completion of the self test suite shipped with the Libtool distribution on the platform named in that row.

There is a ‘PLATFORMS’ file maintained in the Libtool source tree, updated whenever a Libtool user volunteers updated information, or when the Libtool team runs pre-release tests on the platforms to which they individually have access.

The table from the latest source tree at the time of writing follows:

**canonical host name**

This is the configuration triplet returned by `config.guess` on each system for which the test suite was executed. Where the developer who ran the tests considered it to be significant, versions of tools in the compiler toolchain are named below the configuration triplet.

**compiler** The compiler used for the tests.

**libtool release**

The version number of the Libtool distribution most recently tested for the associated configuration triplet. The GNU Autotools all use an alpha version numbering system where ‘odd’ letters (a, c, e, g etc.) represent many CVS snapshots between the ‘even’ lettered (b, d, f etc) alpha release versions. After version 1.4, the CVS revision number of the ‘Changelog’ file will be appended to odd lettered CVS snapshots, ‘1.4a 1.641.2.54’, for example.

**results** Either ‘ok’ if the Libtool test suite passed all tests, or optionally ‘NS’ if the test suite would only pass when the distribution was configured with the ‘--disable-shared’ option.

canonical host name (tools versions)	compiler	libtool release	results
alpha-dec-osf4.0* (egcs-1.1.2)	gcc	1.3b	ok
alpha-dec-osf4.0*	cc	1.3b	ok
alpha-dec-osf3.2	gcc	0.8	ok
alpha-dec-osf3.2	cc	0.8	ok
alpha-dec-osf2.1	gcc	1.2f	NS
alpha*-unknown-linux-gnu (egcs-1.1.2, GNU ld 2.9.1.0.23)	gcc	1.3b	ok
hppa2.0w-hp-hpux11.00	cc	1.2f	ok
hppa2.0-hp-hpux10.20	cc	1.3.2	ok
hppa1.1-hp-hpux10.20	gcc	1.2f	ok
hppa1.1-hp-hpux10.20	cc	1.2f	ok
hppa1.1-hp-hpux10.10	gcc	1.2f	ok
hppa1.1-hp-hpux10.10	cc	1.2f	ok
hppa1.1-hp-hpux9.07	gcc	1.2f	ok
hppa1.1-hp-hpux9.07	cc	1.2f	ok

hppa1.1-hp-hpux9.05	gcc	1.2f	ok
hppa1.1-hp-hpux9.05	cc	1.2f	ok
hppa1.1-hp-hpux9.01	gcc	1.2f	ok
hppa1.1-hp-hpux9.01	cc	1.2f	ok
i*86-*-beos	gcc	1.2f	ok
i*86-*-bsdi4.0.1	gcc	1.3c	ok
(gcc-2.7.2.1)			
i*86-*-bsdi4.0	gcc	1.2f	ok
i*86-*-bsdi3.1	gcc	1.2e	NS
i*86-*-bsdi3.0	gcc	1.2e	NS
i*86-*-bsdi2.1	gcc	1.2e	NS
i*86-pc-cygwin	gcc	1.3b	NS
(egcs-1.1 stock b20.1 compiler)			
i*86-*-dguxR4.20MU01	gcc	1.2	ok
i*86-*-freebsdelf4.0	gcc	1.3c	ok
(egcs-1.1.2)			
i*86-*-freebsdelf3.2	gcc	1.3c	ok
(gcc-2.7.2.1)			
i*86-*-freebsdelf3.1	gcc	1.3c	ok
(gcc-2.7.2.1)			
i*86-*-freebsdelf3.0	gcc	1.3c	ok
i*86-*-freebsd3.0	gcc	1.2e	ok
i*86-*-freebsd2.2.8	gcc	1.3c	ok
(gcc-2.7.2.1)			
i*86-*-freebsd2.2.6	gcc	1.3b	ok
(egcs-1.1 & gcc-2.7.2.1, native ld)			
i*86-*-freebsd2.1.5	gcc	0.5	ok
i*86-*-gnu	gcc	1.3c	ok (1.602)
i*86-*-netbsd1.4	gcc	1.3c	ok
(egcs-1.1.1)			
i*86-*-netbsd1.3.3	gcc	1.3c	ok
(gcc-2.7.2.2+myc2)			
i*86-*-netbsd1.3.2	gcc	1.2e	ok
i*86-*-netbsd1.3I	gcc	1.2e	ok
(egcs 1.1?)			
i*86-*-netbsd1.2	gcc	0.9g	ok
i*86-*-linux-gnu	gcc	1.3b	ok
(egcs-1.1.2, GNU ld 2.9.1.0.23)			
i*86-*-linux-gnulibc1	gcc	1.2f	ok
i*86-*-openbsd2.5	gcc	1.3c	ok
(gcc-2.8.1)			
i*86-*-openbsd2.4	gcc	1.3c	ok
(gcc-2.8.1)			
i*86-*-solaris2.7	gcc	1.3b	ok
(egcs-1.1.2, native ld)			
i*86-*-solaris2.6	gcc	1.2f	ok
i*86-*-solaris2.5.1	gcc	1.2f	ok
i*86-ncr-sysv4.3.03	gcc	1.2f	ok
i*86-ncr-sysv4.3.03	cc	1.2e	ok

```

(cc -Hnocopyr)
i*86-pc-sco3.2v5.0.5 cc 1.3c ok
i*86-pc-sco3.2v5.0.5 gcc 1.3c ok
(gcc 95q4c)
i*86-pc-sco3.2v5.0.5 gcc 1.3c ok
(egcs-1.1.2)
i*86-UnixWare7.1.0-sysv5 cc 1.3c ok
i*86-UnixWare7.1.0-sysv5 gcc 1.3c ok
(egcs-1.1.1)
m68k-next-nextstep3 gcc 1.2f NS
m68k-sun-sunos4.1.1 gcc 1.2f NS
(gcc-2.5.7)
m88k-dg-dguxR4.12TMU01 gcc 1.2 ok
m88k-motorola-sysv4 gcc 1.3 ok
(egcs-1.1.2)
mips-sgi-irix6.5 gcc 1.2f ok
(gcc-2.8.1)
mips-sgi-irix6.4 gcc 1.2f ok
mips-sgi-irix6.3 gcc 1.3b ok
(egcs-1.1.2, native ld)
mips-sgi-irix6.3 cc 1.3b ok
(cc 7.0)
mips-sgi-irix6.2 gcc 1.2f ok
mips-sgi-irix6.2 cc 0.9 ok
mips-sgi-irix5.3 gcc 1.2f ok
(egcs-1.1.1)
mips-sgi-irix5.3 gcc 1.2f NS
(gcc-2.6.3)
mips-sgi-irix5.3 cc 0.8 ok
mips-sgi-irix5.2 gcc 1.3b ok
(egcs-1.1.2, native ld)
mips-sgi-irix5.2 cc 1.3b ok
(cc 3.18)
mipsel-unknown-openbsd2.1 gcc 1.0 ok
powerpc-ibm-aix4.3.1.0 gcc 1.2f ok
(egcs-1.1.1)
powerpc-ibm-aix4.2.1.0 gcc 1.2f ok
(egcs-1.1.1)
powerpc-ibm-aix4.1.5.0 gcc 1.2f ok
(egcs-1.1.1)
powerpc-ibm-aix4.1.5.0 gcc 1.2f NS
(gcc-2.8.1)
powerpc-ibm-aix4.1.4.0 gcc 1.0 ok
powerpc-ibm-aix4.1.4.0 xlc 1.0i ok
rs6000-ibm-aix4.1.5.0 gcc 1.2f ok
(gcc-2.7.2)
rs6000-ibm-aix4.1.4.0 gcc 1.2f ok
(gcc-2.7.2)
rs6000-ibm-aix3.2.5 gcc 1.0i ok

```

rs6000-ibm-aix3.2.5	xlc	1.0i	ok
sparc-sun-solaris2.7	gcc	1.3b	ok
(egcs-1.1.2, GNU ld 2.9.1 & native ld)			
sparc-sun-solaris2.6	gcc	1.3.2	ok
(egcs-1.1.2, GNU ld 2.9.1 & native ld)			
sparc-sun-solaris2.5.1	gcc	1.2f	ok
sparc-sun-solaris2.5	gcc	1.3b	ok
(egcs-1.1.2, GNU ld 2.9.1 & native ld)			
sparc-sun-solaris2.5	cc	1.3b	ok
(SC 3.0.1)			
sparc-sun-solaris2.4	gcc	1.0a	ok
sparc-sun-solaris2.4	cc	1.0a	ok
sparc-sun-solaris2.3	gcc	1.2f	ok
sparc-sun-sunos4.1.4	gcc	1.2f	ok
sparc-sun-sunos4.1.4	cc	1.0f	ok
sparc-sun-sunos4.1.3_U1	gcc	1.2f	ok
sparc-sun-sunos4.1.3C	gcc	1.2f	ok
sparc-sun-sunos4.1.3	gcc	1.3b	ok
(egcs-1.1.2, GNU ld 2.9.1 & native ld)			
sparc-sun-sunos4.1.3	cc	1.3b	ok
sparc-unknown-bsdi4.0	gcc	1.2c	ok
sparc-unknown-linux-gnulibc1	gcc	1.2f	ok
sparc-unknown-linux-gnu	gcc	1.3b	ok
(egcs-1.1.2, GNU ld 2.9.1.0.23)			
sparc64-unknown-linux-gnu	gcc	1.2f	ok

## Notes:

- "ok" means "all tests passed".
- "NS" means "Not Shared", but OK for static libraries

You too can contribute to this file, either if you use a platform which is missing from the table entirely, or if you are using a newer release of Libtool than the version listed in the table. From a freshly unpacked release, do the following:

```
$ cd libtool-1.4
$ ./configure
...
```

```
-----
Configuring libtool 1.4a (1.641.2.54 2000/06/18 03:02:52)
-----
```

```
...
checking host system type... i586-pc-linux-gnu
checking build system type... i586-pc-linux-gnu
...
$ make
...
$ make check
...
=====
```



```
All 76 tests passed
```

```
=====
```

```
...
```

If there are no test failures, and you see a message similar to the above, send a short message to [libtool@gnu.org](mailto:libtool@gnu.org) stating what you did and the configuration triplet for your platform as reported for the ‘host system’ by `configure` (see the example directly above), and the precise version number of the release you have tested as reported by ‘`libtool --version`’:

```
$ pwd
```

```
/tmp/cvs/libtool
```

```
$ ./libtool --version
```

```
ltmain.sh (GNU libtool) 1.4a (1.641.2.41 2000/05/29 10:40:46)
```

The official ‘PLATFORMS’ file will be updated shortly thereafter.



## Appendix C Generated File Dependencies

These diagrams show the data flows associated with each of the tools you might need to use when bootstrapping a project with GNU Autotools. A lot of files are consumed and produced by these tools, and it is important that all of the required input files are present (and correct) at each stage – `configure` requires `Makefile.in` and produces `Makefile` for example. There are many of these relationships, and these diagrams should help you to visualize the dependencies. They will be invaluable while you learn your way around GNU Autotools, but before long you will find that you need to refer to them rarely, if at all.

They do not show how the individual files are laid out in a project directory tree, since some of them, `config.guess` for example, have no single place at which they must appear, and others, `Makefile.am` for example, may be present in several places, depending on how you want to structure your project directories.

The key to the diagrams in this appendix follows:


- The boxes are the individual tools which comprise GNU Autotools.
- Where multiple interlinked boxes appear in a single diagram, this represents one tool itself running other helper programs. If a box is behind another box, it is a (group of) helper program(s) that may be automatically run by the boxes in front.
- Dotted arrows are for optional files, which may be a part of the process.
- Where an input arrow and output arrow are aligned horizontally, the output is created from the input by the process between the two.
- words in parentheses, "()", are for deprecated files which are supported but no longer necessary.

Notice that in some cases, a file output during one stage of the whole process becomes the driver for a subsequent stage.

Each of the following diagrams represents the execution of one of the tools in GNU Autotools; they are presented in the order that we recommend you run them, though some stages may not be required for your project. You shouldn't run `libtoolize` if your project doesn't use `libtool`, for example.


### C.1 aclocal

The `aclocal` program creates the file `aclocal.m4` by combining stock installed macros, user defined macros and the contents of `acinclude.m4` to define all of the macros required by `configure.in` in a single file. `aclocal` was created as a fix for some missing functionality in Autoconf, and as such we consider it a wart. In due course `aclocal` itself will disappear, and Autoconf will perform the same function unaided.



## C.2 autoheader


`autoheader` runs `m4` over ‘`configure.in`’, but with key macros defined differently than when `autoconf` is executed, such that suitable `cpp` definitions are output to ‘`config.h.in`’.



## C.3 automake and libtoolize

`automake` will call `libtoolize` to generate some extra files if the macro ‘`AC_PROG_LIBTOOL`’ is used in ‘`configure.in`’. If it is not present then `automake` will install ‘`config.guess`’ and ‘`config.sub`’ by itself.


`libtoolize` can also be run manually if desired; `automake` will only run `libtoolize` automatically if ‘`ltmain.sh`’ and ‘`ltconfig`’ are missing.



The versions of ‘`config.guess`’ and ‘`config.sub`’ installed differ between releases of Automake and Libtool, and might be different depending on whether `libtoolize` is used to install them or not. Before releasing your own package you should get the latest versions of these files from <ftp://ftp.gnu.org/gnu/config>, in case there have been changes since releases of the GNU Autotools.

## C.4 autoconf

`autoconf` expands the `m4` macros in ‘`configure.in`’, perhaps using macro definitions from ‘`aclocal.m4`’, to generate the `configure` script.



## C.5 configure

The purpose of the preceding processes was to create the input files necessary for `configure` to run correctly. You would ship your project with the generated `script` and the files in columns, *other input* and *processes* (except ‘`config.cache`’), but `configure` is designed to be run by the person installing your package. Naturally, you will run it too while you develop your project, but the files it produces are specific to your development machine, and are not shipped with your package – the person installing it later will run `configure` and generate *output files* specific to their own machine.

Running the `configure` script on the build host executes the various tests originally specified by the ‘`configure.in`’ file, and then creates another script, ‘`config.status`’. This new script generates the ‘`config.h`’ header file from ‘`config.h.in`’, and ‘`Makefile`’s from the named ‘`Makefile.in`’s. Once ‘`config.status`’ has been created, it can be executed by itself to regenerate files without rerunning all the tests. Additionally, if ‘`AC_PROG_LIBTOOL`’ was used, then `ltconfig` is used to generate a `libtool` script.



## Appendix D Autoconf Macro Reference

This is an alphabetical list of each Autoconf macro used in this book, along with a description of what each does. They are provided for your reference while reading this book. The descriptions are only brief; see the appropriate reference manual for a complete description.

**AC\_ARG\_ENABLE**(*feature*, *help-text*, [*if-given*], [*if-not-given*])

This macro allows the maintainer to specify additional package options accepted by ‘configure’—for example, ‘--enable-zlib’. The action shell code may access any arguments to the option in the shell variable `enableval`. For example, ‘--enable-buffers=128’ would cause ‘configure’ to set `enableval` to ‘128’.

**AC\_ARG\_PROGRAM**

This macro places a `sed` transformation program into the output variable `program_transform_name` that can be used to transform the filenames of installed programs. If the ‘--program-prefix’, ‘--program-suffix’ or ‘--program-transform-name’ options are passed to ‘configure’, an appropriate transformation program will be generated. If no options are given, but the type of the host system differs from the type of the target system, program names are transformed by prefixing them with the type of the target (eg. `arm-elf-gcc`).

**AC\_ARG\_WITH**(*package*, *help-text*, [*if-given*], [*if-not-given*])

This macro allows the maintainer to specify additional packages that this package should work with (for example, a library to manipulate shadow passwords). The user indicates this preference by invoking ‘configure’ with an option such as ‘--with-shadow’. If an optional argument is given, this value is available to shell code in the shell variable `withval`.

**AC\_CACHE\_CHECK**(*message*, *cache-variable*, *commands*)

This macro is a convenient front-end to the `AC_CACHE_VAL` macro that takes care of printing messages to the user, including whether or not the result was found in the cache. It should be used in preference to `AC_CACHE_VAL`.

**AC\_CACHE\_VAL**(*cache-variable*, *commands*)

This is a low-level macro which implements the Autoconf cache feature. If the named variable is set at runtime (for instance, if it was read from ‘`config.cache`’), then this macro does nothing. Otherwise, it runs the shell code in *commands*, which is assumed to set the cache variable.

**AC\_CANONICAL\_HOST**

This macro determines the type of the host system and sets the output variable ‘`host`’, as well as other more obscure variables.

**AC\_CANONICAL\_SYSTEM**

This macro determines the type of the build, host and target systems and sets the output variables ‘`build`’, ‘`host`’ and ‘`target`’, amongst other more obscure variables.

**AC\_CHECK\_FILE**(*file*, [*if-found*], [*if-not-found*])

This macro tests for the existence of a file in the file system of the build system, and runs the appropriate shell code depending on whether or not the file is found.

**AC\_CHECK\_FUNCS**(*function-list*, [*if-found*], [*if-not-found*])

This looks for a series of functions. If the function `quux` is found, the C preprocessor macro `HAVE_QUUX` will be defined. In addition, if the *if-found* argument is given, it will be run (as shell code) when a function is found – this code can use the `sh break` command to prevent `AC_CHECK_FUNCS` from looking for the remaining functions in the list. The shell code in *if-not-found* is run if a function is not found.

**AC\_CHECK\_HEADER**(*header*, [*if-found*], [*if-not-found*])

This macro executes some specified shell code if a header file exists. If it is not present, alternative shell code is executed instead.

**AC\_CHECK\_HEADERS**(*header-list*, [*if-found*], [*if-not-found*])

This looks for a series of headers. If the header `quux.h` is found, the C preprocessor macro `HAVE_QUUX_H` will be defined. In addition, if the *if-found* argument is given, it will be run (as shell code) when a header is found – this code can use the `sh break` command to prevent `AC_CHECK_HEADERS` from looking for the remaining headers in the list. The shell code in *if-not-found* is run if a header is not found.

**AC\_CHECK\_LIB**(*library*, *function*, [*if-found*], [*if-not-found*], [*other-libraries*])

This looks for the named function in the named library specified by its base name. For instance the math library, `'libm.a'`, would be named simply `'m'`. If the function is found in the library `'foo'`, then the C preprocessor macro `HAVE_LIBFOO` is defined.

**AC\_CHECK\_PROG**(*variable*, *program-name*, *value-if-found*, [*value-if-not-found*], [*path*], [*reject*])

Checks to see if the program named by *program-name* exists in the path *path*. If found, it sets the shell variable *variable* to the value *value-if-found*; if not it uses the value *value-if-not-found*. If *variable* is already set at runtime, this macro does nothing.

**AC\_CHECK\_SIZEOF**(*type*, [*size-if-cross-compiling*])

This macro determines the size of C and C++ built-in types and defines `SIZEOF_type` to the size, where *type* is transformed—all characters to upper case, spaces to underscores and `'*'` to `'P'`. If the type is unknown to the compiler, the size is set to 0. An optional argument specifies a default size when cross-compiling. The `'configure'` script will abort with an error message if it tries to cross-compile without this default size.

**AC\_CONFIG\_AUX\_DIR**(*directory*)

This macro allows an alternative directory to be specified for the location of auxiliary scripts such as `'config.guess'`, `'config.sub'` and `'install-sh'`. By default, `'$srcdir'`, `'$srcdir/..'` and `'$srcdir/../../.'` are searched for these files.



**AC\_CONFIG\_HEADER(*header-list*)**

This indicates that you want to use a config header, as opposed to having all the C preprocessor macros defined via `-D` options in the DEFS ‘Makefile’ variable. Each header named in *header-list* is created at runtime by ‘configure’ (via `AC_OUTPUT`). There are a variety of optional features for use with config headers (different naming schemes and so forth); see the reference manual for more information.

**AC\_C\_CONST**

This macro defines the C preprocessor macro `const` to the string `const` if the C compiler supports the `const` keyword. Otherwise it is defined to be the empty string.

**AC\_C\_INLINE**

This macro tests if the C compiler can accept the `inline` keyword. It defines the C preprocessor macro `inline` to be the keyword accepted by the compiler or the empty string if it is not accepted at all.

**AC\_DEFINE(*variable*, [*value*], [*description*])**

This is used to define C preprocessor macros. The first argument is the name of the macro to define. The *value* argument, if given, is the value of the macro. The final argument can be used to avoid adding an ‘`#undef`’ for the macro to ‘`acconfig.h`’.

**AC\_DEFINE\_UNQUOTED(*variable*, [*value*], [*description*])**

This is like `AC_DEFINE`, but it handles the quoting of *value* differently. This macro is used when you want to compute the value instead of having it used verbatim.

**AC\_DEFUN(*name*, *body*)**

This macro is used to define new macros. It is similar to M4’s `define` macro, except that it performs additional internal functions.

**AC\_DISABLE\_FAST\_INSTALL**

This macro can be used to disable Libtool’s ‘fast install’ feature.

**AC\_DISABLE\_SHARED**

This macro changes the default behavior of `AC_PROG_LIBTOOL` so that shared libraries will not be built by default. The user can still override this new default by using ‘`--enable-shared`’.

**AC\_DISABLE\_STATIC**

This macro changes the default behavior of `AC_PROG_LIBTOOL` so that static libraries will not be built by default. The user can still override this new default by using ‘`--enable-static`’.

**AC\_EXEEXT**

Sets the output variable `EXEEXT` to the extension of executables produced by the compiler. It is usually set to the empty string on Unix systems and ‘`.exe`’ on Windows.

**AC\_FUNC\_ALLOCA**

This macro defines the C preprocessor macro `HAVE_ALLOCA` if the various tests indicate that the C compiler has built-in `alloca` support. If there is an `'alloca.h'` header file, this macro defines `HAVE_ALLOCA_H`. If, instead, the `alloca` function is found in the standard C library, this macro defines `C_ALLOCA` and sets the output variable `ALLOCA` to `alloca.o`.

**AC\_FUNC\_GETPGRP**

This macro tests if the `getpgrp` function takes a process ID as an argument or not. If it does not, the C preprocessor macro `GETPGRP_VOID` is defined.

**AC\_FUNC\_MEMCMP**

This macro tests for a working version of the `memcmp` function. If absent, or it does not work correctly, `'memcmp.o'` is added to the `LIBOBJS` output variable.

**AC\_FUNC\_MMAP**

Defines the C preprocessor macro `HAVE_MMAP` if the `mmap` function exists and works.

**AC\_FUNC\_SETVBUF\_REVERSED**

On some systems, the order of the `mode` and `buf` arguments is reversed with respect to the ANSI C standard. If so, this macro defines the C preprocessor macro `SETVBUF_REVERSED`.

**AC\_FUNC\_UTIME\_NULL**

Defines the C preprocessor macro `HAVE_UTIME_NULL` if a call to `utime` with a NULL `utimbuf` pointer sets the file's timestamp to the current time.

**AC\_FUNC\_VPRINTF**

Defines the C preprocessor macro `HAVE_VPRINTF` if the `vprintf` function is available. If not and the `_doprnt` function is available instead, this macro defines `HAVE_DOPRNT`.

**AC\_HEADER\_DIRENT**

This macro searches a number of specific header files for a declaration of the C type `DIR`. Depending on which header file the declaration is found in, this macro may define one of the C preprocessor macros `HAVE_DIRENT_H`, `HAVE_SYS_NDIR_H`, `HAVE_SYS_DIR_H` or `HAVE_NDIR_H`. Refer to the Autoconf manual for an example of how these macros should be used in your source code.

**AC\_HEADER\_STDC**

This macro defines the C preprocessor macro `STDC_HEADERS` if the system has the ANSI standard C header files. It determines this by testing for the existence of the `'stdlib.h'`, `'stdarg.h'`, `'string.h'` and `'float.h'` header files and testing if `'string.h'` declares `memchr`, `'stdlib.h'` declares `free`, and `'ctype.h'` macros such as `isdigit` work with 8-bit characters.

**AC\_INIT(filename)**

This macro performs essential initialization for the generated `'configure'` script. An optional argument may provide the name of a file from the source directory to ensure that the directory has been specified correctly.

**AC\_LIBTOOL\_DLOPEN**

Call this macro before **AC\_PROG\_LIBTOOL** to indicate that your package wants to use Libtool's support for dlopened modules.

**AC\_LIBTOOL\_WIN32\_DLL**

Call this macro before **AC\_PROG\_LIBTOOL** to indicate that your package has been written to build DLLs on Windows. If this macro is not called, Libtool will only build static libraries on Windows.

**AC\_LIB\_LTDL**

This macro does the **configure**-time checks needed to cause `'ltdl.c'` to be compiled correctly. That is, this is used to enable dynamic loading via `libltdl`.

**AC\_LINK\_FILES**(*source-list*, *dest-list*)

Use this macro to create a set of links; if possible, symlinks are made. The two arguments are parallel lists: the first element of *dest-list* is the name of a to-be-created link whose target is the first element of *source-list*.

**AC\_MSG\_CHECKING**(*message*)

This macro outputs a message to the user in the usual style of **'configure'** scripts: leading with the word **'checking'** and ending in **'...'**. This message gives the user an indication that the **'configure'** script is still working. A subsequent invocation of **AC\_MSG\_RESULT** should be used to output the result of a test.

**AC\_MSG\_ERROR**(*message*)

This macro outputs an error message to standard error and aborts the **'configure'** script. It should only be used for fatal error conditions.

**AC\_MSG\_RESULT**(*message*)

This macro should be invoked after a corresponding invocation of **AC\_MSG\_CHECKING** with the result of a test. Often the result string can be as simple as **'yes'** or **'no'**.

**AC\_MSG\_WARN**(*message*)

This macro outputs a warning to standard error, but allows the **'configure'** script to continue. It should be used to notify the user of abnormal, but non-fatal, conditions.

**AC\_OBJEXT**

Sets the output variable **OBJEXT** to the extension of object files produced by the compiler. Usually, it is set to **'o'** on Unix systems and **'.obj'** on Windows.

**AC\_OUTPUT**(*files*, [*extra-commands*], [*init-commands*])

This macro must be called at the end of every **'configure.in'**. It creates each file listed in *files*. For a given file, by default, **configure** reads the template file whose name is the name of the input file with **'.in'** appended – for instance, **'Makefile'** is generated from **'Makefile.in'**. This default can be overridden by using a special naming convention for the file.

For each name **'foo'** given as an argument to **AC\_SUBST**, **configure** will replace any occurrence of **'@foo@'** in the template file with the value of the shell variable

‘foo’ in the generated file. This macro also generates the config header, if `AC_CONFIG_HEADER` was called, and any links, if `AC_LINK_FILES` was called. The additional arguments can be used to further tailor the output processing.

#### `AC_OUTPUT_COMMANDS`(*extra-commands*, [*init-commands*])

This macro works like the optional final arguments of `AC_OUTPUT`, except that it can be called more than once from ‘`configure.in`’. (This makes it possible for macros to use this feature and yet remain modular.) See the reference manual for the precise definition of this macro.

#### `AC_PROG_AWK`

This macro searches for an `awk` program and sets the output variable `AWK` to be the best one it finds.

#### `AC_PROG_CC`

This checks for the C compiler to use and sets the shell variable `CC` to the value. If the GNU C compiler is being used, this sets the shell variable `GCC` to ‘yes’. This macro sets the shell variable `CFLAGS` if it has not already been set. It also calls `AC_SUBST` on `CC` and `CFLAGS`.

#### `AC_PROG_CC_STDC`

This macro attempts to discover a necessary command line option to have the C compiler accept ANSI C. If so, it adds the option to the `CC`. If it were not possible to get the C compiler to accept ANSI, the shell variable `ac_cv_prog_cc_stdc` will be set to ‘no’.

#### `AC_PROG_CPP`

This macro sets the output variable `CPP` to a command that runs the C preprocessor. If ‘`$CC -E`’ does not work, it will set the variable to ‘`/lib/cpp`’.

#### `AC_PROG_CXX`

This is like `AC_PROG_CC`, but it checks for the C++ compiler, and sets the variables `CXX`, `GXX` and `CXXFLAGS`.

#### `AC_PROG_GCC_TRADITIONAL`

This macro determines if GCC requires the ‘`-traditional`’ option in order to compile code that uses `ioctl` and, if so, adds ‘`-traditional`’ to the `CC` output variable. This condition is rarely encountered, thought mostly on old systems.

#### `AC_PROG_INSTALL`

This looks for an `install` program and sets the output variables `INSTALL`, `INSTALL_DATA`, `INSTALL_PROGRAM`, and `INSTALL_SCRIPT`. This macro assumes that if an `install` program cannot be found on the system, your package will have ‘`install-sh`’ available in the directory chosen by `AC_CONFIG_AUX_DIR`.

#### `AC_PROG_LEX`

This looks for a `lex`-like program and sets the ‘`Makefile`’ variable `LEX` to the result. It also sets `LEXLIB` to whatever might be needed to link against `lex` output.

**AC\_PROG\_LIBTOOL**

This macro is the primary way to integrate Libtool support into ‘configure’. If you are using Libtool, you should call this macro in ‘configure.in’. Among other things, it adds support for the ‘--enable-shared’ configure flag.

**AC\_PROG\_LN\_S**

This sets the ‘Makefile’ variable LN\_S to ‘ln -s’ if symbolic links work in the current working directory. Otherwise it sets LN\_S to just ‘ln’.

**AC\_PROG\_MAKE\_SET**

Some versions of **make** need to have the ‘Makefile’ variable MAKE set in ‘Makefile’ in order for recursive builds to work. This macro checks whether this is needed, and, if so, it sets the ‘Makefile’ variable SET\_MAKE to the result. **AM\_INIT\_AUTOMAKE** calls this macro, so if you are using Automake, you don’t need to call it or use SET\_MAKE in ‘Makefile.am’.

**AC\_PROG\_RANLIB**

This searches for the **ranlib** program. It sets the ‘Makefile’ variable RANLIB to the result. If **ranlib** is not found, or not needed on the system, then the result is `..`.

**AC\_PROG\_YACC**

This searches for the **yacc** program – it tries **bison**, **byacc**, and **yacc**. It sets the ‘Makefile’ variable YACC to the result.

**AC\_REPLACE\_FUNCS**(*function list*)

This macro takes a single argument, which is a list of functions. For a given function ‘func’, ‘configure’ will do a link test to try to find it. If the function cannot be found, then ‘func.o’ will be added to **LIBOBJS**. If function can be found, then ‘configure’ will define the C preprocessor symbol **HAVE\_FUNC**.

**AC\_REQUIRE**(*macro-name*)

This macro takes a single argument, which is the name of another macro. (Note that you must quote the argument correctly: **AC\_REQUIRE**([FOO]) is correct, while **AC\_REQUIRE**(FOO) is not.) If the named macro has already been invoked, then **AC\_REQUIRE** does nothing. Otherwise, it invokes the named macro with no arguments.

**AC\_REVISION**(*revision*)

This macro takes a single argument, a version string. Autoconf will copy this string into the generated ‘configure’ file.

**AC\_STRUCT\_ST\_BLKSIZE**

Defines the C preprocessor macro **HAVE\_ST\_BLKSIZE** if **struct stat** has an **st\_blksize** member.

**AC\_STRUCT\_ST\_BLOCKS**

Defines the C preprocessor macro **HAVE\_ST\_BLOCKS** if **struct stat** has an **st\_blocks** member.

**AC\_STRUCT\_ST\_RDEV**

Defines the C preprocessor macro **HAVE\_ST\_RDEV** if **struct stat** has an **st\_rdev** member.

**AC\_STRUCT\_TM**

This macro looks for `struct tm` in ‘`time.h`’ and defines `TM_IN_SYS_TIME` if it is not found there.

**AC\_SUBST(*name*)**

This macro takes a single argument, which is the name of a shell variable. When `configure` generates the files listed in `AC_OUTPUT` (e.g., ‘`Makefile`’), it will substitute the variable’s value (at the end of the `configure` run – the value can be changed after `AC_SUBST` is called) anywhere a string of the form ‘`@name@`’ is seen.

**AC\_TRY\_COMPILE(*includes*, *body*, [*if-ok*], [*if-not-ok*])**

This macro is used to try to compile a given function, whose body is given in *body*. *includes* lists any ‘`#include`’ statements needed to compile the function. If the code compiles correctly, the shell commands in *if-ok* are run; if not, *if-not-ok* is run. Note that this macro will not try to link the test program – it will only try to compile it.

**AC\_TRY\_LINK(*includes*, *body*, [*if-found*], [*if-not-found*])**

This is used like `AC_TRY_COMPILE`, but it tries to link the resulting program. The libraries and options in the `LIBS` shell variable are passed to the link.

**AC\_TRY\_RUN(*program*, [*if-true*], [*if-false*], [*if-cross-compiling*])**

This macro tries to compile and link the program whose text is in *program*. If the program compiles, links, and runs successfully, the shell code *if-true* is run. Otherwise, the shell code *if-false* is run. If the current configure is a cross-configure, then the program is not run, and on a successful compile and link, the shell code *if-cross-compiling* is run.

**AC\_TYPE\_SIGNAL**

This macro defines the C preprocessor macro `RETSIGTYPE` to be the correct return type of signal handlers. For instance, it might be ‘`void`’ or ‘`int`’.

**AC\_TYPE\_SIZE\_T**

This macro looks for the type `size_t`. If not defined on the system, it defines it (as a macro) to be ‘`unsigned`’.

**AM\_CONDITIONAL(*name*, *testcode*)**

This Automake macro takes two arguments: the name of a conditional and a shell statement that is used to determine whether the conditional should be true or false. If the shell code returns a successful (0) status, then the conditional will be true. Any conditional in your ‘`configure.in`’ is automatically available for use in any ‘`Makefile.am`’ in that project.

**AM\_CONFIG\_HEADER(*header*)**

This is just like `AC_CONFIG_HEADER`, but does some additional setup required by Automake. If you are using Automake, use this macro. Otherwise, use `AC_CONFIG_HEADER`.

**AM\_INIT\_AUTOMAKE(*package*, *version*, [*nodefine*])**

This macro is used to do all the standard initialization required by Automake. It has two required arguments: the package name and the version number. This

macro sets and calls `AC_SUBST` on the shell variables `PACKAGE` and `VERSION`. By default it also defines these variables (via `AC_DEFINE_UNQUOTED`). However, this macro also accepts an optional third argument which, if not empty, means that the `AC_DEFINE_UNQUOTED` calls for `PACKAGE` and `VERSION` should be suppressed.

#### `AM_MAINTAINER_MODE`

This macro is used to enable a special Automake feature, maintainer mode, which we've documented elsewhere (see [Section 5.3 \[Maintaining Input Files\]](#), page 32).

#### `AM_PROG_CC_STDC`

This macro takes no arguments. It is used to try to get the C compiler to be ANSI compatible. It does this by adding different options known to work with various system compilers. This macro is most typically used in conjunction with Automake when you want to use the automatic de-ANSI-fication feature.

#### `AM_PROG_LEX`

This is like `AC_PROG_LEX`, but it does some additional processing used by Automake-generated 'Makefile's. If you are using Automake, then you should use this. Otherwise, you should use `AC_PROG_LEX` (and perhaps `AC_DECL_YYTEXT`, which `AM_PROG_LEX` calls).

#### `AM_WITH_DMALLOC`

This macro adds support for the '--with-dmalloc' flag to `configure`. If the user chooses to enable `dmalloc` support, then this macro will define the pre-processor symbol `WITH_DMALLOC` and will add `-ldmalloc` to the 'Makefile' variable `LIBS`.





## Appendix E OPL

OPEN PUBLICATION LICENSE Draft v0.4, 8 June 1999

### I. REQUIREMENTS ON BOTH UNMODIFIED AND MODIFIED VERSIONS

The Open Publication works may be reproduced and distributed in whole or in part, in any medium physical or electronic, provided that the terms of this license are adhered to, and that this license or an incorporation of it by reference (with any options elected by the author(s) and/or publisher) is displayed in the reproduction.

Proper form for an incorporation by reference is as follows:

Copyright (c) <year> by <author's name or designee>. This material may be distributed only subject to the terms and conditions set forth in the Open Publication License, vX.Y or later (the latest version is presently available at <URL:http:// TBD>).

The reference must be immediately followed with any options elected by the author(s) and/or publisher of the document (see section VI).

Commercial redistribution of Open Publication-licensed material is permitted.

Any publication in standard (paper) book form shall require the citation of the original publisher and author. The publisher and author's names shall appear on all outer surfaces of the book. On all outer surfaces of the book the original publisher's name shall be as large as the title of the work and cited as possessive with respect to the title.

### II. COPYRIGHT

The copyright to each Open Publication is owned by its author(s) or designee.

### III. SCOPE OF LICENSE

The following license terms apply to all Open Publication works, unless otherwise explicitly stated in the document.

Mere aggregation of Open Publication works or a portion of an Open Publication work with other works or programs on the same media shall not cause this license to apply to those other works. The aggregate work shall contain a notice specifying the inclusion of the Open Publication material and appropriate copyright notice.

SEVERABILITY. If any part of this license is found to be unenforceable

in any jurisdiction, the remaining portions of the license remain in force.

NO WARRANTY. Open Publication works are licensed and provided "as is" without warranty of any kind, express or implied, including, but not limited to, the implied warranties of merchantability and fitness for a particular purpose or a warranty of non-infringement.

#### IV. REQUIREMENTS ON MODIFIED WORKS

All modified versions of documents covered by this license, including translations, anthologies, compilations and partial documents, must meet the following requirements:

- 1) The modified version must be labeled as such.
- 2) The person making the modifications must be identified and the modifications dated.
- 3) Acknowledgement of the original author and publisher if applicable must be retained according to normal academic citation practices.
- 4) The location of the original unmodified document must be identified.
- 5) The original author's (or authors') name(s) may not be used to assert or imply endorsement of the resulting document without the original author's (or authors') permission.

#### V. GOOD-PRACTICE RECOMMENDATIONS

In addition to the requirements of this license, it is requested from and strongly recommended of redistributors that:

- 1) If you are distributing Open Publication works on hardcopy or CD-ROM, you provide email notification to the authors of your intent to redistribute at least thirty days before your manuscript or media freeze, to give the authors time to provide updated documents. This notification should describe modifications, if any, made to the document.
- 2) All substantive modifications (including deletions) be either clearly marked up in the document or else described in an attachment to the document.

Finally, while it is not mandatory under this license, it is considered good form to offer a free copy of any hardcopy and CD-ROM expression of an Open Publication-licensed work to its author(s).

#### VI. LICENSE OPTIONS

The author(s) and/or publisher of an Open Publication-licensed document may elect certain options by appending language to the reference to or

copy of the license. These options are considered part of the license instance and must be included with the license (or its incorporation by reference) in derived works.

- A. To prohibit distribution of substantively modified versions without the explicit permission of the author(s). "Substantive modification" is defined as a change to the semantic content of the document, and excludes mere changes in format or typographical corrections.

To accomplish this, add the phrase 'Distribution of substantively modified versions of this document is prohibited without the explicit permission of the copyright holder.' to the license reference or copy.

- B. To prohibit any publication of this work or derivative works in whole or in part in standard (paper) book form for commercial purposes is prohibited unless prior permission is obtained from the copyright holder.

To accomplish this, add the phrase 'Distribution of the work or derivative of the work in any standard (paper) book form is prohibited unless prior permission is obtained from the copyright holder.' to the license reference or copy.

#### OPEN PUBLICATION POLICY APPENDIX:

(This is not considered part of the license.)

Open Publication works are available in source format via the Open Publication home page at <URL:tbd>.

Open Publication authors who want to include their own license on Open Publication works may do so, as long as their terms are not more restrictive than the Open Publication license.

If you have questions about the Open Publication License, please contact TBD, and/or the Open Publication Authors' List at <TBD>, via email.



# Index

- #**
- `#!env` ..... 241
- 
- `--build` option ..... 297
  - `--host` option ..... 297
  - `--target` option ..... 294
  - `--all-static`, libtool option ..... 90
  - `--DPIC` ..... 85
  - `--static`, libtool option ..... 90
- 8**
- 8.3 filenames ..... 157
  - 8.3 filenames in GNU Autotools ..... 276
- A**
- `AC_CANONICAL_SYSTEM` ..... 294
  - `AC_DISABLE_FAST_INSTALL` ..... 106
  - `AC_DISABLE_SHARED` ..... 106
  - `AC_DISABLE_STATIC` ..... 106
  - `AC_LIBTOOL_WIN32_DLL` ..... 284
  - `autogen.sh` ..... 49
- B**
- back-linking ..... 186
  - binary files ..... 157
  - binary mode `fopen` ..... 271
  - binary mode `open` ..... 271
  - bootstrap script ..... 49
  - build option ..... 297
- C**
- C language portability ..... 149
  - canadian cross in `configure` ..... 298
  - canadian cross in `make` ..... 299
  - canadian cross, configuring ..... 297
  - case-folding filesystems ..... 157
  - configuration name ..... 23
  - `configure` build system ..... 297
  - `configure` cross compiler support ..... 298
  - `configure` host ..... 297
  - `configure` target ..... 294
  - configuring a canadian cross ..... 297
  - cross compilation ..... 293
  - cross compiler support in `configure` ..... 298
  - cross compiler support in `make` ..... 299
  - `CRTDLL.DLL` ..... 267
  - Cygwin autotools compilation ..... 268
  - `CYGWIN` binmode setting ..... 271
  - Cygwin Bourne shell ..... 268
  - Cygwin `full.exe` ..... 267
  - Cygwin `gcc` ..... 268
  - Cygwin M4 ..... 268
  - Cygwin Make ..... 268
  - Cygwin `mount` ..... 270
  - Cygwin package portability ..... 269
  - Cygwin Perl ..... 268
  - Cygwin `sh.exe` ..... 268
  - Cygwin static packages ..... 269
  - Cygwin `usertools.exe` ..... 267
- D**
- directory separator character ..... 277
  - DJGPP ..... 267
- F**
- file name case in Windows ..... 157
- H**
- host option `xgr` ..... 297
  - host system ..... 294
  - `HOST_CC` ..... 299
- L**
- library terminology ..... 81
  - Libtool library ..... 81
  - Libtool object ..... 84, 86
  - `LIBTOOL_DEPS` ..... 107
  - loaders ..... 201
  - `LTALLOCA` ..... 107
  - `LTLIBOBJ` ..... 107
- M**
- make cross compiler support ..... 299
- P**
- partial linking ..... 87
  - path element separator character ..... 277
  - path separator, mixed mode ..... 277
  - PE-COFF binary format ..... 267
  - PIC ..... 85
  - pseudo-library ..... 81
- S**
- shared library ..... 85

**T**

target option .....	294
target system .....	294
text files .....	157
text mode fopen .....	271
text mode open .....	271

**V**

version.texi .....	132
--------------------	-----

**W**

Windows CR-LF .....	157, 270
Windows text line terminator .....	157, 270
Windows, Autoconf .....	268
Windows, Automake .....	268
Windows, Cygwin .....	267
Windows, Libtool philosophy .....	269
Windows, mingw .....	267
wrapper scripts .....	96

## Short Contents

Foreword .....	1
Part I .....	5
1 Introduction .....	7
2 History .....	9
Part II .....	15
3 How to run configure and make .....	17
4 Introducing ‘ <b>Makefile</b> ’s .....	25
5 A Minimal GNU Autotools Project .....	29
6 Writing ‘ <b>configure.in</b> ’ .....	35
7 Introducing GNU Automake .....	41
8 Bootstrapping .....	49
9 A Small GNU Autotools Project .....	51
10 Introducing GNU Libtool .....	81
11 Using GNU Libtool with ‘ <b>configure.in</b> ’ and ‘ <b>Makefile.am</b> ’ .....	103
12 A Large GNU Autotools Project .....	123
13 Rolling Distribution Tarballs .....	139
14 Installing and Uninstalling Configured Packages .....	143
15 Writing Portable C with GNU Autotools .....	149
16 Writing Portable C++ with GNU Autotools .....	161
17 Dynamic Loading .....	177
18 Using GNU libltdl .....	185
19 Advanced GNU Automake Usage .....	205
20 A Complex GNU Autotools Project .....	209
Part III .....	225
21 M4 .....	227
22 Writing Portable Bourne Shell .....	239
23 Writing New Macros for Autoconf .....	253
24 Migrating an Existing Package to GNU Autotools .....	261
25 Using GNU Autotools with Cygnus Cygwin .....	267
26 Cross Compilation with GNU Autotools .....	293
Appendices .....	301
A Installing GNU Autotools .....	303
B PLATFORMS .....	307
C Generated File Dependencies .....	313

D	Autoconf Macro Reference . . . . .	317
E	OPL . . . . .	327
Index	. . . . .	331



# Table of Contents

<b>Foreword</b> .....	<b>1</b>
<b>Part I</b> .....	<b>5</b>
<b>1 Introduction</b> .....	<b>7</b>
1.1 What this book is .....	7
1.2 What the book is not .....	7
1.3 Who should read this book .....	8
1.4 How this book is organized .....	8
<b>2 History</b> .....	<b>9</b>
2.1 The Diversity of Unix Systems .....	9
2.2 The First Configure Programs .....	10
2.3 Configure Development .....	11
2.4 Automake Development .....	11
2.5 Libtool Development .....	12
2.6 Microsoft Windows .....	12
<b>Part II</b> .....	<b>15</b>
<b>3 How to run configure and make</b> .....	<b>17</b>
3.1 Configuring .....	17
3.2 Files generated by configure .....	21
3.3 The most useful Makefile targets .....	22
3.4 Configuration Names .....	23
<b>4 Introducing ‘Makefile’s</b> .....	<b>25</b>
4.1 Targets and dependencies .....	25
4.2 Makefile syntax .....	26
4.3 Macros .....	26
4.4 Suffix rules .....	27
<b>5 A Minimal GNU Autotools Project</b> .....	<b>29</b>
5.1 User-Provided Input Files .....	29
5.2 Generated Output Files .....	30
5.3 Maintaining Input Files .....	32
5.4 Packaging Generated Files .....	33
5.5 Documentation and ChangeLogs .....	33

<b>6</b>	<b>Writing ‘configure.in’</b>	<b>35</b>
6.1	What is Portability?	35
6.2	Brief introduction to portable sh	35
6.3	Ordering Tests	36
6.4	What to check for	37
6.5	Using Configuration Names	39
<b>7</b>	<b>Introducing GNU Automake</b>	<b>41</b>
7.1	General Automake principles	41
7.2	Introduction to Primaries	42
7.3	The easy primaries	42
7.4	Programs and libraries	43
7.5	Frequently Asked Questions	45
7.6	Multiple directories	46
7.7	Testing	47
<b>8</b>	<b>Bootstrapping</b>	<b>49</b>
<b>9</b>	<b>A Small GNU Autotools Project</b>	<b>51</b>
9.1	GNU Autotools in Practice	51
9.1.1	Project Directory Structure	51
9.1.2	C Header Files	52
9.1.3	C++ Compilers	53
9.1.4	Function Definitions	54
9.1.5	Fallback Function Implementations	54
9.1.6	K&R Compilers	55
9.2	A Simple Shell Builders Library	59
9.2.1	Portability Infrastructure	59
9.2.1.1	Error Management	59
9.2.1.2	Memory Management	62
9.2.1.3	Generalised List Data Type	64
9.2.2	Library Implementation	66
9.2.2.1	‘sic.c’ & ‘sic.h’	66
9.2.2.2	‘builtin.c’ & ‘builtin.h’	67
9.2.2.3	‘eval.c’ & ‘eval.h’	67
9.2.2.4	‘syntax.c’ & ‘syntax.h’	68
9.2.3	Beginnings of a ‘configure.in’	68
9.3	A Sample Shell Application	74
9.3.1	‘sic_repl.c’	74
9.3.2	‘sic_syntax.c’	75
9.3.3	‘sic_builtin.c’	76
9.3.4	‘sic.c’ & ‘sic.h’	78

<b>10</b>	<b>Introducing GNU Libtool .....</b>	<b>81</b>
10.1	Creating libtool .....	82
10.2	The Libtool Library .....	84
10.2.1	Position Independent Code .....	84
10.2.2	Creating Shared Libraries .....	85
10.2.3	Creating Static Libraries .....	87
10.2.4	Creating Convenience Libraries .....	87
10.3	Linking an Executable .....	89
10.4	Linking a Library .....	91
10.4.1	Inter-library Dependencies .....	93
10.4.2	Using Convenience Libraries .....	94
10.5	Executing Uninstalled Binaries .....	96
10.6	Installing a Library .....	96
10.7	Installing an Executable .....	99
10.8	Uninstalling .....	101
<b>11</b>	<b>Using GNU Libtool with ‘configure.in’ and ‘Makefile.am’ .....</b>	<b>103</b>
11.1	Integration with ‘configure.in’ .....	103
11.1.1	Extra Configure Options .....	104
11.1.2	Extra Macros for Libtool .....	106
11.2	Integration with ‘Makefile.am’ .....	108
11.2.1	Creating Libtool Libraries with Automake .....	108
11.2.2	Linking against Libtool Libraries with Automake .....	110
11.3	Using libtoolize .....	111
11.4	Library Versioning .....	112
11.5	Convenience Libraries .....	114
<b>12</b>	<b>A Large GNU Autotools Project .....</b>	<b>123</b>
12.1	Using Libtool Libraries .....	123
12.2	Removing ‘--foreign’ .....	126
12.3	Installing Header Files .....	126
12.4	Including Texinfo Documentation .....	131
12.5	Adding a Test Suite .....	133
<b>13</b>	<b>Rolling Distribution Tarballs .....</b>	<b>139</b>
13.1	Introduction to Distributions .....	139
13.2	What goes in .....	140
13.3	The distcheck rule .....	141
13.4	Some caveats .....	141
13.5	Implementation .....	141

<b>14</b>	<b>Installing and Uninstalling Configured Packages .....</b>	<b>143</b>
14.1	Where files are installed .....	143
14.2	Fine-grained control of install .....	145
14.3	Install hooks .....	146
14.4	Uninstall .....	147
<b>15</b>	<b>Writing Portable C with GNU Autotools .....</b>	<b>149</b>
15.1	C Language Portability .....	149
15.1.1	ISO C .....	149
15.1.2	C Data Type Sizes .....	149
15.1.3	C Endianness .....	150
15.1.4	C Structure Layout .....	151
15.1.5	C Floating Point .....	152
15.1.6	GNU cc Extensions .....	152
15.2	Cross-Unix Portability .....	153
15.2.1	Cross-Unix Function Calls .....	153
15.2.2	Cross-Unix System Interfaces .....	154
15.3	Unix/Windows Portability .....	155
15.3.1	Unix/Windows Emulation .....	155
15.3.2	Unix/Windows Portable Scripting Language ...	156
15.3.3	Unix/Windows User Interface Library .....	156
15.3.4	Unix/Windows Specific Code .....	156
15.3.5	Unix/Windows Issues .....	157
15.3.5.1	Text and Binary Files .....	157
15.3.5.2	File system Issues .....	157
15.3.5.3	DOS Filename Restrictions .....	157
15.3.5.4	Windows File Name Case .....	157
15.3.5.5	Whitespace in File Names .....	158
15.3.5.6	Windows Separators and Drive Letters .....	158
15.3.5.7	Miscellaneous Issues .....	158
<b>16</b>	<b>Writing Portable C++ with GNU Autotools .....</b>	<b>161</b>
16.1	Brief History of C++ .....	161
16.2	Changeable C++ .....	162
16.2.1	Built-in bool type .....	162
16.2.2	Exceptions .....	163
16.2.3	Casts .....	163
16.2.4	Variable Scoping in For Loops .....	164
16.2.5	Namespaces .....	164
16.2.6	The <code>explicit</code> Keyword .....	165
16.2.7	The <code>mutable</code> Keyword .....	165
16.2.8	The <code>typename</code> Keyword .....	166
16.2.9	Runtime Type Identification (RTTI) .....	167

16.2.10	Templates .....	168
16.2.11	Default template arguments .....	169
16.2.12	Standard library headers .....	169
16.2.13	Standard Template Library .....	170
16.3	Compiler Quirks .....	170
16.3.1	Template Instantiation .....	170
16.3.2	Name Mangling .....	171
16.4	How GNU Autotools Can Help .....	173
16.4.1	Testing C++ Implementations with Autoconf ...	173
16.4.2	Automake C++ support .....	173
16.4.3	Libtool C++ support .....	174
16.5	Further Reading .....	174
<b>17</b>	<b>Dynamic Loading .....</b>	<b>177</b>
17.1	Dynamic Modules .....	177
17.2	Module Access Functions .....	178
17.3	Finding a Module .....	179
17.4	A Simple GNU/Linux Module Loader .....	180
17.5	A Simple GNU/Linux Dynamic Module .....	183
<b>18</b>	<b>Using GNU libltdl .....</b>	<b>185</b>
18.1	Introducing libltdl .....	185
18.2	Using libltdl .....	187
18.2.1	Configury .....	188
18.2.2	Memory Management .....	190
18.2.3	Module Loader .....	190
18.2.4	Dependent Libraries .....	194
18.2.5	Dynamic Module .....	195
18.3	Portable Library Design .....	196
18.4	dlpreopen Loading .....	198
18.5	User Module Loaders .....	200
18.5.1	Loader Mechanism .....	201
18.5.2	Loader Management .....	202
18.5.3	Loader Errors .....	203
<b>19</b>	<b>Advanced GNU Automake Usage .....</b>	<b>205</b>
19.1	Conditionals .....	205
19.2	Language support .....	206
19.3	Automatic dependency tracking .....	207

**20 A Complex GNU Autotools Project . . . . . 209**

20.1	A Module Loading Subsystem . . . . .	209
20.1.1	Initialising the Module Loader . . . . .	209
20.1.2	Managing Module Loader Errors . . . . .	211
20.1.3	Loading a Module . . . . .	212
20.1.4	Unloading a Module . . . . .	214
20.2	A Loadable Module . . . . .	219
20.3	Interpreting Commands from a File . . . . .	222
20.4	Integrating Dmalloc . . . . .	223

**Part III . . . . . 225****21 M4 . . . . . 227**

21.1	What does M4 do? . . . . .	227
21.2	How GNU Autotools uses M4 . . . . .	227
21.3	Fundamentals of M4 processing . . . . .	228
21.3.1	Token scanning . . . . .	228
21.3.2	Macros and macro expansion . . . . .	229
21.3.3	Quoting . . . . .	231
21.4	Features of M4 . . . . .	232
21.4.1	Discarding input . . . . .	232
21.4.2	Macro management . . . . .	233
21.4.3	Conditionals . . . . .	234
21.4.4	Looping . . . . .	235
21.4.5	Diversions . . . . .	235
21.4.6	Including files . . . . .	235
21.5	Writing macros within the GNU Autotools framework . .	236
21.5.1	Syntactic conventions . . . . .	236
21.5.2	Debugging with M4 . . . . .	236

**22 Writing Portable Bourne Shell . . . . . 239**

22.1	Why Use the Bourne Shell? . . . . .	239
22.2	Implementation . . . . .	239
22.2.1	Size Limitations . . . . .	240
22.2.2	#! . . . . .	240
22.2.3	: . . . . .	241
22.2.4	() . . . . .	242
22.2.5	. . . . .	243
22.2.6	[ . . . . .	244
22.2.7	\$ . . . . .	246
22.2.8	* versus .* . . . . .	247
22.3	Environment . . . . .	248
22.4	Utilities . . . . .	249

<b>23</b>	<b>Writing New Macros for Autoconf.....</b>	<b>253</b>
23.1	Autoconf Preliminaries .....	253
23.2	Reusing Existing Macros.....	253
23.3	Guidelines for writing macros .....	254
23.3.1	Non-interactive behavior .....	254
23.3.2	Testing system features at application runtime .....	254
23.3.3	Output from macros .....	255
23.3.4	Naming macros.....	255
23.3.5	Macro interface.....	256
23.4	Implementation specifics .....	257
23.4.1	Writing shell code .....	257
23.4.2	Using M4 correctly .....	257
23.4.3	Caching results.....	258
23.5	Future directions for macro writers .....	258
23.5.1	Autoconf macro archive .....	258
23.5.2	Primitive macros to aid in building macros ....	259
<b>24</b>	<b>Migrating an Existing Package to GNU Autotools .....</b>	<b>261</b>
24.1	Why autconfiscate .....	261
24.2	Overview of the Two Approaches.....	261
24.3	Example: Quick And Dirty .....	262
24.4	Example: The Full Pull.....	264
<b>25</b>	<b>Using GNU Autotools with Cygnus Cygwin .....</b>	<b>267</b>
25.1	Preliminaries .....	267
25.2	Installing GNU Autotools on Cygwin.....	268
25.3	Writing A Cygwin Friendly Package .....	269
25.3.1	Text vs Binary Modes .....	270
25.3.2	File System Limitations.....	276
25.3.2.1	8.3 Filenames.....	276
25.3.2.2	Separators and Drive Letters.....	277
25.3.3	Executable Filename Extensions .....	279
25.4	DLLs with Libtool .....	280
25.4.1	DLL Support with GNU Autotools .....	281
25.4.2	A Makefile.am for DLLs.....	282
25.4.3	A configure.in for DLLs .....	283
25.4.4	Handling Data Exports from DLLs .....	285
25.4.5	Runtime Loading of DLLs.....	290
25.5	Package Installation .....	290

<b>26</b>	<b>Cross Compilation with GNU Autotools</b>	<b>293</b>
26.1	Host and Target	294
26.2	Specifying the Target	294
26.3	Using the Target Type	294
26.4	Building with a Cross Compiler	296
26.4.1	Canadian Cross Example	296
26.4.2	Canadian Cross Concepts	296
26.4.3	Build Cross Host Tools	297
26.4.4	Build and Host Options	297
26.4.5	Canadian Cross Tools	297
26.4.6	Supporting Building with a Cross Compiler	298
26.4.6.1	Supporting Building with a Cross Compiler in Configure Scripts	298
26.4.6.2	Supporting Building with a Cross Compiler in Makefiles	299
	<b>Appendices</b>	<b>301</b>
	<b>Appendix A Installing GNU Autotools</b>	<b>303</b>
A.1	Prerequisite tools	303
A.2	Downloading GNU Autotools	303
A.3	Installing the tools	304
	<b>Appendix B PLATFORMS</b>	<b>307</b>
	<b>Appendix C Generated File Dependencies</b>	<b>313</b>
C.1	aclocal	313
C.2	autoheader	314
C.3	automake and libtoolize	314
C.4	autoconf	315
C.5	configure	315
C.6	make	316
	<b>Appendix D Autoconf Macro Reference</b>	<b>317</b>
	<b>Appendix E OPL</b>	<b>327</b>
	<b>Index</b>	<b>331</b>